

GOVERNMENT OF INDIA
ARCHAEOLOGICAL SURVEY OF INDIA

CENTRAL
ARCHAEOLOGICAL
LIBRARY

ACCESSION NO 21625

CALL No. R 913.012/IDA/Bus

D.G.A. 79

~~12160~~



ARCHÆOLOGICAL SURVEY OF INDIA.

(NEW IMPERIAL SERIES.)

VOLUME XXXIII.

WESTERN INDIA

VOLUME VIII.


MUHAMMADAN ARCHITECTURE OF AHMADABAD.

PART II.



Price Thirty-one shillings and sixpence.





RANI RUPAWANTI'S MASJID IN MIRZAPUR, AHMADABAD.

ARCHÆOLOGICAL SURVEY OF WESTERN INDIA, VOL. VIII.

THE
MUHAMMADAN ARCHITECTURE

OF

AHMADABAD.

PART II.

WITH MUSLIM AND HINDU REMAINS IN THE VICINITY.

ILLUSTRATED BY 85 PHOTOGRAPHIC AND LITHOGRAPHED PLATES, &c.

BY

JAS. BURGESS, C.I.E., LL.D., F.R.S.E.,

HON. A.R.I.B.A.; HON. M. IMP. RUSS. ARCHÆOL. SOC., AMER. OR. SOC., AND GLASGOW PHIL. SOC.; F.R.G.S.;
M. SOC. AS. PARIS; M.R.A.S.; HON. COR. M. BERLIN SOC. ANTHROP. ETHN. ETC., AND BATAVIAN SOC. ARTS AND SC.
[LATE DIRECTOR-GENERAL OF THE ARCHÆOLOGICAL SURVEY OF INDIA.]

21625

Vol 33


R 913.012
IDA/Bur

LONDON:

BERNARD QUARITCH; KEGAN PAUL, TRENCH, TRÜBNER & Co.;
WILLIAM GRIGGS & SONS, LIMITED.

CALCUTTA: THACKER, SPINK & Co. BOMBAY: THACKER & Co., LIMITED.

1905.



Acc. No. 13.10.55
Date...

Date... 13.10.2013
Call No. 2913-012/I.D. A/Bur

PREFACE.

THE previous volume of the Architecture of Ahmadâbâd took account of the principal Muhammadan buildings erected there from the foundation of the city in A.D. 1412 to about 1520. There remained, however, several structures belonging to the latter portion of that period that were excluded from want of space, and these are taken up in the present volume, whilst the series is continued down into the eighteenth century. Thus, together with volume VI of the Western India Survey Reports, which dealt with the Muhammadan architecture of the districts outside Ahmadâbâd, this may be regarded as completing the survey of the Gujarât style of Muslim Architecture, and the three volumes together as forming a monograph on the subject. This volume has accordingly been supplied with an index to the three.

But as the Muhammadan remains at Ahmadâbâd are so very numerous, it is only a selection of them that could be surveyed and delineated in any detail; to supply some idea, however, of those that have been passed over, short descriptive accounts have been given in chapters XV and XVI of those within the city and in the suburbs respectively. These accounts or notes are based on the returns prepared for the Collector in 1886 by the Deputy-Collector, Mr. J. F. Fernandez, supplemented by personal observation and from the Lists of Remains prepared by me in 1884-5.

With this survey it was necessary to include the step-well or Wāv of Bâi Harir, constructed under Muhammadan supervision, but entirely Hindû in execution, and with it both the adjoining early Hindû well of Mâtâ Bhavâni, and the sister well to Bâi Harir's at Adâlaj; and with these the ~~old~~ ^{new} Jain temple of Śeṭh Hathisingh together with a slight ~~notice of the other temples~~ ^{of the other temples} in the city belonging to the Śrâvak sect. Further,—surveys were also made in the surrounding districts—at Viramgâm, Mândal, Kapadvâñj, and Sarnal—of remains, both Muhammadan and Hindû, and some account of these has been added so as to include the whole of the materials collected.

The drawings, as in previous volumes, were mostly prepared under the supervision of Mr. Henry Cousens, to whom was largely entrusted the details of the survey after 1886; and to him are also due nearly all the photographs used. In such a publication the illustrations are a most important feature of the work;

and, whether in plans or decorative details, these represent with architectural accuracy the monuments described in the text.

The ornamental details are so beautiful and interesting that it may be regretted that several of them are not reproduced to larger scales; but financial considerations interposed in this, in the arrangement of some of the details, and in the reproducing of more of the illustrative photographs made for the survey.

In the preparation of the text I have received valuable assistance from Rev. Geo. P. Taylor of Almadâbâd, and through him from the late Mûsâ Miyân, the representative of the descendants of Shah 'Alam, and from Sayyid Fakrud-din Abubakr al Edrûs, Huzûr Deputy Collector: to these my special thanks are due.

This volume completes, I believe, my work for the Government of India.

Edinburgh, February 1905.

ERRATA IN PART I.

- P. 2, l. 24, *for Nasiru'd din read Nasrat Khân.*
 P. 2, l. 29, *for Muhammad Tughlaq II read Mahmûd Shâh II of the Toghlaqi dynasty.*
 P. 2, l. 32, *for Muhammad Shâh read Mahmûd Shâh.*
 P. 7, l. 6, and p. 8, No. 13, *for Muhammad III read Mahmûd III.*
 P. 8, last line, *for imposter read impostor.*
 P. 14, under woodcut, *for VIMALA Śâh read TEJAPĀLA VASTUPĀLA.*
-



THE MATA BHAVANI WAV AT ASARWA, AHMADABAD.

CONTENTS.

CHAPTER I.	
Mâtâ Bhavâni's step-well at Asârwa	Page 1
CHAPTER II.	
Bâi Harîr's Wâv or step-well,—its date, cost and structure. Her Mosque and Tomb	4
CHAPTER III.	
The 'Adâlahj wâv or step-well; its structure; the Navagraha represented; inscription and date; dimensions. Other step-wells in Gujarât; at Uvârsad; at Îsanpur;—its dimensions, &c; Jijî Bâbâ Râpi's well	10
CHAPTER IV.	
Shâh 'Âlam: the genealogy of the Bukhârîah Sayyids; Muḥammad Shâh 'Âlam; his tomb at Rasûlâbâd; the endowments of the buildings squandered; Government action; area of the buildings; the dargâh of Shâh 'Âlam; others interred in it; tomb of Maqbûl 'Âlam and qadam-i rasûl; Mir Abû Turâb and his qadam-i rasûl; other graves in Maqbûl 'Âlam's tomb; tombs in the enclosure; the Masjid;—dimensions and style; the tank; the Diwan Khâna—its history; the gateways; endowments and 'urs	15
CHAPTER V.	
Sidi Bashîr's mosque. Minârs at the Railway Station. Darvesh 'Alî's or Ojâ Bîbi's masjid and rauza; the reservoir or tânka	24
CHAPTER VI.	
Sârangpur mosque of Kiwâmu'l Mulk Sârang; Malik Sârang's career; the minârs of the masjid taken down; arrangements of the masjid; the tomb	28
CHAPTER VII.	
Râpi Rupâvañi's Masjid in Mirzapur; date and dimensions; style; the adjoining tomb; area and alienations	32
CHAPTER VIII.	
Faṭh Masjid in Daryâpur quarter; condition. Three other trabeate mosques: Gumti masjid at Îsanpur; Pâldi Kochrab mosque and Bâwâ Faizullah's; Ibrâhîm Sayyid's mosque and rauza in Kaṅgalpuri	36
CHAPTER IX.	
Îsanpur mosque and rauza of 'Imâd al Mulk Malik Îsan; situation; plan and details. Shâh 'Alîjî Kûmdhani's masjid and rauza in Râyakhâd Robilawâd. Alîf Khân's or Bâbi masjid and tomb. Shâh Ghazni Masjid	40

CONTENTS.

CHAPTER X.

Shâhpur masjid of Shaikh Hasan Muhammad Chishtî; position and dimensions; façade and minarets. Bâbâ Lulûi or Bâbâ Muhammad Ja'far's masjid; age; plan	Page - - - - - 44
---	----------------------

CHAPTER XI.

Mosque of Muhammad Ghaus in Sârangpur quarter; style; alterations of façade. Tomb of Abû Turâb; his career; his qadam-i-rasûl; the tomb at Berhampur	- - - - - 48
--	--------------

CHAPTER XII.

Rauza of Wajih-ad-dîn; age and style. 'Alî Khân's or Chhota Idrus Masjid. Masjid and rauza of Nawâb Sardâr Khân; extent of the buildings; area	- - - - - 53
--	--------------

CHAPTER XIII.

Shâh-i-Bâgh; built by Shâh Jahân: Mandelslo's account of it; Jas. Forbes's description; the structure; alterations; 'Azam Khân's Palace, now the Jail; changes of use; the building; Mandelslo's visit	- - - - - 57
--	--------------

CHAPTER XIV.

Mosque and Tomb of Shujâ'at Khan—Kârtalâb Khân: Shujâ'at Khan's career; his masjid—its style and size: the rauza. The Hilâyat Bakhsh madrasa and City Qâzi's mosque	- - - - - 61
---	--------------

CHAPTER XV.

Other Mosques and Tombs: 1, Ganj 'Inâyat Shâh's mosque; 2, Champâ-ki Masjid in Shâhpur; 3, Kharâti Masjid; 4, Bâdshâh Sayyid's Masjid; 5, Mira Sayyid 'Alî's Masjid; 6, Miyân Muhammad Husain's masjid; 7, Hâjî Sâkbi's masjid; 8, 'Abdullâ Razzâq's rauza and mosque; 9, Pir-i Dastgir's masjid and rauza; 10, Pir Vazirshâh's masjid and rauza; 11, Shâh 'Abdul Fa'ha's masjid; 12, Shâh 'Abdul Wâhhâb's masjid and rauza; 13, Nawâb Shâhjahân Khân's and Momia Khân's masjid; 14, Muhammad Sayyid's mosque; 15, Shaikh Muhammad Jahid's mosque and tomb; 16, Rauza of Sayyid Abdullâ Idrus; 17, Husain Sayyid's masjid; 18, Asraf Khân's masjid and Badâ Miyân's burial place; 19, Pirmâl Shâh's mosque and rauza; 20, Shaikh Muhammad Chishtî's rauza; 21, Bâwâ Ahmad's masjid; 22, 'Alîf Murtaza's masjid; 23, Râo Magdâlik's tomb; 24, Galiyârâ's masjid and Pir Kamâl's graveyard; 25, 'Âlam Khân's rauza; 26, Rauza near the Râyakhad Gate; 27, Sayyid Muhammad Ja'far and Sarâzi Sâheb's Rampas; 28, Qâzi Sâheb's Masjid; 29, Sayyid Ja'far's Masjid; 30, Shâh Muhammad 'Alî's Masjid; 31, Mustafâ Sayyid's Masjid; 32, Pir Qutb-ad dîn Sayyid's Rauza; 33, Makhdûm Sâheb's Masjid, &c.; 34, Shâh Badâ Qâsim's Rauza; 35, Kâchhi Masjid; 36, Pirânpir's Dargâh; 37, Khân Jahân's Masjid	- - - - - 64
--	--------------

CHAPTER XVI.

Muhammadian Mosques and Tombs in the Suburbs, &c.: 1, Tombs of 'Azam and Mu'ayyaz Khân; 2, Rauza of Qâsim Khân; 3, Mûsâ Suhâg's Mosque and Rauza; 4, The Badâmi Mosque; 5, Mosque and Rauza of Bâwâ Bârakalla Chishtî and others; 6, Two Tombs opposite Daryâ Khân's; 7, Shâh Badshâh Pir's Rauza; 8, Char Tolâ Qabrastân; 9, Pir Qâsim Khân's Rauza; 10, Pir Bâqir Shâh's Rauza; 11, Pir Mashâyek's Rauza; 12, Shâh Mahbûb Majnah's Rauza; 13, Afzal Khân Bombani's Mosque; 14, Bibîji's Mosque in Râjapur Hirpur; 15, Mosque and Tomb of Mariam Bibî; 16, Muhammad Anwar Khân Bâbî's Rauza; 17, Nenpurwâdâ Masjid; 18, Rakhyal Small Mosque; 19, Ganj Shâhoda's Rauza	- - - - - 78
---	--------------

CHAPTER XVII.

Hindû Anmadâbâd: The ancient city; old sculptures excavated; Jaina temples in the city; the great Jaina temple of Seth Hathisingh; its design; description. Hindu temples; Svâmi Nârâyana's	- - - - - 84
---	--------------

CONTENTS.

ix

CHAPTER XVIII.

	Page
Virangām and Māndal, Kapaḍvanj and Sarnal. The Mānasarovar at Virangām. Māndal mosques : Jāmi' masjid ; Sayyidi masjid ; Pāliyus. Kapadvanj : Jāmi' masjid ; the Kaṇḍa ; Kirtistambha. Sarnal : temple of Gaṭeśvara - - - - -	91
Plates XIII. to LXXXV. - - - - -	After p. 96
INDEX - - - - -	97

LIST OF PLATES.

PLATE			
I.	Rāṇi Rupāvati Masjid in Mirzāpur (<i>collotype</i>)	- - - - -	to face Title.
II.	The Mātā Bhavānī Wāv at Asārwa	" - - - - -	to face page 1
III.	Bāi Harir's Well : 1, View of the Wāv from the entrance platform looking west ; 2, View across the main shaft looking east (<i>collotypes</i>)	" - - - - -	4
IV.	Masjid of Bāi Harir at Asārwa (<i>collotype</i>)	- - - - -	6
V.	Rauza of Bāi Harir at Asārwa	" - - - - -	8
VI.	Adālaḥ Wāv : 1, the Wāv from the north platform ; 2, across the octagonal well (<i>collotypes</i>)	- - - - -	10
VII.	1, Tomb of Shāh 'Ālam, west front. 2, Masjid and court at Shāh 'Ālam (<i>collotypes</i>)	- - - - -	15
VIII.	Sārangpur Mosque (<i>collotype</i>)	- - - - -	28
IX.	Tomb at Rāṇi Rupāvati Mosque in Mirzāpur (<i>collotype</i>)	- - - - -	34
X.	Faṭhe Masjid (<i>collotype</i>)	- - - - -	36
XI.	'Īsanpur Masjid	" - - - - -	40
XII.	Mosque of Muḥammad Ghaus (<i>collotype</i>)	- - - - -	48

After page 96 :—

XIII.	Mātā Bhavānī's Wāv at Asārwa.
XIV.	Mātā Bhavānī's Wāv and Bāi Harir's Wāv and Tomb :—1, Screen from Mātā Bhavānī's Wāv ; 2, pillar ; 3, Bāi Harir's wāv—sculptured niche ; 4, Bāi Harir's Tomb—window under the dome.
XV.	Bāi Harir's wāv at Asārwa : 1, section of east portion ; 2, plan.
XVI.	Bāi Harir's wāv ; section of west portion.
XVII.	Mosque and Tomb of Bāi Harir at Asārwa : 1, plan ; 2, antefixa on cornice of the tomb ; 3, pendant in dome ; 4, drip of cornice of the tomb.
XVIII.	Bāi Harir's Well and Mosque : 1, 2, niches in the wāv ; 3, niche in the Mosque ; 4 6, Plan, elevation and section of north mihrāb.
XIX.	Bāi Harir's Masjid : cross section.
XX.	Bāi Harir's Tomb : 1, elevation, south face ; 2, screen at the corner of the verandah in S. face E. end.
XXI.	Bāi Harir's Mosque and Tomb : 1, small dome in corner of the verandah of the tomb ; 2, pillar, &c., of the tomb ; 3, niches in minaret of the mosque.
XXII.	The Wāv at Adālaḥ : Plan, section, rail-pattern, niche and pillar (<i>double plate</i>).
XXIII.	Jatḥabbāi Mulji's Wāv at 'Īsanpur : 1, section : upper portion ; 2, section through the reservoir and draw-well shafts ; 3, plan.
XXIV.	Tomb of Shāh 'Ālam, with surrounding buildings (<i>double plate</i>).
XXV.	Shāh 'Ālam : inner door of the tomb.
XXVI.	" " : 1, outer gateway ; 2, inner corridor of the mausoleum on the west side, from the south (<i>collotypes</i>).
XXVII.	" " : Perforated window in the tomb. Sidi Bashir's masjid—one of the minārs.
XXVIII.	" " : 1, Perforated stone window ; 2, Tomb at Darvesh 'Alī's Mosque ; 3, Minār at Shāh 'Alī's Mosque.

PLATE	XXIX.	Darvesh 'Alī's Mosque and Dargāh : 1, Plan of Mosque and tomb ; 2, Half elevation and section of the Masjid.
"	XXX.	Darvesh 'Alī's Mosque : 1, Window ; 2, Battress ; 3, 4, Panels from Adāraj Wāv.
"	XXXI.	Sārangpur Masjid and Tomb : plan.
"	XXXII.	" " : 1, cross section ; 2, 3, two windows from inside.
"	XXXIII.	" " : Four panels from the minars.
"	XXXIV.	" " : Mihrāb—elevation, section, plan.
"	XXXV.	" " : Windows—1, second window from north corner ; 2, second window from south corner ; 3, on south front ; 4, on north front.
"	XXXVI.	" " : 1, Entrance to the stair ; 2, side elevation of minar ; 3, Mirzāpur Masjid minār.
"	XXXVII.	Rānī Rupāvati Masjid in Mirzāpur : 1, Plan ; 2, front pillar under the central dome.
"	XXXVIII.	" " : Windows in north half of the façade ; 2, the central Mihrāb.
"	XXXIX.	" " : 1, 2, Roof panel—plan and section ; 3, 4, Niches from the minars.
"	XL.	Fatḥ Masjid : Elevation—south end of the façade ; 2, plan.
"	XLI.	Small Masjid at Īsanpur : Front elevation ; plan.
"	XLII.	Bāwā 'Alishāh's Masjid at Kochrab : 1, Elevation ; 2, pillar. 3, Ibrāhīm Sayyid's Masjid near Shāh 'Ālam—Elevation.
"	XLIII.	The small Masjid at Īsanpur : 1, elevation ; 2, plan.
"	XLIV.	1, Niche from Ibrāhīm Sayyid's Masjid, south side of south minār ; 2, niche from south minār of Mirzāpur masjid ; 3, 4, Niches in the walls of 'Alī Khān Qāzī's Masjid.
"	XLV.	Shāikh Ḥasan Muḥammad Chishtī's Masjid in Shāhpur (<i>collotype</i>).
"	XLVI.	" " " " Plan.
"	XLVII.	" " Figs. 1-4. Four panels from the minarets.
"	XLVIII.	" " : " 5-8. " " "
"	XLIX.	'Alī Khān's Masjid : 1-3, Mihrāb—elevation, plan and section ; 4, Mosque of Muḥammad Ghauṣ, plan ; 5, Plan of the tomb of Abū Turāb.
"	L.	Interior of the Mosque of Muḥammad Ghauṣ (<i>collotype</i>).
"	LI.	Mosque of Muḥammad Ghauṣ : Mihrāb—elevation, plan and section ; transverse section of the mosque.
"	LII.	Vajīb-ad-dīn's Tomb (<i>collotype</i>).
"	LIII.	Shāh-i-Bāgh (<i>collotype</i>).
"	LIV.	Masjid of Bābā Lulū (<i>collotype</i>).
"	LV.	Bābā Lulū's Masjid : 1, plan ; 2, niche in minaret. 3, Perforated marble window in Pir Muḥammad's masjid.
"	LVI.	Bābā Lulū's Mosque : elevation.
"	LVII.	Palace of Āzam Khān—now the Jail (<i>collotype</i>).
"	LVIII.	" " " : Upper floor ; section of part of upper floor ; ground floor.
"	LIX.	1, 'Alī Qāzī's or Nānhā Idrus Masjid—Plan. 2, Plan of the Rauḍa of Nānhā Idrus ; 3, elevation.
"	LX.	Nawāb Sardār Khān's Masjid (<i>collotype</i>).
"	LXI.	" " " Tomb "
"	LXII.	Masjid of Nawāb Shujā'at Khān "
"	LXIII.	" and tomb of Nawāb Shujā'at Khān : plan.
"	LXIV.	Hidāyat Bakhsh Madrasa Masjid (<i>collotype</i>).
"	LXV.	Mosque at Hidāyat Bakhsh Madrasa : plan.
"	LXVI.	Elevation of Bibijī's Masjid at Rājapur Hirpur (<i>double plate</i>).
"	LXVII.	Old Hindū Sculptures : figs. 1-8.
"	LXVIII.	" " " : figs. 9-18.
"	LXIX.	Jaina Temple of Śeṭh Hathisingh, from the south-west (<i>collotype</i>).
"	LXX.	" " " " plan.
"	LXXI.	" " " " from the north-east (<i>collotype</i>).
"	LXXII.	Plan of the Mānasarovar at Viramgām.

PLATE	LXXIII.	Plans and elevations of small shrines on the margin of the Mânasarovar ; 1, double temple ; 2, single shrine ; 3, 4, front and side elevations of a single shrine.
„	LXXIV.	Virangâm Mânasarovar : 1, View along south side, looking west ; 2, East end, looking north (<i>collotypes</i>).
„	LXXV.	Mândal : Jami' Masjid—plan ; 2, Sayyidi Masjid, elevation of back wall ; 3, 4, Memorial and Sati Stones.
„	LXXVI.	„ 1, Sayyidi Masjid ; 2, Jami' Masjid (<i>collotypes</i>).
„	LXXVII.	„ Sayyidi Masjid—1, plan ; 2, cornice and kaṅgaras in elevation and section ; 3-5, mihrâb, elevation, plan and section ; 6, pillar.
„	LXXVIII.	Kapaḍvanj : Jami' Masjid ; 1, plan ; 2-3, Dome in plan and section.
„	LXXIX.	„ : 1, 2, pillars in Jami' Masjid ; 3, window in Jami' Masjid ; 4, small Pavilion at the tank.
„	LXXX.	„ : Plan of old Tank or well in the market-place.
„	LXXXI.	„ : Section of old tank well.
„	LXXXII.	„ : Kîrti-Stambh at the tank.
„	LXXXIII.	„ : Modern carved window and bracket.
„	LXXXIV.	Hindû Temple of Galtesvara at Sarnal : plan.
„	LXXXV.	Galtesvara Temple : 1-3, Doorway of the shrine in elevation, plan and section ; 4, pillar in the maḍḍapa.

ILLUSTRATIONS IN THE TEXT.

1.	A Minaret of Bâi Ḥarîr's mosque, about 1870	-	-	-	-	-	-	Page 7
2.	The Nava Graha or nine planets in Adâlaḥ Wâv	-	-	-	-	-	-	11
3.	The two lofty minârs at the Railway station	-	-	-	-	-	-	25
4.	North minaret of the Sârangpur masjid, about 1870	-	-	-	-	-	-	29
5.	The Mosque at Pâlḍi Kochrab, from the south-west	-	-	-	-	-	-	38
6.	Upper portion of the façade of the masjid of Muḥammad Ghaus about 1870	-	-	-	-	-	-	49
7.	The Dargâh of Sayyid Abû Turâb, from a photograph	-	-	-	-	-	-	51
8.	The Ranza of Sayyid al 'Idrûs	-	-	-	-	-	-	69
9.	Modern Bird-roost, Ahmadâbâd	-	-	-	-	-	-	76
10.	Eighteenth-century tombs to the north of the city	-	-	-	-	-	-	80



THE
ARCHÆOLOGICAL SURVEY OF WESTERN INDIA.

ARCHITECTURE

OF

AHMADABAD.

PART II.

CHAPTER I.

MATA BHAVANI'S STEP-WELL.

PLATES II, XIII AND XIV.

IN the previous volume on the Architecture of Ahmadâbâd, the principal features of the Muhammadan buildings in that city were traced from the date when it became the capital of the Ahmad Shâhi dynasty early in the fifteenth century, down to about a century later. In that review, however, some monuments that belong to the end of this period were passed over, from considerations of space and grouping, which may now be taken up as preliminary to the account of the architecture of the city and surrounding district during the subsequent sixteenth and seventeenth centuries.

First among the earlier buildings stands the old Hindû step-well at Asâr-wâ, known as Mâtâ Bhavânî's, about three-quarters of a mile outside Ahmadâbâd to the north-east, and three hundred yards to the north of the later Muhammadan well, known as Dâdâ, or Bâi Harîr's Wâv, in connection] with which it may be most conveniently treated.

A Wâv or bauli is a large structure, picturesque and stately as well as peculiar in design, but eminently suited to the habits of the Hindûs. It consists of two parts:—a well, circular or octagonal, from which the water is drawn up for irrigation, in skins, by the help of bullocks, the draw-ropes passing over rollers fixed on the upper edge of the shaft; and secondly, a series of galleries or floors, connected by flights of steps descending successively from the uppermost platform to a lower

landing on which stand pillars supporting a roof of equal breadth above. A second flight of steps continues the descent to a still lower landing, over which are two storeys. In this way the descent continues stage by stage till the water level is reached; and this level may vary with the season. This second portion ends in the cistern or reservoir, which connects with the draw-well. Round the shaft of this reservoir are platforms in each storey, protected by parapets surrounding the octagonal shaft—their backs forming seats for loungers. To these platforms round the shaft descend spiral stairs constructed in the side walls of the wâv.

The Hindû well at Asâr-wâ (Plate II) takes the name of Mâtâ Bhavâni's from a small shrine, formed in the back of the circular shaft of the draw-well at the west end, just above the water level, and appropriated to that mother-goddess, the Śaktî of Śiva, and, as a goddess of production, usually identified with Pârvatî. This epithet for the wâv, however, has no certain claim to antiquity, though the well evidently belongs to the pre-Muhammadian period and probably goes back to the eleventh century. Nor does the small shrine of Bhavâni appear to be original—indeed it is probably of quite recent date. It is built on to the circular wall of the shaft and supported by cross-beams upon brackets. A Gosain or devotee closed in the space on the middle landing, between three of the pillars and the wall, as a residence, where he collected some detached figures of Durgâ, Gaṇapati, &c., and obtained a living from the people.

If Aḥmadâbâd really occupies the site of the earlier Karṇâvatî, as is reasonably supposed, then this wâv may probably belong to the reign of Karṇa Solankî (1063–1093 A.D.) the reputed founder of Karṇâvatî.

Compared with the later wells of Dâdâ or Bâi Harir close by, and that at Adâlaĵ to the north of Aḥmadâbâd, it is inferior in plan, but is interesting as one of the earliest of the kind that has survived to our times.

The circular shaft of the draw-well is 16 feet in diameter and is connected by a neck about 6 feet wide with the cistern of the well, which is some 31 feet in length by 16 in width (Plate XIII). The platform immediately in front of this is 17 feet across, under a roof supported on six pillars, and is approached by a stair leading down from the gallery above, where is also another platform on which stand six pillars supporting the roof over it again; and to this the upper stair leads down. These stairs are not well arranged,—for, the ascent being too great for the space allowed, each series of steps is broken about the middle, and short steps inserted at right angles to the line of descent. These somewhat obstruct the approach; but, at the same time they provide resting places, where the women can more easily set down their water-pots and again lift them on to their heads.

Rising above the ground level, over each landing platform in the descent, is a canopy supported by nine pillars (Plate II). These *chhatris* or canopies have projecting eaves and form an additional storey above each platform. The pillars throughout the work are very plain, having square bases and lower shafts, changing first to octagonal and then to circular, with bracket capitals (Plate XIV, fig. 2). At the corners of the roofs of these canopies are conventional lions, and in the middle of each side there were figures of secondary Hindû divinities, now partly destroyed.

The frieze forming the face of the side parapets or screen walls of the canopies is carved in that old style which is found so often on the walls of Hindû and Jaina temples of the tenth and later centuries—and derived from the Buddhist rail-pattern of earlier times. This is illustrated in the photograph, Plate II, and on Plate XIV, fig. 1.

The interest of this old wâv consists largely in its being almost the last remaining example of purely Hindû times, and in having supplied the pattern for the similar structures of a much later period under Muhammadan rule. We may easily trace this in their arrangements, as in that of the neighbouring one of full four centuries later date.

CHAPTER II.

BAI HARIR'S WÂV, MOSQUE AND TOMB.

PLATES III, XIV-XVI, AND XVIII.

THE second Wâv at Asâr-wâ is known as Dâdâ Harîr's or Bâi Harîr's wâv (Plate III.) It was constructed at the expense of a certain lady, who is described in a Sanskrit inscription placed in the first gallery, on the south or left side of the descent, as Bâi Śrî Harîra, "the chief superintendent at the entrance of the royal apartments (or ḥarîm), the illustrious and pious lady Śrî Harîra, the chief adviser of the king Maḥmûd." This epigraph is dated on Monday 13th Pausa-sudi, Samvat 1556, and Śaka 1421: which would correspond to 15th December 1499 A.D. but that day fell on a Sunday, though 13th Pausa-vadi fell on Monday, 30th December, 1499.¹ Again, on a marble slab in the north wall, is another inscription, in Arabic, which speaks of "this splendid building, enclosed by walls with carved ornaments and a plantation of fruit-bearing trees," as constructed "during the reign of Nâṣir-ad-dunya wa'd-din Abu'l Faṭḥ Maḥmûd Shâh, son of Muḥammad Shâh, son of Aḥmad Shâh, &c., by Śrî Bâi Harîr Sultâni, whom his august majesty made the chief attendant at the door of the guarded entrance (ḥarîm). On the 8th Jumâda I, 906 A.H.," or Monday, 30th November 1500 A.D., that is, a year later than the date in the other inscription.²

The cost of the structure, as stated in the Sanskrit inscription, was 329,000 of some unspecified coin, most probably however, the *maḥmûdî*—being the coin of the reign, and which was valued at about 27 *maḥmûdîs* to 13 rupees:³ whence this expenditure would amount to about 158,400 rupees.

This well and the one at Adâlaġ, twelve miles to the north of Ahmadâbâd, which was also built about the same time, are by far the finest now left in Gujarât,—the second being somewhat the larger. Bâi Harîr's, from the front of the ascent to the pavilion at the entrance on the east end, to the west side of the shaft of the draw-well, measures over all 241½ feet; and from the first step of the descent towards the well to the same point, 215½ feet. The width of the platforms in the galleries is 16 feet 1½ inch, and of the stairs nearly 18½ feet.⁴ But round the octagonal shaft, near the west end, it widens into a square of 24 feet (Plates XV and XVI).

¹ *Epigraphia Indica*, vol. IV, pp. 297-300, and vol. V, app. No. 300.


² Under the last syllables of the Arabic inscription are the figures "26"; this cannot be the regnal year, for that was in A.H. 889. The date in this inscription has sometimes been misread; the version given here was kindly supplied by Sir Charles J. Lyall, and confirms that of Mr. Briggs, *Cities of Gujarashtra*, p. 218.

³ Wicquefort, *Suite de la Relat. du Voyage d'Adam Olearius*, (vol. II), p. 232; Briggs, *Cities of Gujarashtra*, p. 218. A *maḥmûdî* was thus equal to 7 ānās, 8½ paṇas, or a hundred rupees would be about equal to 208 *maḥmûdîs*, and 100 *maḥmûdîs* to 48 rupees.

⁴ In the *Bombay Gazetteer*, vol. IV, p. 282, the date of the inscriptions is erroneously given as 1485 A.D., the cost at 3,00,000 rupees, and the dimensions (taken from Briggs) as 196 feet in length by 40 feet wide. Conf. Forbes, *Oriental Memoirs*, vol. III, p. 140.



1. VIEW OF THE WAY FROM THE ENTRANCE PLATFORM,
LOOKING WEST.



2. VIEW ACROSS THE MAIN SHAFT, LOOKING EAST.

At the east end, the well is approached from a pavilion, 14 feet 9 inches square inside, covered by a dome which is supported by twelve pillars, standing on a platform raised fully 6 feet above the ground-level and reached by steps on the three outer sides. From the west side of this the stair leads down to the well, having one broad step in the middle of the descent, and lands 11 feet below, on the platform in the first gallery. This platform is 19 feet broad and is covered by a roof supported on eight pillars standing on it with corresponding pilasters against the walls. Again a second flight of steps leads down to the floor of the second gallery, on a platform 9 feet broad with four pillars supporting the roof. From this, a third stair leads down into the lower gallery, at a depth of 32 feet 9 inches—having three tiers of roofs over it on the levels of the different platforms (Plates XV and XVI). Unlike Mâtâ Bhavâni's, the storeys over the platforms do not rise as pavilions above the sides of the wâv (Plate III, 1).

Usually the water stands well up in the third gallery, the fourth being always submerged. Hence the depths—beyond about 25 feet—can only be found by the plummet, and the floor of the fourth gallery must be covered with mud and debris to some depth: the soundings give from 38 to 40 feet below the level of the entrance pavilion, but it may be two or even three feet lower. The fourth is the lowest of the galleries, and its platform is carried forward to the octagonal well—a length of over 50 feet. After the third gallery is reached and the depth exceeds 30 feet, the side walls require more support, and the builders, well aware of this, divided the next opening, over the stair leading down from the third gallery, into two, by lintels 4 feet broad, in each storey, supported by two pairs of coupled shafts; and again, after another roof of about 19 feet in length standing on eight pillars, a second shaft follows, similarly divided by lintels in each storey. By this structural arrangement the side thrusts of the walls were effectively met and overcome.

The octagonal well (Plates III, 2, XV, 2 and XVI) is an open shaft 14 feet 9 inches across, with low parapet walls 2 feet high round it on each floor and at the top. The faces of these parapets towards the shaft are elaborately carved in tracery of purely Hindû pattern, though without figure sculpture. The whole width of the structure here forms a square of 24 feet, allowing a passage quite round the shaft,—the pillars being arranged as they would be to support a dome, that is, in a square of twelve so disposed that eight form a regular octagon. In the side walls of this area are spiral staircases by which access is found from above to the platforms in the different storeys,—the entries above being under two small square canopies or *chhatris* above the ground level.

Between the main shaft, which is over 46 feet in depth, and the circular draw-well at the west end, there are also platforms in each gallery, the sections next to the latter being about 5 feet 4 inches wide and having a seat with its sloping back towards the shaft. Here, and round the main shaft, loungers could enjoy a cool retreat during the hottest hours of the day.

The coping of the side walls is carved on the lower margin after the same pattern as at Mâtâ Bhavâni's, and the friezes round the octagonal shaft are only a little richer in detail than those over the gallery fronts in that earlier work. The

latter has also string courses introduced at intervals on the wall faces after the manner in which they are employed to decorate the walls of mosques (Plate III, 2). In line with the floors of the upper galleries are ledges projecting about a foot from the side walls and supported on the under side by carved brackets: these run round the circular shaft also (Plate XVI).

In the walls of the first gallery, between the pilasters, are three niches or panels on each side; the central ones contain the inscriptions already mentioned, and the others are filled with tracery in the florid style of the similar niches in the minarets of the mosques, but these have higher pediments. Other niches, similarly carved, recur in the galleries over the second and third landings, in the side walls of the gallery round the main shaft, and one in the end shaft at the level of the second gallery (Plate XVI). Of these examples—two from the lower and one from the upper galleries—are given on Plate XIV, fig. 3, and Plate XVIII, figs. 1, 2, one of them presenting the purely Hindû decoration of conventionalized peacocks and snakes and the others showing patterns more like those employed in windows than what are usual in the niches of minarets.¹

The whole work is admirably conceived for its purpose, and the structural execution is carefully planned to meet the thrusts of the side walls, whilst the ornamental sculpture is rich and tastefully applied.

The well at the west extremity is worked by one of the Gosvâmi Mahârâjas of the notorious Vallabhâchârya sect, for the irrigation of his land adjoining on the north of the wâv, the water being raised in the usual way—in a skin which is drawn up by bullocks by means of ropes passing over an axle. The arrangements for this are supported by masonry raised over brackets in the wall of the shaft.

The adjoining land, measuring about $5\frac{1}{2}$ acres of which $4\frac{3}{4}$ acres are cultivated, is held by the Gosvâmi as *jat* or personal *in'âm*, and was granted to a predecessor, in November 1833, in exchange for ground previously belonging to him in the village of Vejalpur, lying to the west of Ahmadâbâd, which was then required by Government for the erection of butts for artillery practice.²

About twenty-five years ago, Government spent a thousand rupees on repairs to this well.

THE MOSQUE AND TOMB.

PLATES IV, V, XIV, 4, AND XVII-XXI.

At Asârwâ, Bâi Harîr is said to have founded a suburb that went by the name of Harîrpûra; and to the west of the well are a mosque and tomb or *rauza* that still preserve her name. In 1847 when Mr. Henry G. Briggs visited the latter, he found the tombs inside destroyed—apparently by the Gosvâmi's people, whose encroachments, however, were stopped through the interference of the Qâzî.

¹ In the *Journal of Indian Art and Industry*, vol. VI, Oct. 1895, on plates 79-81, are given some more details of these niches.

² Briggs, *Cities of Gujarashtra*, p. 219; Crawley-Boevey, *Scheme for the protection and conservation of antient buildings at Ahmedabad* (1886), app. p. lxxv.



MASJID OF BAI HARIR AT ASARWA.

The plan of this mosque (Plate XVII) is a simplification of those of Bibi Achut Kūkī and Miyān Khān Chishtī,—the width of the building being in this case restricted to the diameter of the domes—or 15 feet; but in length it has five domes, each with its corresponding *qibla* or *mihrāb* in the west wall. Over the walls the building measures $20\frac{1}{2}$ feet deep by $87\frac{1}{2}$ in length, and the pillars supporting the domes are arranged in pairs. A comparison of the plans of the mosques just mentioned¹ shows that the stairs leading up behind the minarets were managed in the same way in all three; the design of the façade bears analogy to that of the Rājapur Masjid as well as to that of Miyān Khān Chishtī's; the turrets, though plainer in the octagonal portions, are treated somewhat like those of Bibi Achut Kūkī's; and the resemblances in the details of the three mosques, sufficiently confirm the tradition that this one belongs also to the end of the fifteenth century or the beginning of the sixteenth. And among those of that period it is deserving a place, which—owing to its locality and its neglected treatment during the last fifty years—has not hitherto been assigned to it.²



1. MINARET ON BAI HARIR'S MOSQUE.³

Unfortunately, about thirty years ago, the south minaret had become unsafe and was taken down by the Public Works Department, but no attempt was subsequently made to rebuild it, and, as in the case of other mosques similarly treated, the stones were still lying in front of the mosque at the time of the survey. The accompanying illustration (No. 1), from a photograph taken about 1870, shows a large portion of the south minaret as it then was. What is still left of these minarets is richly carved from the ground up to $2\frac{1}{2}$ feet above the front of the side wings, or to $18\frac{3}{4}$ feet from the ground (Plates IV and XIX). Above this they were octagonal and plain, except for a string-course at the head of the front screen wall or central section of the façade, which rises about 10 feet higher than the wings,

¹ See *Ahmadābād*, Part I, Plates lxxvii and lxxxvii.

² Except by Briggs, in his *Cities of Gujarashtra*, this mosque and tomb had scarcely been noticed; Colonel Biggs took no photograph of it, so that it was not referred to in Hope and Fergusson's *Ahmedabad* (1866). After the survey, some students from the Bombay School of Art were sent in 1893 to make drawings, which were published in the *Journal of Indian Art and Industry*, vol. VI (1895), where the north end wing of the mosque is represented, on Plates 74 and 75, with a wall on the south side, as if it were the whole structure, and even the buttress behind the *Mihrāb* is omitted both in plan and section.

³ From Capt. Lyon's photograph. The minaret was then entire though shaken. Whether any drawing was made before demolishing the minarets here and elsewhere in Ahmadābād, so as to provide for their correct restoration, is not known. The oldest mosque—that of Ahmad Shāh in the Bhadr— and others were similarly deprived of their turrets, and the stones long left lying about instead of being replaced whilst each course of the original masonry was still known.

and extends to a length of 40 feet. At this height the minarets had projecting mouldings, supported on small brackets, and with imitation antefixa carved in relief on the octagonal shaft, which rose another storey above this and was crowned by a carved projecting balcony supported on brackets. A short section above this again was circular and upheld a second balcony for the mu'azzan, who came out from a door on this balcony:—it was the three upper storeys that were taken down. The lower portions of the minarets are very elaborately carved in the usual style, and the two front niches in the south minâr are represented on Plate XXI, fig. 3, and another panel from the side on Plate XVIII, fig. 3.

The building has been long uncared for and roughly handled; the entrances to the wings have mostly been bricked up, and the beautiful perforated stone tracery in the windows—of which there were ten in the west wall and two in each end—has been much destroyed. In the front are two balcony windows supported by carved brackets and sills, and a larger one of the same pattern in each end (Plate IV).

The central dome, behind the front screen, like that of Muḥâfaz Khân's and other fifteenth-century mosques, rises on a second storey, the side walls of which were of perforated work over a carefully carved frieze,—but there is no inner gallery. This arrangement is best explained by the section on Plate XIX.


The pulpit was also of the high pattern in use in the early mosques, but the canopy over it has long since disappeared. The *mihrâbs* or *qiblas* are, as usual, carved with taste, and there was an inscription over the central one. The *mihrâb* in the north wing is represented in detail on Plate XVIII, figs. 4, 5 and 6.¹

The whole structure has been covered of late inside and out by thick coatings of whitewash, which takes away from its appearance.

The tomb or dargâh stands close to the mosque on the north-east, upon a low base or platform, 50 feet square; on this are twenty pillars which support the verandah surrounding the domed room, 27 feet square inside (Plates XVII and XX, fig. 1). These pillars are unusually richly carved with surface ornament on their bases and capitals, and on the outer faces they have elaborately wrought projecting brackets, to support the sloping drip or eaves that overhangs the façade. One of the columns is represented on Plate XXI, fig. 2.

The walls are faced by twelve pilasters corresponding to the pillars in the front of the verandah, and support the lintels of the roof. The tomb itself is covered by a dome resting on the four walls, and on arches thrown across the corners—being the earliest instance here of this mode of construction. To make room for these, the walls rise to a height of 25 feet, and have a perforated window in each side wall of the upper storey. These have been wrought, in some cases, with a single pattern running through the different panels: one of them is represented on Plate XIV, fig. 4. The entrance is on the south side, and the arched openings on the other three sides were probably at first filled in with perforated stone work; but they have long since been bricked up (Plate V). The dome is carefully carved with a small pendant in the centre (Plate XVII, 3). There are three graves in the floor—two of men, and one of a

¹ These figures are from the drawings by a Bombay School of Art Student in the *Jour. Ind. Art and Industry*, vol. VI, plate 73.



RAUZA OF BAI HANIR AT ASARWA.

woman—but they are probably of a date not earlier than the commencement of last century (Plate XVII).

The corner squares of the verandah are roofed by small domes, and the rest by flat roofing, and the whole has very projecting eaves. These small domes have been carved with an elaboration and care that could hardly have been excelled in marble or ivory. One of them is drawn in detail on Plate XXI, fig. 1.

The antefixa, that crowned the cornice of the verandahs, and the walls supporting the dome of this rauza, have been largely destroyed or carried away, but were of exquisite beauty and endless variety of ornamentation. An example of those from the upper cornice is given on Plate XVII, fig. 2, and others appear in the photograph, Plate V. The stops on the under edge of the cornice are also carved with taste (see Plate XVII, fig. 4).

The corner openings into the verandah are filled by low breast walls, the outer faces of which are beautifully carved in a remarkable variety of ornament, all in perfect harmony and yet without repetition of the patterns. On the inner side this wall is 31 inches in height, with a ledge 16 inches high on the outer face, sloping outwards to form a back or rest for the seat formed on the upper plinth of the wall such as is often found in the maṇḍapas or halls of Hindū temples. A section of this breast wall at the east end of the south face is given in detail on Plate XX, fig. 2.

CHAPTER III.

THE ADALAJ WÂV OR STEP-WELL, AND OTHERS.

PLATES VI, XXII, AND XXX, FIGS. 3, 4.

PERHAPS the finest of the Gujarât Wâvs is that at the village of Adâlaġ, about twelve miles north from Aġmadâbâd, built almost at the same time as, and not very materially differing in plan and dimensions from that of Bâġ Ĥarġr. It varies, however, in the arrangements of the access; for here the entrance to the head of the stair is from both sides, and is reached by a few steps from the ground level, landing on platforms 23 and 26 feet across, from which again are descents of 11 feet on three sides to a spacious landing which measures 41 feet each way. This wâv runs from south to north, and the stair from the north side of the landing leads down to the reservoir (Plate XXII).

On the first platform stand twelve pillars, forming a square $22\frac{1}{2}$ feet across, between their centres. These are arranged in the usual way, so that an octagon is formed by the lintels connecting the inner eight, which support a deep frieze, richly carved after the style of sculpture on the Aġmadâbâd wells (Plate XXII, plan). Probably this supported a dome over the landing, which, however, has long since disappeared. Behind these pillars, on each side, stand two others, which, with those of the octagon, form porches on the four sides of the area. The pillars on the north side stand on the descent and are taller than the others; they are also more elaborately carved as shown in the detail drawing, Plate XXII, d. At the corners of the platform are four small rooms—each only about 4 feet square inside,—with balcony windows facing east and west, and doors on the north and south sides. The details of the window (c) at the head of the descent, on the right, are given in the plan, section and elevation of it on Plate XXII, c; and it will be noted that, though generally the sculpture closely resembles that on Bâġ Ĥarġr's, there is inserted here below the sill a course of Hindû animal figure sculpture. This is continued on the string-course at the same level all along the walls of the wâv.

The descents of the stairs are gentle, every fifth step being of double breadth, and the height of the galleries from floor to floor is about 11 feet 6 inches.

Carved niches occur only in the upper gallery and are of the patterns found in the *minârs* and *qiblas* of mosques (Plate XXX, e. f.), showing how the Hindû artificers applied their designs in the works they erected—to whatever religious class they belonged.

In the second gallery on the right side of the octagonal well, over a door leading to the spiral stair that comes down from the ground level (Plate VI, fig. 2) is a frieze carved with the *Navagraha* or lords of the nine *grahas*. These are the sun and moon, five planets, and the ascending and descending nodes of the moon.




1. THE WAV FROM THE NORTH PLATFORM.



2. ACROSS THE OCTAGONAL WELL.

The nine figures (illustration 2) are rather coarsely carved and have suffered from age, damp, and possibly violence. They are perhaps a remnant of that Sun-worship, once so prevalent in Gujarât.¹ The two on the right are Râhu—the ascending node,—represented by a head (the Dragon's head of western phraseology), and Kêtu, who has a head with the tail of a fish, representing the descending node (or Dragon's tail).

The Hindûs arrange the planets, as in the classic systems of astronomy,² in the order of their distances from the earth, beginning with the remotest: viz. (1) Śani—Saturn; (2) Brîhaspati—Jupiter, (3) Maṅgala—Mars, (4) Sûrya or Ravi—the sun, (5) Śukra—Venus, (6) Budha—Mercury; and (7) Soma—the Moon. As with the Greeks, each hour of the day was assigned in succession to one of the planetary divinities as lords or presidents, whilst the whole day is presided over



2. THE NAVA GRAHA IN ADALAJ WÂV.

and takes its name from the lord of the first hour. Ravivâra or Sunday is also recognised as the first day of the present age; and so the enumeration begins with Sûrya, to whom is assigned the first, 8th, 15th and 22nd hour, the 23rd then falls to Venus, the 24th to Mercury and the 25th hour, or first of the second day, to the Moon or Soma as lord of Monday. In the same way the 49th hour and 3rd day fall to Maṅgala, and so on,—always passing over two in the list—to Budha, Brîhaspati, Śukra, Śani, in succession.

In this representation, the planetary divinities are arranged in the order of the days of the week: the first figure on the left is easily recognised as Sûrya, holding two sun-flowers or lotuses; Soma or Chandra scarcely differs in form from him; Maṅgala or Bhauma—Mars, is four-armed and holds an *aṅkuśa* or elephant goad in his upper right hand,—the other emblems are defaced. The next figure shows how the Hindûs themselves make mistakes in their own mythology, for, instead of Budha or Mercury, who presides over Wednesday, the sculptor has here carved

¹ See *Arch. Sur. Westn. India*, vol. IX, pp. 72-74.

² Conf. Ideler, *Handbh. d. Math. u. tech. Chronologie*, Bd. I. Ss. 178f.; *Ind. Antiquary*, vol. XIV, p. 322 f. The month is always reckoned as of 30 solar days, and follows the same system: if the first month begin with Sunday, Sûrya presides over it, and the next month will begin with Maṅgala as its lord, and so on. The artificial year of 360 days has also its presiding planetary divinities, fixed by the same method (*Sûrya Siddhânta* xii, 78-79).

a figure of Buddha—the founder of Buddhism.¹ The presiding divinity of Thursday is *Bṛihaspati* or *Guru*—four-armed and recognised by his beard; *Śukra* is also four-armed and holds up something like three water-pots one upon another on his upper left hand; and *Śani* or *Saturn*, four-armed, has a bullock at his left foot. *Rāhu* and *Kētu*,—the ascending and descending nodes—not representing real planets, have no place in the astrological government of the day.

In one of the niches on the right side of the upper gallery is a Sanskrit inscription which begins “Samvat 1558 (A.D. 1502) in the month *Māgha*, *Maḥmūd* *Padshāh* being king. Salutation to *Vipāyaka*, to whose race belonged king *Mokala*, chief of the district of *Dandāhi*. To him was born *Karṇa*, whose son was *Mūlarāja*. *Mahīpa* was *Mūlarāja*’s son, and *Virasimha* and *Naisha* were the sons of *Mahīpa*. *Virasimha*’s queen, whose name is *Rūjhā* (or *Rūdā*) has constructed this well: it is dedicated at the time when the sun is in the north, in the month *Māgha*, the bright fortnight, the fifth day, Wednesday, the lunar asterism *Uttarā*, the *karana* *Bava*, the *yoga* being *Siddhi*.”

Then follows a glowing description of the structure, after which the consort of the chief is praised in a few verses; and the cost is stated at 5,00,111 *ṭaṅkas*.² What this sum exactly amounted to depends on the value of the *ṭaṅka* which is rather uncertain; if it were a third of a rupee,³ the amount would be about 1,66,700 rupees or slightly over the cost of the *Asār wā wāv* of the same date. If, however, the *ṭaṅka* were two-thirds of a *maḥmūdi*, or scarcely one-third of a rupee (and it probably bore some such definite relation to these coins), then the sum named would be somewhat less, or about 1,60,500 Rs. and 3,33,450 *maḥmūdīs*.

This *Virasimha*, whose consort constructed the well, was a descendant of *Ānandadeva Vāghela* the chief of *Kālol*. With his brother *Ajītrasimha*, he is said to have been at feud with the Muhammadans, who slew the elder brother and placed a garrison in *Kālol*. It was, however, held for several generations afterwards by *Virasimha*’s descendants till it was lost in A.D. 1728 by *Bhagatsimha*. That chief retired on *Limbodarā*, a village which he took from the *Ānjanā Kumbīs*, and it continues to be held by his descendants who still claim to be the representative chiefs of the *Vāghela* family.⁴

As already mentioned, the *wāv* runs from south to north,—the approach being at the south end; and from the back of the irrigation shaft, at the north end to the extreme south of the masonry is 251 feet, or a little in excess of the length of *Bāi Harīr*’s. The shaft is 17 feet in diameter; the width of the landing platform 23 feet, and of that round the main shaft is 28 feet. To this latter a spiral stair descends on each side as at *Aḥmadābād*, but there are no canopies or *chhatris* above their entrances:—possibly they have been destroyed.

¹ Even Europeans in their theorizings have not escaped this error: see *Cunningham, Bhilsa Topes*, pref. p. vii. For some account of the Navagraha and their representations see my paper in the *Indian Antiquary*, vol. XXXIII, pp. 61 ff.

² *Architecture and Scenery in Gujarat and Rajputana*, p. 7.

³ It may, however, have been somewhat less, or about a quarter of a rupee. Conf. *Thomas, Chronicles of the Pathan kings of Delhi*, pp. 50n. 224n.

⁴ *Rās Mālā*, vol. I, p. 345.

The front of the frieze round the octagonal opening at the head of this main shaft is carefully sculptured in that ever recurrent pattern in Hindû ornamentation—the Buddhist rail (*see* Plate XXII a). The depth of this reservoir from the top of its upper frieze is fully 53 feet, and this is also about the depth of the draw-well at the north end.

Two turrets, each 14 feet 4 inches high, stood at the sides of the two entrances from east and west. Those on the west have been more or less ruined; but the two on the east are still entire.

OTHER STEP-WELLS.

PLATE XXIII.

Gujarât and the provinces to the north-east of it seem to have been a sort of habitat of these wâvs or step-wells; but, in the wars that ravaged the country from the twelfth to the sixteenth century, large numbers of them must have been destroyed. In Northern Gujarât we still find examples at Roho and Vayad, the fragment of a fine one at Pâtan, and others scattered over the province from Baroda northwards.¹ At Uvârsad, only three miles north from Adâlj is an old wâv built of brick, with stone pillars, lintels, steps, &c.; and at Chhatrâl, twelve miles to the north-west of this and four miles from Kâlol, is a step-well dating from about the same time as this at Adâlj.

But one more wâv, two and a half miles south of Ahmadâbâd, near Isânpur and between that and the lands of Dâni Limḍa, still calls for mention, as being perhaps one of the most modern examples of the regular wâv. It was constructed little more than forty years ago by the late Jeṭhâbhâi Jivanlâl Nagjibhâi (or Mulji) of Ahmadâbâd. To obtain the materials, he purchased from the holder of Shâh 'Âlam the *rauṣa* belonging to a masjid known as that of Mâlik 'Âlam or 'Ilîm, standing a little to the north of Shâh 'Âlam and described in the previous volume,² and from the late Qâzi Hasan-ad-dîn of Ahmadâbâd he bought the Nenpurvâḍâ masjid at Râjapur-Hirpur together with its accompanying *rauṣa*. These were pulled down by the Hindû purchaser and the materials used in the construction of this well and in putting up a portico to his temple in the Shahrkoṭṭa suburb. In the ornamentation of the well one of the *mihrâbs* of the mosque has evidently been utilized.

This wâv (Plate XXIII) is 210 feet in extreme length and from 21 to 22 feet wide, with a dome raised on twelve pillars on the entrance at the west end. It has the usual descents from platform or gallery to gallery. The first and third platforms are about 18 feet wide each and the second 23 feet across; besides there is a narrower one of 15½ feet broad, just in front of the shaft of the draw-well (Plate XXIII, figs. 2 and 3). To the second, third and fourth platforms from the entrance there are small spiral stairs descending from above—that to the second platform being on the

¹ *Archæol. Surv. Westn. Ind.* vol. IX, pp. 37, 101, 112, 116-117.

² *Ibid.* vol. VII, pp. 26-29.

north side. The pillars used are mostly from the old mosques and rauzas, but mixed up with them are others of a totally different style from Hindû or Jaina remains, clumsily fitted together. The whole work is devoid of any evidences of originality in structural or architectural arrangements; and, moreover, it seems to have failed of its purpose, for it is filled with fetid water and quite disused.

At the entrance to Îsanpur village is another step-well of stone—known as Jiji-bâbâ Râñî's; and elsewhere in the vicinity are two others built of brick.



1. TOMB OF SHAH ALAM, WEST FRONT.



2. MASJID AND COURT AT SHAH ALAM.

CHAPTER IV.

SHAH ALAM.

PLATES VII, XXIV-XXVIII, 1.

MUHAMMAD Shâh 'Âlam was the son of 'Abdullah Quṭb-al-'Âlam or Sayyid Burhân-ad-dîn the founder of the Bukhâriah Sayyids of Gujarât, and whose tomb is at Baṭuwâ or Vaṭuvâ, six miles to the south of Aḥmadâbâd, and has been described in the previous volume.¹

It may help to the identification of the different members of the Bukhâriah Sayyid family mentioned in connexion with these tombs if we give here the genealogy of its representatives till the end of the seventeenth century:—

1. 'Abdullah Quṭb 'Âlam, styled Shaikh or Sayyid Burhân-ad-dîn, was the grandson of Shaikh Jalâl or Makhdûm Jahâniân Jahângasht Sayyid Jalâl Bukhâri (A.D. 1308-1384), the son of Sayyid Aḥmad Kabir, the son of Sayyid Jalâl. Shaikh Jalâl was buried at Uchha;² and his grandson Quṭb-al-'Âlam died in A.D. 1453 and was buried at Baṭuwâ.³

2. Sayyid Muḥammad Shâh 'Âlam, son of Quṭb-al-'Âlam, died 20th Jamâda'l âkhir A.H. 880, or Saturday 21st October A.D. 1475, and was buried here.

3. Sayyid Râjû Sattâr 'Âlam, son of Shâh 'Âlam.

4. Sayyid Aḥmad Shahîd Panâh 'Âlam, son of Râjû Sattâr.

5. Sayyid 'Abd-al-Ghafûr Mazhir 'Âlam, son of Sayyid Aḥmad.

6. Sayyid Ḥasan Nur 'Âlam, son of Sayyid 'Abd-al-Ghafûr.

7. Sayyid Jalâl-ad-dîn Mâh 'Âlam, son of Sayyid Ḥasan.

8. Sayyid Muḥammad Maqbûl 'Âlam, son of Sayyid Jalâl-ad-dîn Mâh; he was buried in the second large tomb at Shâh 'Âlam.

9. Sayyid Jalâl-ad-dîn Maqṣûd 'Âlam, son of Sayyid Muḥammad Maqbûl.

10. Sayyid Ja'far Badr 'Âlam, son of Jalâl-ad-dîn Maqṣûd.

11. Sayyid Muḥammad Maḥbûb 'Âlam (cir. 1700 A.D.), son of Sayyid Ja'far Badr 'Âlam.

Sayyid Muḥammad Shâh 'Âlam Bukhâri is said to have been the eleventh of the twelve sons of Quṭb-al-'Âlam and was known generally as Miyân Manjla. He accompanied the Sultân Quṭb-ad-dîn when he set out to resist the invasion of Maḥmûd Khilji; but, after encouraging his sovereign he returned before the armies met at Kapadvanj (March 1451). He had married Mirgî a daughter of the Jâm of Sindh, whilst Muḥammad Shâh II. had married her sister Moghalî. The latter had a son Faṭh Khân who was entrusted to the care of his aunt, Shâh 'Âlam's wife, and was brought up in his family and there protected from the jealousy of Quṭb-ad-dîn.

¹ *Ante*, Part I, pp. 60-63 and Plates lxxiii, lxxiv.

² Thomas, *Chronicles of the Pathan kings of Delhi*, p. 94n.

³ *Ante*, Part I, p. 60.

The great influence and repute of the derveshes, however, was scarcely sufficient to effect this, and had to be aided by means of disguises and stratagems. On the death of the Sultân in May 1459, his uncle Dâûd Shâh succeeded him, but he soon proved unfit for rule, and the nobles brought into the city the young Faṭḥ Khân, the half brother of Qutb-ad-din, then in his fourteenth year, and placed him on the throne, 18th June 1459, when he assumed the title of Maḥmûd Shâh I,—also known as Bigarah or Baiqara. During his reign Shâh 'Âlam died in 1475, and his tomb at Rasûlâbâd, where he had lived, was afterwards built by Tâjkhân Narpâli,¹ a noble of Maḥmûd's court.

Rasûlâbâd, "the dwelling of the apostle"² or, as the place is now usually styled, Shâh 'Âlam, is within the bounds of the village of Dâni-Limḍa or Sundhal Khândrol, about a mile and a quarter to the south of Aḥmadâbâd, and two and a half miles north-west of Baṭuwâ or Vaṭuvâ, where is the tomb of Shâh 'Âlam's father.

The group of buildings here was erected at various dates between A.D. 1475 and 1570. Besides a number of smaller and miscellaneous structures, the chief are two large tombs, the Masjid, and the assembly hall.

What endowments were originally settled upon the tombs and Masjid for their maintenance is now unknown, though they were doubtless very liberal. But notwithstanding the strictness of Muslim law for the protection of such *waqf* endowments, human faithlessness always finds means of evading it, and the incomes of these establishments are usually alienated by their trustees and lost. A century after the extinction of the Aḥmad Shâhi dynasty, we find the Shâh 'Âlam Rauza in want of support, and a *sanad* was accordingly granted by 'Âlamgir or Aurangzib in A.H. 1080 (A.D. 1670) assigning for the maintenance of the Rauza and the support of its custodians—the Sayyids of Baṭuwâ, the villages of Îsanpur, Sârsa, Wâsna Faṭhepur near Aḥmadâbâd, Wâsna Buzûrg near Mâhar in Khêḍâ, Wâsna Mârâgiya, and Sâlaḍâ in Dholkâ pargana.

By another deed, fifty-four years later, in 1724, the Gaikwâd Trimbakrâo Dabade assigned or confirmed the following villages:—Îsanpur, Sârsa, Wâsna Buzûrg, Bâkrol in Daskrohi, Wâsna Sarkhej, Sâlaḍâ, Palḍi, Jalâlpur, and Lâli in Maḥmûdâbâd.

When Gujarât came under British charge, in 1817, most of these villages seem to have been again alienated or sold, and at a later date Wâsna Buzûrg in the Maḥmûdâbâd pargana of Khêḍâ zilla,—which the Sayyids still held on *in'âm*, subject to a quit-rent,—owing to their mismanagement, was made *khâlsa* and placed under Government control. All but three villages had then passed out of the hands of the Sayyids; but no accounts were available as to the circumstances or reasons for this. Those remaining are Îsanpur in the Daskroi pargana, valued in 1864 at Rs. 2090 per annum; Sârsa in Jethalpur pargana, worth about Rs. 2000; and Wâsna Faṭhepur in Daskroi, valued at Rs. 960 a year.

¹ Bayley, *Gujarat*, p. 238, has Tûrpâli, and at p. 312,—Narpâli; Bird, *History of Gujarat*, p. 211, has Nariâli; Sir T. C. Hope, followed by the *Bombay Gazetteer* (vol. V, p. 296), has also Nariâli; and H. Briggs, *Cities of Gujarashtra*, has Nirpoli. Rev. G. P. Taylor has verified this reading for me.

² From *rasl*, "news," comes *rasûl*, "a messenger"—also a title of Muḥammad.

The statements submitted in 1867 respecting these three villages were to the following effect:—About 1826 the Sayyids obtained some 14,000 rupees on the mortgage of Īsanpur to a Hindû: this was repaid with interest, about 1856, by Bibi Basti Begum the wife of Mir Ja'far 'Alī, and the mortgage was transferred to her. Her father, the Qâzi of Almadâbâd, was her agent, and in 1867 about 10,000 rupees of her claim was still unredeemed, and a sum of fifty rupees was said to be paid monthly towards the expenses of the annual 'Urs, when offerings are made at the shrine.

Sârsa had been leased to a Hindû in 1836 for a period of 32 years in consideration of a payment of 23,000 rupees. And the revenues of Wâsna Faṭhepur were divided into six parts, of which one was in the hands of the manager, a second with two Sayyids—Ḥasan 'Alī Bâqir 'Alī and Faẓl 'Alī Diwânji, a third with the heir of Sayyid Chulâm Shujâ'at, for whose debts it was attached; the fourth was leased by Ḥasan 'Alī Bâqir 'Alī to a Hindû; the fifth, on account of the debts of Sayyid Ḥasan 'Alī Gisa's heirs, was attached in favour of the same banker as the third; and the sixth had been secured by another in satisfaction of a debt of the heirs of Faẓl 'Alī Diwânji and Amir Miyân Sâheb. The Rauza having sustained considerable injury by the earthquake of June 1819, the Sayyids further averred that as much as 45,000 rupees were spent in repairing it¹; but, though some repairs had been effected, it would have been hard to account for so large a sum spent on them. This is a fair sample of how the endowments of these old foundations have been diverted to private purposes, squandered and misapplied.

The late Sir Barrow H. Ellis, then Revenue Commissioner, started an inquiry in 1862-63 into the revenues and administration of these and other Muhammadan foundations, proposing to hand over to the Sayyids between Rs. 1300 and Rs. 1400 a year as surplus proceeds of the revenue of Wâsna Buzûrg, if they would guarantee to keep the Shâh 'Ālam buildings in repair out of this and the other revenues. The collector, however, replied to this in 1867, objecting to the expenditure of money on the preservation of buildings whose architectural beauties he did not consider warranted it; whose keepers had hitherto neglected their duties; and because the Musalmâns were the most antagonistic to British rule. The then Commissioner supported this on the ground of funds being more urgently needed for public works than "for expenditure on these old buildings."

The Government of Bombay next reminded these officers "that it was not because these buildings are, or ought to be, objects of veneration to people of any particular creed, that their repair is desirable, but because the remarkable architecture of the structures renders them worthy of care on their own account." Three months later the acting collector declared that he did not agree with his predecessors, and that the "Rauza partook more of the nature of a monument of the wealth and character of the Muhammadan empire in Gujarât than a religious building, and as such deserved to be cared for at the hands of our Government." Immediately after this, Government, acting on the initiative given three years

¹ A. W. Crawley-Boevey, *Scheme, &c.*, pp. 42f.; in the Appendix, p. lxxix, however, the villages are named as Sârsa, Īsanpur, and Wâsna Makhdumpur.

previously by Sir Barrow H. Ellis, sanctioned a sum of Rs. 5300 for repairs at Shâh 'Âlam and Rs. 5000 for the same at Sarkhej, the management of the repairs being entrusted to the constituted authorities of the district. The double authority of collector and the engineer, however, did not always work well, and very little good was done.

The ground occupied by the Shâh 'Âlam buildings is of very irregular shape (Plate XXIV). Originally it may have been little more than an oblong area, about 100 yards from east to west, and 70 from north to south, including the sites of the mosque and great tomb; to this other plots of varying sizes had been added from time to time during the first century after the death of the Pir; and now its extreme length is 221 yards, with a breadth close to the southern boundary of 185 yards; but from the entrance gate to the assembly hall, a length of about 80 yards, the width is only from 40 to 50 yards; in front of the hall it is 90 yards across to the back of the mosque. The whole area covered is about 24,400 square yards or somewhat over 5 acres. The land is personal grant or in'âm and is assessed at Rs. 13, as quit-rent, for which Government receives only R. 1, 14 ânâs.¹ All the ground to the south of the principal dargâhs, extending to an acre and a quarter is simply a graveyard or *qabrgâh*; for it is esteemed a privilege by religious Muhammadans to be buried in or near the tombs of such holy pirs as Shâh 'Âlam.

The buildings in this enclosure are two dargâhs of the same size,—one of the saint, near the centre of the area,—and the other (H) to the south of the mosque; the masjid on the west; the Jamâ'at Khâna, Diwân Khâna or Hall, facing the principal dargâh from the north; a number of subsidiary buildings and two entrances—one on the north and the other on the west (K). The ground plan (Plate XXIV) shows the arrangement and relative size of the different structures.

The dargâh or tomb of Shâh 'Âlam (Plate VII, 1) occupies the central position, and was doubtless the first of the structures erected in the enclosure—and must have been begun soon after the Pir's death in 1475, by Tâj Khân Narpâlî, and it is said to have taken ten years to complete.² It stands on a low base or platform 65 feet square, which supports three concentric squares of pillars,—the outer consisting of twenty-eight connected by stone trellis work, forming the outer walls; the intermediate square of twenty pillars stands in a corridor round the inner square of twelve which support the dome, under which is the sarcophagus or tomb. There are entrances on each of the four sides, but on the west is the principal doorway with a porch in front of it supported by coupled pillars. On this face also the six other interspaces between the pillars are occupied by arched openings filled in by wooden frames with wire gratings, and perforated stonework only between the jambs and the pillars (Plate VII, 1). The arches over these openings

¹ Crawley-Boevey, *Scheme, &c.*, app. p. lxxix.

² Briggs, *Cities of Gujarashtra*, p. 322, says it was begun in the time of Mahmûd Baiqara, "and in the year A.H. 938," or A.D. 1532; but this was twenty-two years after Mahmûd's death, and sixty after the death of Shâh 'Âlam. As Tâj Khân was a notable in the courts of Mahmûd Baiqara and Muzaffar, we may be satisfied that the erection of the tomb was begun between A.H. 879 and 915, when Mahmûd died, and that Tâj Khân's share in the work was completed before the death of Mahmûd, and probably between 1480 and 1500 A.D. (885-905 A.H.).

are completely filled with pierced stonework, carved in beautiful and varied patterns; that on the left of the entrance is represented on Plate XXVIII, 1. It seems not improbable that the original intention was to fill the lower interspaces on this side also, as on the other three, with stone tracery,—but that either the funds fell short or some accident befell the structure, and it was completed after the pattern of the neighbouring tomb. The corresponding spaces on the other three sides are filled with stone trellis work from the upper line of the bases of the pillars to the heads of the arches,—an example of which is represented on Plate XXVII, 1. In both these examples may be noted the carrying of the pattern through several of the squares into which the astragals divide the windows.

The floor round the central tomb, on which stand the twenty pillars dividing the aisles of the corridor, is paved with black, white and grey marbles; and with yellow slabs in places, especially in front of the entrance to the tomb. The black slabs are arranged in lines between the pillars and pilasters—forming squares which are generally filled in with white and grey slabs in alternate squares (Plate XXVI, 2). The outer aisle is roofed by small domes—seven appearing on each face.

The inner chamber, containing the tomb, is surrounded by richly perforated marble work between the pillars, with doors in three of the sides—but not on the north, towards which is the head of the tomb, the foot being about the centre of the chamber. Round it is a white marble perforated screen, about four feet high, with small doors on three sides; and over this is a carved wooden canopy, similar to that at Sarkhej, and elaborately inlaid with mother-o'-pearl in a florid pattern. The sarcophagus is of the same general pattern as those in the royal cemetery of the queens, but plainer.

The roof over the chamber is stilted or raised on a sort of clerestorey wall above the surrounding screens, and has on each side a pointed arched window, filled with perforated stone-work. Over this the dome rises in concentric mouldings richly decorated inside with abundance of inlaid mother-o'-pearl and with the stone coloured—dark blue, reddish brown, &c. This decoration is said to have been executed at the expense of Âṣaf Khân, whom Briggs calls the brother of the celebrated Nûr Jahân¹;—but this must be a mistake: this Âṣaf Khân seems more likely to have been Ghayas-ad-dîn 'Alî Âṣaf Khân, who distinguished himself in the conquest of Gujarât under Akbar; and died there in 1581.

The doors of this tomb, which are surrounded by richly-perforated stone tracery, have been filled in, within recent years, by perforated brass work made in Ahmadâbâd from patterns derived from other buildings. The merits of this modern work may be judged from the delineation of one of them on Plate XXV. The white marble work round and about the door is represented in the same illustration, from which it will be noted that the doorway is simply an imitation of a *mihrâb*, and has an inscription over it.

¹ Briggs, *Cities of Gujarashtra*, p. 322. There were four nobles who bore the name of Âṣaf Khân: Nûr Jahân's brother was Mîrza Abu'l Ḥasan Âṣaf Khân, who married a daughter of Ghayas-ad-dîn 'Alî Âṣaf Khân, and was the father of the famous Mumtâz Mahal, sometimes called the second Nûr Jahân. He was buried at Lahor. Conf. Blochmann, *Âin-i-Akbari*, vol. I, pp. 369, 510 f.; Beale's *Oriental Biog. Dict.* (ed. 1894), s.v. Âṣaf Khân.

In this mausoleum, at the east end of the south corridor, an area measuring 19 feet by 26, is screened off by trellis-work, having two doors in its west end. It contains seven tombs of Sayyids, said to be those of four sons of Shâh 'Âlam and three of his grandsons: there is also a tiny one of a parrot. They are of sandstone. To the west of the south entrance is a small room in the corridor, surrounded by exquisitely carved trellis-work. In this is said to be buried Sayyid Jalâl-ad-dîn Mâh 'Âlam—the fifth in lineal descent from Muḥammad Shâh 'Âlam.¹ It has, however, sometimes been loosely stated that it is the grave of a brother of Shâh 'Âlam. The *Mirat-i-Aḥmadî* also informs us that Shaikh Kabîr, the son of Shaikh Munâwar, a man renowned for his learning, was buried in this mausoleum in A.H. 1026, A.D. 1617.

At a distance of about sixty yards west-south-west from the central mausoleum, is a second on the same plan and scale, but having its main entrance on the east, another on the south, and doors between the pillars on each face (H, Plate XXIV). The arches over these doors are all filled with the same beautiful perforated stone work as in the Pîr's tomb; much of this, however, has probably been restored in an imitative way, during the nineteenth century. The central grave in this tomb is that of Sayyid Muḥammad Maqbûl 'Âlam, the son of Sayyid Jalâl-ad-dîn Mâh 'Âlam, and sixth in descent from the pîr. Over this grave, upon a stone tablet, are the footprints of the prophet (*qadam i-rasûl yâ sharîf*). Inside the dargâh also are three other graves on the south side; these are of Maqbûl 'Âlam's son Sayyid Jalâl-ad-dîn Maqsûd 'Âlam, in the centre; of Sayyid Jâ'far Bhadr 'Âlam, the son of Jalâl-ad-dîn, to the west; and of his son Sayyid Muḥammad Maḥbûb 'Âlam on the east of Jalâl-ad-dîn's. The *qadam i-rasûl* or footprints of the prophet affixed to the principal grave here is specially honoured on the *bâri wafât* or *wafât sharîf*—the anniversary of the death of Muḥammad, on the 12th of Rabi'û'l awwal.

This veneration of the footprints of their prophet by the Musalmâns, bears a close analogy to the worship by Hindûs, Buddhists and Jainas of the *pâdukas* of Vishṇu, Śâkyamuni and the Tirthakaras respectively. Further, we learn that a deduction from the revenue was granted by Muhammadan governments to zamindârs to provide for the upkeep of a *dargâh* or *rauza*, in which a tablet with the prophet's footprints was preserved for veneration; but whether such a subvention had any influence in the erection of this large rauza, we have no information. At Gaur in Bengal there is a fine mosque known as the Qadam Rasûl Masjid, erected in 1530, in which is a slab bearing the footprints, said to have been brought from Arabia by 'Ala-ad-dîn Ḥusain Shâh king of Bengal (1494–1521). In the time of Sirâj-ad-daulah it was carried off, but was restored to its place by Ja'far 'Alî Khân, and is still carefully guarded by the Maulawî.² Among other examples of such objects, we learn that Sayyid Jalâl-ad-dîn Makhdûm Jahâniân Jahângasht or Makhdûm Jahâniân Sayyid Jalâl-i-Bukhârî the great grandfather of Shâh 'Âlam, brought from Makkah in the time of Sulṭân Firûz, a large stone bearing the *qadam-i rasûl*, said to have been placed in a Jâmi' Masjid at Dehli. And in 1579 Mîr Abû Turâb, the son of Kamâl-ad-dîn—a teacher

¹ This is on the authority of the late inâmdâr Mûsâ Miyân Ḥammad 'Alî, through the Rev. G. P. Taylor, to whom I am indebted for several details.

² Ravenshaw's *Gaur*, p. 20; Fergusson's *Ind. and East. Archit.* p. 548; see also *inf.*, p. 50, note 2.

and scholar—brought back with him from Makkah another similar stone, which, as will be noticed below,¹ was afterwards placed over his tomb in the neighbouring village lands of Behrāmpur, to the north-west of Shāh 'Ālam. The *qadam i Mubārak* in the tomb of Maqbūl 'Ālam, however, is said to be only a copy made from the stone in the Jāmi' Masjid at Dehli; but by whom made, or when brought to this place is not known.

The dome over the tomb is quite plain, without mouldings or ornament. The floor is of marble, but large areas of it are covered by irregular slabs, and some of these are evidently the abaci of old pillars. In the north-west corner is a carved slab of white marble, let into the floor and measuring 4 feet 6 inches by 2 feet 10 inches—apparently meant to represent a prayer-mat. There is no inscription in this tomb.

In the south corridor, and also outside on the south are many graves—one being in the middle of the porch.

On the domes of both these large mausolea are tall metal finials terminated with the pipal leaf which seems to have been the symbol of the Muhammadan rulers of Gujarāt, and was placed on all their tombs and mosques.

To the south of these two dargāhs is a large area containing a few canopied tombs and a great many of the ordinary low type. One of the larger, about twenty yards south of Maqbūl 'Ālam's (at J on the plan) is beautifully carved; and the late Mūsā Miyān stated that this was the tomb of Ṣaif Khān, who was an officer of high rank under Sulṭān Muẓaffar II, and was sent with Nizām-al-Mulk Sulṭāni and others in 1513 from Dhār to Dilāwāḍa, when they were attacked near Māṇḍu but defeated the Mālwā troops; and again in 1520 he was sent with Khizr Khān Asad-al-Mulk to assist Nizām-al-Mulk against the Rāṇā of Idar (A.D. 1520).²

Between the two large rauẓas there stands a small one (at M on the plan) with pierced stone windows and containing a somewhat plain tomb,³ which is said to be that of Nawāb Nāṣir-ad-dīn of Baroda, who was a *murīd* or disciple of the descendant and successor of Shāh 'Ālam, living about 1780 A.D.

Eighteen yards north of the second mausoleum is the mosque, said to have been erected by Muḥammad Sālīh Badākshi (Plate VII, 2). The minārs were begun by Najābat Khān early in the seventeenth century, and after his death were completed about 1620 by Ṣaif Khān—the same person who built a hospital and college in Ahmadābād.⁴

This masjid is of a later style than any we have yet met with, and, with that of Muḥammad Ghaus in the city, is more of the usual form of such buildings in other parts of India, and can scarcely be described as belonging to the local style. "The interiors, however, of both these mosques are well worthy of study

¹ See *infra.*, p. 50.

² Bayley, *Gujarāt*, pp. 251, 267.

³ Hope, *Ahmedabad*, p. 96.

⁴ Briggs, *Cities of Gujarashtra*, p. 322, and followed by Hope, *Archit. of Ahmedabad*, p. 61. Owing to the frequency of the same titles among Muhammadan nobles, it is difficult—in the absence of dates—to say with any confidence, to which of several individuals a particular work is to be assigned.

(Plates VII, 2 and L, LI). The mode in which the pendentives are brought up to receive the circular domes is quite as happy as any of the constructive expedients of the Gothic architects and more elegant in execution. The Byzantine architects never accomplished this—their peculiar expedient—so successfully.”¹

The masjid is 121 feet in length over the walls, and 54 feet across,—the inside measurements being 116 by 51 feet. The minârs having been added afterwards, stand forward about 9 feet from the end walls; they rise to a height of about 90 feet, exclusive of the finials, are of elegant design, and have four galleries supported on carved brackets.

The whole area of the floor is divided longitudinally into three aisles—the wider one in the middle being 18 feet 4 inches between the centres of the pillars, and the other two 14 feet 8 inches; and across—it has seven bays, of which three are of the wider size. This arrangement gives eight smaller square areas and three larger, with ten that are oblong—measuring 17 feet 4 inches by 12 feet 8 inches within the pillars. These areas are all covered by domes, of which the three larger, along the middle of the roof, are higher and finished outside with finials. The domes are supported by pendentives connecting the cross arches between the pillars, as illustrated in the case of the mosque of Muḥammad Ghaus, Plate L.

In line with the principal domes are three mihrâbs or qiblas—the central one being much the larger—and all have carved recesses.

The great earthquake of 1819, besides injuring the minarets, had considerably shaken the back wall, and outside, opposite each of the cross lines of pillars, a heavy brick buttress has been raised against it. The minarets have also been repaired since 1863.

In front of the mosque and about fifteen yards from it, is a large sunk reservoir or tank, some 72 feet square, covered over on a level with the court, and having open shafts in the centre, the two west and the south-east corners,—whilst beyond it, to the north-east, is the open ablution tank, about 22 feet square, with arcaded porticoes on its north and south sides.

To the north-west of this again is the Diwân Khâna, Jamâ’at Khâna, or assembly hall, which faces the south; it is about 61 feet by 41, open in front, and supported by pillars, and is surrounded on three sides by small rooms,—in one of which is a stair leading up to the roof. The hall is used for the accommodation of guests, especially of such as come at the time of the ‘Urs celebration, whilst the small rooms are for the safe keeping of their baggage and vessels.

The first erection of this hall is ascribed to the lifetime of Shâh ‘Âlam and the reign of Muḥammad Shâh II (1443–1451 A.D.), but it was restored under Muẓaffar Shâh, the last of the Aḥmad-Shâhi kings (1561–1572). It was again renewed, towards the end of the seventeenth century, by Sayyid Ja’far Bhadr ‘Âlam, a descendant in the eighth generation from Shâh ‘Âlam. It is said to have had a wooden roof covered with tiles; but, in the war with the Marâṭhas, when General Goddard, in February 1780, besieged Ahmadâbâd, this hall was partly demolished

¹ Fergusson, *Ahmedabad*, pp. 92, 93.

to furnish materials for the siege. It has now a good terraced roof with a pavilion over the west end rooms.

To the west of this, and extending as far as the north end of the masjid, are a number of buildings of various heights (A, B, C, D, L, on the plan) and probably of different dates, which are occupied by visitors at the '*Urs*, a festival celebrated on the anniversary of the death of the saint,' which occurs on the 19th day of the month Jumâdâ'l-akhar; but all the week from the 17th to the 23rd are held as high days. On the 23rd ladies alone (*parda-nishîn*) are admitted to the premises. The time of the festival is spent in social re-unions (*majlis*), the reading of the *Qorân* and prayers.

At the north-west corner of the hall is the inner gateway, divided into three by two rows of pillars that support the roof. On the north side it has a square porch with two coupled pillars in front; and over the south side is an open storey,—such as Muhammadans fancy for rest and conversation. About fifty-three yards to the north of this last stands the handsome main entrance (Plate XXVI, 1) forming a block about 33 feet square with an arched gateway in the centre, rooms for the guard on each side, and an upper storey having two small pavilions upon the roof towards the inner or south side (see the plan, Plate XXIV).

To the support of the establishment, besides the revenue of the villages above referred to, Rs. 148 Sa. 8p. are paid annually to the manager from the Mamlat-dâr's treasury, Rs. 137 being on account of the annual '*urs* at the Rauza, when offerings of food, incense, &c., are made, and the balance is on account of compensation for the abolition of transit duties.²

¹ '*Urs* also means marriage festivities; but it is likewise applied to the ceremonies observed on the anniversaries of the death of notable *murshids* or saints.

² Crawley-Boevey, *Scheme*, p. 23.

CHAPTER V.

SIDI BASHIR'S MOSQUE, MINARS AT THE RAILWAY STATION, AND
DARVESH 'ALI'S MOSQUE AND RAUZA.

PLATES XXVII, 2; XXVIII, 2; XXIX AND XXX.

ABOUT a quarter of a mile south of the railway station and nearly opposite the Sârangpur gate, are the remains of a mosque known as Sidi Basîr or Sidi Bashîr's, with an adjoining tomb. Nothing of the mosque is now left but the principal entrance archway with its two lofty flanking minârs which are in fair condition. They have three balconies above the roof line of the front, with doors on the west side: one of them is shown in the drawing, Plate XXVII, 2. They are $69\frac{1}{2}$ feet in height, elaborately carved, in fairly good preservation, and have been compared in style with the architecture of Miẓân Khân Chishtî's mosque¹, but are probably of somewhat later date. Sir T. C. Hope ascribed the mosque either to Sidi Bashîr, a favourite slave of the Sultân Aḥmad, or to Malik Sârang, a noble of the court of Maḥmûd Baiqara, who founded the adjoining quarter of the city, called after him Sârangpur, and who is said to be buried in the adjoining Rauza; Sidi Bashîr's remains do not lie there, but in a walled enclosure below the masjid platform to the north-east.

This mosque was ruined in the contest between the Marâṭhas and the Muhammadan Deputy-vice-roy Jawân Mard Khân Bâbi, about 1753. One angle of the tomb with two pillars, has fallen, and the rest of it, supported by thirty pillars, is occupied by faqîrs and grass dealers, who have divided it up by mud walls, cook in it, and keep it in disorder.

It stands on a piece of Government waste ground in the railway suburb, measuring 2027 square yards.²

MINÂRS AT THE RAILWAY STATION.

North of this last, and at the south end of the Railway station platform, stand the two largest and loftiest minarets at Aḥmadâbâd. They are apparently about 95 or 100 feet in height. All traces of the mosque to which these magnificent towers belonged have vanished and its very designation is lost. They narrowly escaped removal to make room for the railway, and at a later date it was proposed to incorporate them in a new station to be designed in the Muhammadan style.³


¹ See Part I, pp. 69, 70.

² Hope and Fergusson, *Ahmedabad*, p. 55; Crawley-Boevey, *Scheme*, app. p. lxiv; *Lists of Remains*, 1st ed. p. 146, No. 21, or 2nd. ed. p. 70, No. 16.

³ Hope, *Ahmedabad*, p. 57 and plate 88.

The style and material seem to point to the period in which the Sidi Bashîr and Râjapur-Hirpur mosques were erected, or to the beginning of the the sixteenth

century as the approximate date of the building. Though much damaged about the bases, the stairs inside may still be used (see illustration No. 3).



3. MINARS AT AHMADABAD RAILWAY STATION.

DARVESH 'ALI'S, OR OJÂ BIBI'S MASJID
AND TOMB.

PLATES XXVIII, 2, XXIX, XXX, 1, 2.

In Jhaveriwâdâ, near Permad Shâh's rauza, is a handsome little stone mosque with a tomb, popularly known as Darvesh 'Ali's, Tânkawâlâ, or Ojâ Bibi's Masjid; but properly, it is said, it should be called Khonjâ Bibi's—of whom, however, we know nothing. But in an inscription we find it dated in A.H. 910, or August 1504, so that we have no difficulty about its age.

In the City Survey of 1824 it stood in an area of 10,009 square yards or 2 acres and 10 perches; whilst forty years later it was found that nearly the whole of this had been gradually occupied as private property, and all that was left was merely the site of the mosque and rauza, measuring about $28\frac{1}{2}$ yards from east to west, and half as much from north to south, or in all 410 square yards.

The mosque itself (Plate XXIX, 1) is only 37 feet in length inside, with four pillars along the centre and as many coupled shafts in front; and is roofed by six small domes in two rows. In plan and style it bears a very distinct resemblance to Bâi Harîr's on the one hand and to Râni Sipari's on the other¹; and though it is smaller, it does not suffer by comparison with the elegance of the latter. Its present position, however, in a dirty, crowded locality and off the street, has probably tended to its almost complete neglect hitherto,—though its architectural merits ought, long since, to have secured for it a better fate, for it is in various ways a gem of Muhammadan architecture well deserving most careful preservation.

¹ Part I, pp. 84–87, and Plates cvi–cviii; and ante, pp. 6–8.

The façade, as a whole, is perhaps a little crudely managed: the second and fourth interspaces between the front columns, being necessarily narrower than the other three, are occupied by carved balcony windows, about $2\frac{3}{4}$ feet from the ground, projecting outwards and supported on carved brackets; the other three interspaces are quite open as in Rânî Siparî's. This feature of windows in the front was judiciously dispensed with in the smaller trabeate mosques built immediately after the date of this one.

The minarets are slender, in three storeys, and 30 feet in height (Plate XXIX, fig. 2). Whilst ornately carved from base to summit, they differ from the usual pattern in wanting the richly sculptured niches filled with interlaced floral patterns which are so constant on the Gujarât mosques. But close examination of the details of different mosques, of however nearly the same date, manifests in such sculptured work distinct proofs of the independence of taste among the individual architects:—hence the weak mistake of restoring lost lattice patterns in any one building by copying those of another to fill their places.

These minarets are broken at the head of each storey by projecting mouldings supported by carved brackets, and the line of crenellated antefixa or battlements, that crowns the façade, is continued round the minârs.

Inside are three *mihrâbs*, carved with the usual elaboration. Behind them, on the outside, are buttresses—richly moulded in keeping with the details of the minarets and *mihrâbs* (Plate XXX, fig. 2). The *mimbâr* has only three steps, but, as in so many other instances, it may have been altered at a later date. In the back wall also are two windows, each filled in by twelve squares of perforated stonework in varied patterns. Their jambs are ornamented with pilasters and they are crowned by pediments much in the style usual for *qiblas* (Plate XXX, fig. 1).

The domes of the roof, though small, are also carved with much taste, the finest—as usual—being that over the square in front of the central *qibla*, which is illustrated in plan and section on Plate XXIX, figs. 3 and 4.

In front of the masjid, at a distance of about seven yards, stands the connected Rauza or tomb, planned directly from the mosque, and measuring about 22 feet square,—the four pillars in its west face corresponding exactly in spacing with those of the masjid. The twelve pillars of the square are arranged in the usual Indian style so as to support, on the lintels of a regular octagon, the dome—about $18\frac{1}{2}$ feet in diameter inside. The entrance to the tomb is, as almost always, on the south face and is finished in the style of the *mihrâbs*, with perforated panels up each side. The other eleven spaces between the pillars on the four sides are also filled with perforated stonework of great variety of patterns, which is still wonderfully entire (see Plate XXVIII, fig. 2, and XXIX, fig. 1).

Inside are three tombs, of which the central one only is of stone, and the others of brick and plaster. Both mosque and dargâh have been much neglected, and the latter especially has not been kept decently clean.

To the east of this area is a very large underground reservoir or Tâhka. The upper portion is carefully terraced and must formerly have been a favourite place of resort and amusement. On another terrace in the area stands a small building, of comparatively recent erection, used as a school of the Anjuman-i-Islâm for Musalmân boys; the rest of the ground is studded with huts and low houses occupied by poor people.

CHAPTER VI.

SARANGPUR MASJID.

PLATES VIII, XXXI-XXXVI.

NOT far from the Sâraṅpur gate on the east side of the city, and opposite to the minarets of Sidi Bashîr's mosque, is the masjid of Malik Sârang, but which now frequently goes by the name of the Râṇî's or Queen's masjid in Sâraṅpur ward.


It is understood to take name from Malik Kiwâm-al Mulk Sârang, a powerful noble at the courts of Maḥmûd Baiqara and his son Sultân Muzaḥḥar II. He and his brother, also a courtier, were of Râjput extraction, taken as captives and obliged to accept Islâm. About 1471 Sultân Maḥmûd appointed Malik Kiwâm to the government of the Godhrâ district, and in 1480 we find him at the head of a force, joining Imâd-al-Mulk in preventing an insurrection in Aḥmadâbâd; and at the storming of Pâwâgaḍh, November 20th, 1484, he distinguished himself in the assault; whilst in 1490, he was sent with an army to punish Bahâdur Gilânî at Dâbhol in the south Konkan. On the death of Maḥmûd Baiqara, he supported the accession of Muzaḥḥar II to the throne; but under his rule he proved turbulent and violent, though retained in power. In 1513 he was sent to hold Dhâr for Gujarât; in 1517 he behaved notably at the siege of Mânḍû; and soon after, in 1518, he was sent with 'Âdil Khân Âsiri to repel the invasion of Râṇâ Saṅgramasimha of Mewâḍ. In 1520, he was made governor of Aḥmadâbâd, where he ruled arbitrarily, and, with Malik Kotî, he plotted against Malik Husain Bahmani Nizâm-al-Mulk, who held Idar for Gujarât, leaving him unaided when invaded by the Mewâḍ Râṇâ. He is spoken of later in the time of Bahâdur Shâh, as being placed by that Sultân in charge of Diu, in 1528, when he captured a Portuguese ship—making the crew prisoners.¹ He must then have been an old man, and probably died soon after.

Whilst he was governor of Aḥmadâbâd under Muzaḥḥar II, it is most natural to suppose that he rebuilt the *maḥalla* or ward in the south-east of the city which still bears the name of Sâraṅpur, though there is no evidence that he may not have begun the work in the later years of Maḥmûd Baiqara's reign. There he erected the large mosque together with the tomb in front of it which, on completion, must have been among the finest in the city. The tomb is now known as Râṇî Bîbî's rauza,—possibly referring to the wife of Malik Sârang, though this may be doubted; and the epithet has perhaps led to the mosque itself being sometimes called the Râṇî's mosque.

The minârs of this mosque closely resembled in details those of the great mosque at Râjapur²; but about forty years ago, the south minâr was taken down to the

¹ Bayley's *Gujarât*, pp. 171, 193, 203, &c.

² See Part I, Plate lxxxvii, and Plate lxxvi of this.



SARANGPUR MOSQUE, AHMADABAD.

level of the roof by one Fazl 'Alī Himmat 'Alī, who then claimed possession of the mosque and who sold the stones of the minaret.


The north minār, which was still entire, was also taken down by the Public Works Department about fifteen years afterwards, as it was considered to be then unsafe; and as in many other similar cases at Aḥmadābād, no effort was made to restore it, though the scaffolding used to take it down might have been economically used also to re-erect it. That its form may not be entirely forgotten, the accompanying illustration, No. 4, from an old photograph is inserted here.

The masjid measures 147 feet 3 inches in length inside by 36 feet 6 inches deep, and has five larger domes over so many square areas, which are separated from one another and from the end walls by aisles $6\frac{1}{2}$ feet wide between the shafts of the pillars, and also from the front and back walls by two others 6 feet 10 inches wide. In front of, and behind each of the larger domes is a smaller one on the front and back aisles, and the other portions of the roof are flat (Plate XXXI).

In line with the larger domes are five arched entrances in the façade, the central one being the largest and considerably higher than the other four and richly carved on the archivolt—the others being finished with simple mouldings (Plate VIII). Three carved string-courses run along the face of the walls and a fourth just under the eaves, which are double.

On each side of the central arch stand the bases of the minarets, which are all that is now left of them. They are unusually massive and very richly and elegantly carved (Plates VIII and XXXVI, fig. 2). The stairs leading to the roof and gallery are carried up the interior of these towers, and are entered from inside the mosque by doors with neatly carved architraves and arched heads, over which are carved pyramidal fronts (Plate XXXVI, fig. 1).

In the lower niches in front of the minārs are two panels cut with a freedom and taste that recall those in the façade of the Jāmi' Masjid and the panel at Shaikh Farid's tomb at Pattana.¹ They are damaged in parts and suggest the probability that they belonged to some older Hindū building. On Plate XXXIII, fig. 1, is a drawing of the front niche in the north minār, and fig. 2 of that in the south one. The panels on the north and south sides of each minaret are in a



4. MINARET OF SĀRANGPUR MOSQUE.

¹ See Part I, Plate xxxiv.; and *Arch. Sur. Westn. India*, vol. IX., Plate xvi.

very different style and were doubtless carved for the mosque; those of the north tower are represented on the plate in figs. 3 and 4.

The front wall behind the minarets is raised, as in most cases, about $9\frac{1}{2}$ feet above the rest of the façade for a length of 42 feet. This gives room for the high central entrance over which the projecting eaves are supported on carved stone brackets.

Inside, we have not the two usual high columns near the entrance, but on pillars of the usual height rests a breast or parapet frieze running across and returning to the front wall at each end and forming a sort of balcony from the gallery (see the section, Plate XXXII, fig. 1). Under the central dome, and connected with this is a gallery with the usual seat having its *kakshāsana* or back towards the open area under the dome.

The parapet or frieze over the pillars supporting this *kakshāsana* is carved in the usual style, as a rail, and the area of the gallery extends back to the next row of pillars on three sides. These galleries seem to have been a favourite feature of the larger mosques and were doubtless much frequented by the leisured class for conversation and discussion: they are cool and sufficiently retired.

Some of the mihrābs are plainer than in many of the other mosques, and the central one has a flat back, but the arch and inner architrave are ornamented by stones of different colours let into them; but it has been reft of the marble slab that commemorated the builder and the date of completion. The bay of the roof in front of this *qibla* is carved with a pretty rosette having a central pendant. The mihrābs on each side of the central one, are much richer in carving, as may be seen from the representation on Plate XXXIV. They have circular backs; and the end ones have square backs and are quite as richly carved. The mimbār or pulpit is in the general style of that in Ahmad Shāh's mosque, but the canopy has been carried off.

The interiors of the larger domes themselves are plain, the smaller ones are carved with leaf patterns. The only portion of the floor that is of marble is that under the central dome.

In the front wall are four perforated windows—each divided into twelve squares filled with a variety of patterns symmetrically arranged. These do not require description, as they are represented, though on a small scale, on Plate XXXV, figs. 1-4. In the back wall also are six windows and two in each end, of which Plate XXXII, figs. 2 and 3, present those in the south end as seen from inside.

Though constructed on a large scale, and with a very considerable amount of ornamental detail, this mosque is somewhat heavy in style and shows little if any advance on those erected during the first quarter of the fifteenth century.

The tomb, like those of Rāṇī Siparī, Sayyid 'Usmān and others, is right in front of the masjid at a distance of 26 yards, and stands on a base $74\frac{1}{2}$ feet square (see Plate XXXI). It must have been a splendid mausoleum when entire—one of the finest in the city. On each face $19\frac{1}{2}$ feet from the corners was protected by walls, the outer face of which has now been all torn off, and the interspace was divided by four pairs of coupled pillars, as in the façade of Rāṇī Siparī's masjid. Inside, the area is 67 feet

5 inches square with thirty-six pillars and pilasters, about 13 feet high, supporting the roof. Within this the second series of columns numbers twenty-eight round the square, the third is necessarily of twenty shafts, and within this again a square of twelve, measuring 18 feet 4 inches inside the pillars, and supporting the central dome over the octagon formed by lintels resting on them. This central square had its entrance on the south side and was once surrounded by trellis-work screens between the shafts—now nearly all carried off or destroyed.

The square of twenty pillars rises through the roof on short upper pillars that enclose a gallery surrounding the central dome, and the area—about 38 feet square—is covered by this dome with four smaller ones at the corners. The two tombs under the dome have been robbed of their carved marble coverings.

The mosque has long been entirely disused; the open space between the masjid and *rauza* is utilised for drying cow-dung cakes for fuel, spinning silk, preparing rice, &c., and the interior of the *rauza* is full of rubbish, and—together with the masjid—was long kept in a condition that is disgraceful to the Muhammadan Panchâyat having charge of it.

CHAPTER VII.

THE RANI RUPAVATI MASJID AND TOMB IN MIRZAPUR, KNOWN AS
THE QUEEN'S MOSQUE.

PLATES I, IX, XXXVI, 3, AND XXXVII-XXXIX.

THE Mirzapur Masjid is one of the most beautiful mosques in the city, and stands on the main street leading from the Karañj northwards to the Dehli gate. Its minarets fell from the earthquake of March 1819, and no drawing or view of the mosque, while it was still undamaged, has come down to us.

It is said to take its name from two ladies of the royal household who were buried in the adjoining Rauza, but in whose reign they lived or what the exact date of the masjid is not on record. The *Bombay Gazetteer* (vol. VIII, p. 278), says that it was built probably in the latter years (1430-1440) of Sultân Aḥmad's reign; but there seems no record on which to base such a statement; architecturally it certainly does not belong to an earlier date than the reign of Maḥmūd Shāh I, and not improbably to that of Muẓaffar Shāh II (1511-1526).

Comparing its ornamental details with those of Bibi Achut Kuki's on the one hand, and of the Rāñi Siparī's on the other, we must feel that it is later than the former (A.D. 1472), though possibly not quite as late as the latter (A.D. 1514). It belongs to that mixed style or combination of the arcuate brought in by the Muhammadan conquerors, with the trabeate which the Hindū workmen manipulated with such success. During the reign of Maḥmūd Shāh I, both styles were prevalent side by side; and in the mosques just noticed we have some of the best surviving examples of the trabeate Hindū style. In this mosque, however, we have a fairly successful combination of the arch and lintel (see Plate I).

Over the walls it measures 103 feet in length by 46 feet from front to back, and inside 93½ feet by 36½ feet (Plate XXXVII). The roof has three large domes, and the façade has a wide arched entrance opposite the central and higher one, flanked by the minarets, and smaller entrances—also arched—opposite the other two side domes. These secondary entrances have balcony windows on each side, and again a lattice window near the ends of the façade. In the back wall are also four lattice windows, with two others and an open balcony one in each end.

Each of the three domes is supported by twelve pillars arranged in squares, which leave a passage or aisle along the front, back and end walls, as also between these squares. The domes are each 19 feet wide at the lintels of the octagons on which they rest. In front of, and behind each of these are small domes, as also at the ends of the mosque, whilst the other small spaces are roofed in the ordinary way, by flat stones cutting off the corners of the squares, so that the remaining space can be covered by one square flagstone.

As in other mosques of the style, the central part of the façade, for about 46 feet in length, is raised considerably above the general level of the rest of the roof, making room for the great central arched entrance, and at the same time screening off a clerestorey by means of which some light is admitted under the central and highest dome covering the gallery. This gallery—the parapet of which is richly carved—surrounds three sides of the area, and the pillars within the entrance are carried up through the second storey, a height of 18 feet, to above the head of the central arch. They are in plan six pointed, and the adjoining faces are at right angles to one another, so that there are six re-entrant angles between the points of 150° each. They have very carefully carved bases and cinctures at four different heights and carry a carved frieze (see Plate XXXVII, fig. 2).

The gallery is roofed over to the next line of pillars, about 8 feet beyond those of the dome; but the trellis-work between the outer pillars is now wanting. It is reached by the stairs that lead up from the jambs of the entrance and turn into the minarets. They are narrow and dark with awkward turnings.

The minârs—though the turrets above the façade wall have now totally disappeared—are still remarkable for their richness of decoration (Plates I and XXXVI, fig. 3). Every detail is ornamented, and the niches on the face and sides are varied and beautiful; indeed, the ornamentation of all the parts of this mosque is striking in its delicacy.

As Mr. Fergusson well remarked¹—"perhaps, after all, the greatest beauty of this mosque is to be found in its details, especially in that beautiful form of tracery which fills the niches of the minarets. In every Jaina or Hindû temple there always is on each face and on each storey a niche which is occupied by a statue or group indicative of the worship to which the temple was dedicated." Images, however, the Muslim could not tolerate, "but as the niche was there and the Hindû architects did not know what to substitute in its place, they retained it, but filled it with tracery, sometimes pierced to form a window, sometimes blind, as a mere ornament. Generally these were drawn with so free a hand, and at the same time so gracefully, that they form the most beautiful details, taken singly, in Ahmadâbâd. All are different, not only in detail but often in character." Two examples of these niche ornaments are given in detail on Plate XXXIX, figs. 3 and 4 and a third on Plate XLIV, fig. 2.

The same elaboration is bestowed on the windows as on the minârs. The balcony windows project from the wall, and are supported by most elaborately carved brackets under the sills—the outer faces of which are covered with sculptured foliage, as are also the lintels. The other windows are smaller, framed in sculptured mouldings and filled with perforated lattice-work in every variety of pattern, usually arranged symmetrically (see Plate XXXVIII, fig. 1).

In the back wall, opposite each of the three domes, which are carved inside, is a *qibla* or *mihrâb*² of white marble with an enriched pediment. These *mihrâbs*

¹ Hope and Fergusson's *Ahmedabad*, p. 85.

² For the origin of the *Qibla* conf. *Muhammadian Archit. of Gujarât*, vol. VI, pp. 26, 37; *Qoran*, sura ii, vv. 136-143; and Osborne, *Islâm under the Arabs*, p. 58.

are very elegant and not at all overlaid with ornament: the central and richest one is represented on Plate XXXVIII, fig. 2. The rosette in the back and the lamp hung from it by chains, is a survival and fully as prominent here as usual.

In the floor in front of the central *mihrâb* is laid a slab of black marble measuring about 5 feet 6 inches by 2 feet 9 inches, the head of it rounded and entering the recess of the *qibla*. The backs of these *mihrâbs* in this masjid are square. Outside, on the back wall behind them, are the usual moulded and carved buttresses, on which much attention was always bestowed.

The mimbar is ascended by a steep sandstone stair on the north or right side of the principal *qibla*, but the canopy over it is gone. The roof, in the back aisle, in front of the central *mihrâb*, is covered by an octagonal slab beautifully carved as a *patera* and resting on four corner pieces. The illustration (Plate XXXIX, figs. 1 and 2) will better explain the design of this than any description and may render such superfluous.


To sum up, we have, in this mosque—to use Mr. Fergusson's words—"an attempt to combine the Muhammadan arcuate style with the Hindû trabeate architecture; and although the architects had got over much of the awkwardness that characterised their earlier efforts in this direction, they had not yet conquered them. There is, for instance, a very disagreeable contrast between the extreme richness of the minarets on each side of the central arch and the extreme plainness of the arch itself. The richness of the cornice above it adds to the discordant effect. These parts the Hindû architects could manage perfectly; but how to adorn an arch they did not know, and, strange to say, never learnt. Perhaps it may be said that the building gains in majesty and variety of outline what it loses in unity, by the introduction of these contrasts, and to some extent this is no doubt true."

The tomb or *rauza* belonging to this masjid stands on the north-east of it, upon a low platform 40 feet square, and has a verandah or corridor round it supported on twenty pillars having a small dome over each corner, with some neatly carved arabesques in the spandrels of the squares which they cover. Within these is a square of twelve pillars which supports a frieze rising above the roof of the verandah and supporting the principal dome of the tomb. This wall is prettily carved inside with square panels of geometric patterns and bands of frets (see Plate IX).

It is a similar structure to the tomb of Râqî Sipari, "but the architect has seen the defect in proportion pointed out in speaking of that one, and lowered the base of the dome so as to bring it more into harmony with the basement storey of the building."¹ All remains of a screen of perforated lattice-work between the pillars of the inner square have long since disappeared, except a base for such along the east side.

The tomb in the centre of this was of white marble, but of the original structure only the side panels now remain, carved with the usual ornamentation of lamps hanging from chains. The upper portion has been repaired in stone.

¹ Part I, p. 87; and *Ahmedabad*, p. 86.



TOMB AT RANI RUPAWANTI MOSQUE IN MIRZAPUR.

On the west side are the remains of another marble tomb, much dilapidated—only one marble slab of the original remaining.

In 1824, the City Survey shows a ground area for the site of this mosque and tomb, of 4438 square yards. Forty years later it was only 2376 square yards, 754 square yards having been taken up for roads, 83 as belonging to government, and the remaining 1225 occupied as private property. About 1850 we learn that what ground then remained on the north side, between it and the Traveller's Rest-house, was bought or taken up by Mr. Leonard Hykoop, head clerk in the Ahmadâbâd Adâlat, who built a house on it, the walls of the enclosure round the platform of the masjid being utilized in the erection of outhouses.¹ The place is in charge of Musalman butchers, who live about the place and occasionally hold services in it. It was repaired about twenty years ago by the Public Works Department at an expense to government of about 1529 rupees.

¹ J. F. Fernandez in *Crawley-Boevey's Scheme*, App. p. xxvi. The same gives the area in the City Survey 1863-67 as 2376 sq. yds. at p. xxv, but as 2990 sq. yds. at p. lxxxiv. The former agrees closely with the measurements of the plan (Plate xxxiii.)

CHAPTER VIII.

FATH MASJID; GUMTI, KOCHRAH, AND IBRAHIM SAYYID'S MASJIDS.

PLATES X, XL, XLI, XLII.

IN the Daryâpur mahalla, in the north end of the city, between the Dehli and Daryâpur gates, is a large desecrated mosque, now usually called the Phuti masjid as being in decay but which is said to have been originally named Fath. It is of considerable dimensions,—116 feet in length inside by about $26\frac{1}{2}$ feet deep from inside the front pillars to the back wall. The whole façade is open, supported by eighteen pillars, and it has on the roof five domes. The area covered by the central one is separated from those on each side of it by a double aisle: the two at each end stand close together. The structure is undated, but may with considerable certainty be placed in the first quarter of the sixteenth century or at the very end of the preceding (Plates X and XL).

The pillars have high square bases, and are themselves square to about half their total height, above which the corners are chamfered off, making the upper portions octagonal. All the seventy free standing pillars and twenty-eight attached to the walls as pilasters are very plain,—except eight that must apparently have been taken from some Hindû or Jaina temple. The minarets are slender, 25 feet high, in three storeys, and with scarcely any carving upon them except the continuations of the three string-courses of the end walls: like those on the Râni Sipari Mosque, they are not minarets in the proper sense, being solid pinnacles without any stair for the mu'azzin to ascend. In mosques of this type he could only have called the azân from the corner of the mosque, and in the smaller masjids this was usually done by the Imâm or leader of the prayers.

The *Mihrabs* are of three styles: those at the ends unusually plain—with little more than moulding ornament; the intermediate two are considerably richer; and the chief or central one—of a peculiar pattern, unlike those in other masjids—is very richly carved. The last is the only one having a buttress behind it, on the back of the structure (see Plate XL).

The pavement—judging from what little remains near the north end—seems to have been of marble, but it has nearly all been removed.

In the back wall are two windows, the perforated work of which is rapidly disappearing; and in each end is a projecting balcony window supported on carved brackets.

Opposite to the masjid on the other side of the *hauz* or cistern is a Rauza of the general form, the dome being supported on twelve well-carved pillars and richly carved inside. It is entirely neglected.



FATHI MASJID, AHMADABAD.

The area belonging to this masjid is 2231 square yards, but a large portion of the ground has been encroached upon, and the small space that is left to it is used by carpenters who work there and have done much damage. The premises have been for long greatly neglected and are kept in a dirty condition. The well originally belonging to this mosque, which now goes by the name of Sultân Ahmad's well, is some sixty yards away, near the city wall and beyond the present limits of the area.¹

ÎSANPUR GUMTI MOSQUE.

Other three mosques of similar style and probably of about the same period may be here noticed. The first is at Îsanpur, a village about three miles south from the Astodiyâ gate of the city, or nearly a mile and half beyond Shâh 'Âlam, and almost two and a half miles N.N.E. from Baṭuvâ. The road to it from Shâh 'Âlam skirts the east side of what was the original embankment of the great Handôlâ tank. The village is now held as an Inâm belonging to the head of the Shâh 'Âlam establishment.

This Îsanpur mosque is a small deserted one that seems to have no distinctive appellation, though sometimes called the Gumti mosque. It is situated close by the Jeṭhâbhât-Jivanlâl Mulji wâv or step-well.

It is open in front, like the preceding, the façade having four pairs of coupled pillars in front, with other four single pillars along the middle of the floor (see Plate XLI). These support the roof of two rows of three domes each with two flat-roofed spaces between.

Inside are three *qiblas*, originally carved in the richest style, though now much defaced, and the dedicatory inscription slab torn from its place over the central one. In plan, two of these *mihrâbs* are nearly semicircular and the central one is oblong. The usual ornamented buttresses on the outside wall at the back are wanting—their places being only indicated on the base.

In each of the end walls is an arched door and a window, and in the back wall are two windows—most of the stone lattice-work that once filled them being now broken away. The pavement was being gradually carried off in 1885; and the north-west corner of the structure was also falling into disrepair.

The minarets are solid turrets, like the other examples of this class, but are carved more elaborately, and are of a different style from any others in Ahmadâbâd—nearly every inch of their height has been overlaid with sculpture and mouldings to an extent that perhaps detracts from their elegance. They rise to a height of 27 feet, but the finials seem to be wanting, if not the upper portion also of the pinnacles.

PÂLDI KOCHRAB MASJID.

Closely akin to the last in plan and style is a small but elegant mosque on the south of the little village of Pâldi Kochrab, across the river from Ahmadâbâd, and

¹ Crawley-Boevey, *Scheme*, App. p. xxxiv.

standing on Government Land.¹ It is locally known as the Râñî's Masjid, but seems also to bear the name of Bâwâ 'Alishâh's, though it is not ascertained who the founder was, and the inscription slab having been carried off from over the central *qibla*, we have no means of learning its precise date (Plate XLII, fig. 1).

It is even more dilapidated than the last, only the basement storey of the south minaret is left, and one storey above the roof of the north one; the antefixa that



5. MOSQUE AT PALDI KOCHRAB FROM THE SOUTH-WEST.

ran along the façade over the eaves have been of very varied patterns, but are also largely gone. The interior is 37 feet long and 9 feet from the front of the pillars to the back wall. There are no pillars inside, only four in the front, and the corresponding pilasters; but these pillars are of very elegant proportions and have projecting brackets against the capitals in the front to support the projecting eaves (Plate XLII, 2).

As in the Īsanpur mosque, there are three domes, one at each end and one in the middle, chastely carved inside, the two interspaces being flat-roofed. The three *qiblas* are very

carefully finished, the central one being, as usual, the larger, though hardly differing in other details; the supporting buttresses behind these are also models of rich and beautiful carving. The illustration No. 5 shows the south end and back wall of the mosque, which has been quite recently repaired.

Of the north minaret, the two storeys of the original height that still remain show that they followed pretty closely the pattern of Râñî Siparî's.² The balcony windows in the end and back walls, supported on carved brackets, are also very richly ornamented and increase the correspondence in details with the same mosque, and with Shâh Khub's. The two windows in the back wall were filled with perforated stonework, but the original was almost completely destroyed, and recently restored in the usual way. Altogether, when entire, this small mosque must have been one of the prettiest and most attractive in or near the city.

BÂWÂ FAİZULLAH'S MOSQUE AT KOCHRAB.

At Kochrab there is also another mosque and tomb, known as Bâwâ Faizullah's. They stand on a mound in an area of 9,800 square yards surrounded by a wall with an entrance on the east side. The Rauza is domed, and has four carved clerestorey

¹ In the *Revised List of Antiquarian Remains*, pp. 78-83, Nos. 101, 102, and 104, these interesting Mosques have been unfortunately classified as unnecessary to conserve. No mosque in Ahmadâbâd, on so small a scale as that at Kochrab, shows more elegant workmanship.

² See Part I, Plates x, cvii.

windows. Bâwâ Faizullah was a Sayyid of the family of the Imâm Shâh of Pirâna in the fifth or sixth generation, and was buried here with his wife. The tombs are of brick and lime and have a canopy over them. Connected with the Rauza is an open masjid without a roof; in front it has four plain arches and two low plain minarets. The Rauza is well cared for, whilst the masjid is neglected.¹

IBRÂHIM SAYYID'S MASJID.

The third masjid of the trabeate style to be noted here is that of Ibrâhim Sayyid or Shahîd (martyr)² which, with the connected *rauza*, is at Kangalpuri, in the village area of Râjapur Hirpur, on the way from the Astodiyâ gate to Shâh 'Âlam and north-west from the Kânkariyâ Talâv (Plate XLII, 3). This mosque, in size, plan and detail, is an almost exact copy of the Shâh Khub masjid already described.³ It is much dilapidated, but repairable. The minârs are solid and 32 feet high, in three storeys and almost perfect. The panels or niches in the minârs are filled with beautifully carved foliage, of which an example from the south side of the south minâr is represented in detail on Plate XLIV, fig. 1.

The open façade has six pillars, nearly equally spaced, and inside are other two rows of the same number—the total length being 68 feet inside by 31 feet deep; and the roof is covered by three rows of seven domes each. One of the beams in the roof having cracked, two supports of brick and mortar have been inserted. There are three *qiblas* in the back wall, of sandstone—which perhaps accounts for their still being left, though the inscription slab in the tympanum of the central *mihrâb* has long since been removed. In the back wall were four windows—one of them behind the *mimbar*—but the lattice-work has disappeared from all of them, except in that next in the north end. In the end walls are carved balcony windows supported on brackets. The floor has been entirely denuded of its pavement.

The Rauza is plain, the dome resting on twelve pillars, but the pavement has been dug up and the *qabr* or tomb totally removed. To the north-east of the mosque, in the area where the faqîr lives who claims to be the owner of the masjid, stands a brick tomb on a platform, well cared for, and under which Ibrâhim Shahîd is said to have been buried. It is shaded by a canopy painted yellow, green and red, and the shrine is much venerated by the Musalman community. "Legend states that the position of the tomb changes by the length of one rice grain every year: and to have already moved some three yards from its original position."⁴ Without such an indication we need have no difficulty, on architectural grounds, in ascribing the building to about the middle of the sixteenth century.

Graves in front of the mosque indicate that burials have taken place up to the very entrance.

¹ J. F. Fernandez, in Appendix to Crawley-Boevey's *Scheme*, p. lxxii.

² Whilst *shahîd* properly means a "witness" or "martyr," it is applied to any Muhammadan killed in battle or slain unjustly, and besides to any who die suddenly or of malignant disease, or in a foreign country or even on Thursday night.

³ See Part I, pp. 82-83; and Plates lxxviii and cv.

⁴ J. F. Fernandez, in Crawley-Boevey's *Scheme*, App. p. lxxvii; also p. xiii.

CHAPTER IX.

ISANPUR MASJID AND RAUZA; SHAH 'ALIJI KAMDHANI'S,
'ALIF KHAN'S MASJIDS, &c.

PLATES XI, XXVIII, FIG. 3, XLIII, AND XLIX, FIGS. 1-3.

JUST outside the hamlet of Īsanpur is another mosque bearing the name of 'Imād-ul-Mulk Malik 'Īsan. He was one of the great nobles in the court of Maḥmūd Baiqara and of Muẓaffar II, having the title of Nizām al Mulk, and, as the *Mirāt-i-Sikandarī* informs us, he built Īsanpur—"Between Baṭuvā and Rasūlābād, which is one of the most beautiful suburbs of Ahmadābād," and the author further adds that "Shāh 'Ālam used to call it 'Blessed on both sides,' because it had Baṭuva to the south where is the tomb of the saint Quṭb al Kitāb, and Rasūlābād on the north, where was the house, and afterwards the tomb, of Shāh 'Ālam."¹ Here Malik 'Īsan built his dargāh and the accompanying fine masjid, planted groves of Mango and Rāyana trees near it, and made a tank to the east of it.²

Whilst this mosque differs considerably in conception from the other Ahmadābād mosques, the general plan is a copy of that of the Jāmi' masjid, though on a smaller scale, and a comparison with that of Dastur Khān will suggest some analogy. The masjid is at the west end of an oblong court surrounded by a corridor with the tomb—as in the case of Sayyid 'Usman's, Malik Sārang's, and others—placed right in the middle of the court, in front of the mosque, and having its columns arranged in lines corresponding with those of the masjid (see Plates XI and XLIII).

The court, with its corridors and mosque, stands on a raised masonry platform 107½ feet from north to south by 138 feet from east to west, and has outside porches as at Dastur Khān's, at the entrances on the east and north sides, each approached by nine steps.

The Masjid occupies the west end of this area and is 59 feet in length over the end walls and 34 feet in depth, but has at each end a wing, standing back and extending to the limits of the platform, and each wing is covered by a dome, not so high, but of the same size as the central one on the mosque. The outward thrusts of these domes are met by pairs of coupled pillars on the north and south sides.

¹ Bayley, *Gujarāt*, p. 237, writes 'Ainpurāh, and calls the founder Malik 'Ain, but this is certainly a mistake, probably due to a fault in the MS. used; for there can be no question that Īsanpur is meant. "The description of the beauties of 'Ainpurāh" is unfortunately omitted by Sir E. C. Bayley in his version. It is much to be regretted that we have not yet a complete version of so valuable a work as the *Mirāt-i-Ahmadī*, which would throw so much light upon the whole history of Gujarāt.

² It is probable, though difficult to determine with certainty, that the "Malik 'Ain al Mulk," mentioned a little later in Bayley's extracts from the *Mirāt-i-Sikandarī* as Nizām al Mulk and governor of Pattan about 1512, who was defeated by the Rājā of Īdar, was the same person. If so, he was with Muẓaffar II during his invasion of Mālwa in 1513, and defeated the Māndu troops who attacked him on his way from Nālehā. Bayley's *Gujarāt*, pp. 249, 251-2.



ISANPUR MASJID, NEAR AHMADABAD.

The area in front of the mosque is nearly square and is surrounded on the three remaining sides by an open corridor or piazza 12 feet wide, with small domes and flat roofs over alternate spaces between the pillars. Entrance porches on the north and east sides lead into the corridors, which also run into the north and south wings of the mosque.

The enclosure within the corridors measures $84\frac{1}{2}$ feet wide by $92\frac{1}{2}$ feet in length, and in the centre of it stands the domed rauza or dargâh, 39 feet square, constructed on the usual plan, the roof being supported on two concentric squares of columns—the outer of twenty and the inner of twelve, so arranged that eight of the latter form a regular octagon, on which the central dome rests. Round it—at the outer corners and middle of each side—are eight small domes. And while the arrangement of the columns of the dargâh corresponds in their spacings with those of the mosque, the corridors on the north, east and south sides are also made to agree with those of the tomb.

Inside the dargâh there appear to have been two high *qabrs* or tombs, covered with marble, but they have been destroyed, and now there are at least seven graves under the roof of the *rauza*. The floor has also been torn up and carried off.

This masjid has a distinct architectural character of its own. It has no minarets or access to the roof for the *mu'azzin*, since, being a small and private or family mosque, the *azân*, or summons to prayer, would be given by the imâm or leader of the devotions, whoever he might be,—even a member of the family.

The façade is supported on six coupled pillars with shafts about $15\frac{1}{2}$ inches square—the two spaces at the ends and that in the middle being each 7 feet wide, and the intermediate ones 4 feet 4 inches. These three openings have pointed arches rising higher in the façade than the side wings, which are trabeate. The central arch is cusped, and the pillars on each side of it are carried up in front of the wall.

Behind the façade a passage 7 feet wide runs the length of the mosque, opening through arched doorways at each end into the corners of the court. In the middle of the mosque, as usual, is a domed area 18 feet square: the pillars round it are square to about half their height, with sections of eight and sixteen sides, then round to the capitals, which are more like the Hindû type than the usual Muhammadan. Over the architrave upon these, is a triforium filled in with large panels of geometrical trellis stone-work. This rises to about 18 feet from the floor, where the corners are cut off and the area is covered by the large dome which is carefully carved inside with a neat pendant from its apex. On the flanks of this only the central squares on each side rise to the same height and are covered by smaller domes, whilst a third small dome covers the middle space immediately behind the façade. The rest of the mosque roof is flat (Plates XI, XLIII).

Inside were once three very ornate *qiblas* or *mihrâbs*—in line with the three domes—but the central and finest one, which most probably had a historic inscription over it, has been torn out and removed for the sake of the marble.

There are four windows of perforated stone in the back wall and three in each

end looking into the domed areas that flank the mosque. Twenty years ago most of these windows were in fair preservation.

In this whole structure there is a unity and compactness of design and an adaptation to its proper purpose as a private chapel that rank it with the best of the Muhammadan remains in Gujarât. It is not so elaborately carved as Muḥâfiẓ Khân's in the city, but the façade is elegant in the tasteful application of the ornament to its structural features. It belongs, as we may confidently assign it, to the first quarter of the sixteenth century.

It is much to be regretted that it has been hitherto so utterly neglected. The flooring has been largely torn up and destroyed for the sake of the slabs: much of the coping of the façade is gone: and the whole area is overgrown with weeds.

The tank mentioned by the chronicler is in front of the east entrance, but is now quite dry.

SHÂH 'ALIJĪ KÂMDHANI'S MASJID AND RAUZA.

In Râyakhâd-Rohilawâd ward are three sites of which a word may be said in passing. They are to the west of the street leading south from Kâmashâh's chakla to the Jamâlpur ward.

Nearest to the road is Shâh 'Alijī Kâmdhani's masjid and *rauza*. The *rauza* is of stone, standing on a square basement, and its walls are pierced with rows of stone windows—the beauty of which is now for the most part hidden under a thick coat of whitewash. Inside, under the dome, is the tomb of Shâh 'Alijī Kâmdhani, who was a grandson of Sayyid 'Abdur-rahîm, a descendant of Sayyid Aḥmad Kabîr, whose *urs* falls on the 14th of Shawwâl. He died on 14th Jumâdâ'l awwal, 973—(Friday, 7th December 1565). The ground all round is studded with graves, and the area must at first have been very extensive.

In the City Survey of 1824 the area belonging to this mosque and tomb is stated at 23,262 square yards or nearly five acres: it is now limited to 627 square yards—nearly 4000 having been taken possession of and since claimed as private property, whilst over 9500 were declared liable to summary settlement, and other portions taken up for roads. The mosque now attached is quite a recent structure, to the west, and of no pretensions whatever. In front is a small *hauz* for water.

'ALĪF KHÂN OR BÂBĪ MASJID AND TOMB.

To the west of this, at a distance of about 60 yards, is Alif Khân's masjid, also known as Bâbî's masjid, and between the two still stand the remains of two arched gateways of stone. It was a stone mosque; but its roof and all the pillars except one have been removed: only the walls and minarets remain.¹

¹ I learn from Rev. G. P. Taylor of Ahmadâbâd, that the tomb between this and Shâh 'Alijī Kâmdhani's masjid, to the East, is known as 'Alif Khân's tomb.

In the back wall are three *qiblas* each with an inscription over it, that upon the south *mihrâb* ending with the words—"the year nine hundred and sixty" or A.D. 1553, and that over the north one indicating that it was completed in the reign of Aḥmad Shâh [II], cousin of Maḥmûd Shâh [III], son of Laṭif Shâh, the brother of Bahâdur Shâh, &c.¹ Of course we know that Aḥmad Shâh [II] was not of the blood royal, but was placed on the throne as a son of Aḥmad Khân, a brother of Maḥmûd Shâh [III], who had been Governor of Aḥmadâbâd. He began to reign in 1564, apparently before the mosque was completed.

The *mihrâbs* are plain but neat: one is represented on Plate XLIX, figs. 1-3; and the minarets, though with numerous mouldings on the lower storey, or up to the level of the roof, are simply slender round pillars 15½ feet in height with two cinctures round their shafts and a moulded finial. One is represented on Plate XXVIII, fig. 3.

Between this mosque and Shâh 'Alijî Kâmdhani's and quite close to the latter, stands Alif Khân's tomb. It is not enclosed and has partly crumbled away.

SHAH GHAZNI'S MASJID.

To the south of the last and south-west of the other, at a distance of 120 yards, is an old enclosure measuring 3380 square yards which sometimes goes by the name of the masjid of Shâh Ghaznî and contained the tombs of Shâh 'Alî, Izat Khân, and Shâh Ghaznî. The mosque has entirely disappeared, but the Tâṅka and the gateway of the enclosure remain; the Rauza is a ruin, but the tomb is left. There is here also Lâdle Pîr's rauza of brick in pretty fair condition. The ground is largely covered with graves.²

¹ *Lists of Antiq. Rem.* pp. 251 and 252; or *Revised Lists*, pp. 297, 298.

² Conf. J. F. Fernandez, in Appendix to Crawley Boevey's *Scheme*, p. xlix.

CHAPTER X.

QUTB AL AULIYA SHAIKH ḤASAN MUḤAMMAD CHISHTI'S MASJID IN SHAHPUR, AND BABA LULU'S MASJID IN BEHRAMPUR.

PLATES XLIV–XLVIII, AND LIV, LV.

THE mosque of Qutb al Auliya Shaikh Ḥasan MuḤammad Chishtī is in the north of the city, within about a hundred and eighty yards of the Shāhpūr gate. It is the “Shāhpūr Mosque” of Hope, and must not be confounded with one standing a little to the north-west of it, which, in the City Survey, is styled “the Shāhpūr mosque.” This is owned by the descendants of Shaikh Ḥasan MuḤammad Chishtī, for whom it was built and whose descendants are the hereditary Qāzis of the Shāhpūr division of the city.

Over the central *mihrāb* is a short inscription written by Dost MuḤammad Sakhar, whose name is engraved on the intersection of the fillets that separate the lines vertically and horizontally by a cross.

It states that “the pole (*qutb*) of the age—Shaikh Ḥasan—built this masjid, that in it pious people might pray for the Shaikh. When he erected this noble edifice, the date of it according to *Fidā* was *bnai shaikh*.” This *abjad* stands for A.H. 973, corresponding to 1565–66. It may have been begun in A.H. 964, as a Persian manuscript assigns its erection to that date.

Since Shaikh MuḤammad Chishtī died in 1574, at the age 59, and Akbar had invaded and subdued Gujarāt only two years previously, it was probably owing, partly at least, to the disturbed state of the country previous to that event, that the construction was arrested and the minarets raised no higher than the end walls of the mosque; or, want of means may have stopped the work.

His son became Qāzi of this section of Ahmadābād, and the office has since been hereditary in his family. The present Qāzi has the dignity of *Pīrzāda* or spiritual guide to several nobles in the Haidarābād and Baroda territories, but he does not appear to be in easy circumstances, and does nothing for the upkeep of the mosque. The area adjoining it has been occupied by private houses, and what is now assigned to the mosque in the City Survey is only 1881 square yards; within this is also the shrine of Rashīd Miyān Pīr, for which the Māmlatdār's treasury makes a cash allowance of two rupees per annum.¹

The interior dimensions of this masjid are 59 feet in length by 38 feet deep; and to plan the arrangement of the columns for such an area, a square of twelve columns was formed in the centre, 19 feet 4 inches across inside the shafts,—the middle pair on the east side being 8 feet 8 inches between centres and the others 6 feet between centres. This fixes the lines of the pillars longitudinally; and transversely; aisles 6½ feet wide flank each side of the central square and run along

¹ Crawley-Boevey, *Scheme*, &c., p. 23.

the front, back, and end walls of the mosque, leaving the second from the end 7 feet 3 inches wide, or the same as the central cross aisle. The twelve pillars of the central square are arranged in the usual way, so that by the lintels it is readily converted into a regular octagon to support the dome (Plate XLVI). Including the twenty pilasters against the walls, there are fifty-six shafts in all. The close resemblance of this plan to that of Bâbâ Lulûi's (Plate LV, fig. 1) will be at once remarked.

The pillars of the façade support nine Saracenic arches; and over the five central ones—crossing the whole depth of the building—is a second storey, consisting of an outer verandah, within which are the upper tier of pillars supporting the dome. The interspaces between these are filled with a rough sort of lattice-work—perhaps meant originally as a temporary expedient. This upper verandah has a screen richly carved on the front (Plate XLV) and providing a seat on the inner side; but the sloping back-rest upon it has either fallen away or had never been fixed. Over the central entrance this screen was broken by a small balcony projecting on carved brackets. The frieze or screen with its balcony contributes largely to render the façade at once simple and chaste, whilst, when complete, it must have been of great elegance. It is, as remarked by Mr. Fergusson, a very happy attempt to combine for mosque purposes, the pillared style with a certain amount of arcuation.

The minarets, so far as executed, are exuberantly rich in their carvings: in this respect, indeed, they are among the most elaborate in Gujarât, and the traceries of the niches have attracted much attention, as surpassing almost all others. They are frequently copied in wood for articles of richly carved blackwood furniture, and formed the first models for an industry in this way almost special to the city.

A few of these niches are illustrated in the plates. Plate XLVII, fig. 2 represents the lower niche on the front of the south minaret, and fig. 4 the niche above on the same face. Often the upper niches in the minarets are much smaller than the lower ones; but in this mosque they are of the same size. Fig. 1 represents the lower niche on the north side of the south minâr, and fig. 3 the lower panel on the face of the north minâr, whilst on Plate XLVIII, fig. 5 and fig. 7 are drawings of the lower and upper niches respectively on the south side of the north minâr; and figs. 6 and 8 are two others also from the same minâr. All the other niches would have been equally deserving of representation had the limits of this work permitted. And what still remains of the perforated lattice-work in the windows as well as the *mihrâbs* is artistically worthy of representation.

In the north and south walls are balcony windows similar to those in Muzaffar Khân's, Râni Sipari's, and other mosques. These are always quite open to the light. And in the back wall are four lattice windows, with three richly carved *mihrâbs*—very shallow—and backed on the outside by richly carved buttresses.

BÂBÂ LULÛI'S MASJID.

This once fine mosque is in the village lands of Behrâmpur, about a mile south-south-west from the city. From certain resemblances to the mosque of Qâzî Hasan Muḥammad Chishtî in the Shâhpur quarter of the city, it has been assumed that it

belongs to about the same date. But, whilst the Shâhpur Masjid has manifestly controlled the design, this one might possibly belong to a later period. This is suggested by the minor details more than by the general style, and if the central dome—now without finial—is deficient in dignity for its situation, the harmony between the centre and wings renders it on the whole a more pleasing structure than the Shâhpur mosque. The want of the whole of the upper portions of the minarets detracts most seriously from the effectiveness of the design: whether they were ever built is long since forgotten.

Bâbâ Lului or Laulvi, also called Bâbâ Muḥammad Jâ'far, is said to have been a pearl-merchant of the seventeenth century; but if he is to be reckoned among the "twelve Bâbâs" commemorated by the Gujarât Musalmans, it seems not improbable that he may have lived at an earlier date, during the second half of the sixteenth century, or as a contemporary of Shaikh Ḥasan Muḥammad Chishtî.

An area of nearly three and a quarter acres belongs to the mosque and tomb, and is reckoned as government waste land, whilst the sum of three rupees is paid to a Muhammadan for lighting on proper occasions. His 'urs or anniversary falls on the 2nd Muharram.

The building was damaged by the great flood of 1875, but at a much earlier date brick walls were built at the north and south sides of the court cutting off the larger portions of the minarets which at first must have stood entirely within the court, and this very seriously spoils their appearance: it would be of great advantage if these could be removed four yards or so beyond the minarets. The original entrance, now inaccessible, was by a domed pavilion on four pillars.

The masjid measures inside 69 feet in length and 37 feet deep from the front of the flooring, and is arcuate in the open façade but trabeate in the interior and has one large central dome, with three smaller ones across near each end. There are nine Saracenic arches in the front—three of them opposite the *mihrâbs* being 7 feet 1 inch wide, while the two on each side the central arch are 4 feet 6 inches, the other four being each 6 feet 7 inches between pillars. To correspond with this arrangement the front and back of the longitudinal isles are made 6 feet 7 inches wide, the central one 7 feet 1 inch, and the two intermediate each 6 feet 4 inches (Plate LV, fig. 1).

The twelve pillars of the central area support others of shorter height, on which the principal dome is raised. There is here no arrangement for the usual covered gallery, and whilst the light thrown into the interior would be more than in the older form of construction, this arrangement would not protect the interior so well from rain when accompanied by wind; for at the sides the outward projection of the drip-stone of the upper roof over the face of the architrave round the octagon upon the pillars is only about $3\frac{1}{2}$ feet. The corners are sheltered by the extension of the roof to cover the square; and a flat stone bench runs round the four sides of this square formed by the upper pillars (Plates LIV and LVI).

One of the corner lintels having cracked about forty years ago, it was supported by the insertion of a heavy stone arch (Plate LIV), and the like expedient was adopted in the corners of the large square below.

The four small windows in the back wall were filled in with carved stone lattice-work, and in each end is a neat balcony window supported on carved brackets.

The three *qiblas* are of marble and tastefully carved, the pediments over them varying somewhat in minor details from the forms of earlier date. Outside, behind them, are buttresses, richly moulded as usual.

The mimbar or pulpit is of the high pattern rising by a stair 7 feet 9 inches from the floor, but is of brick and lime.

The minarets project about 10 feet in front of the masjid and stand on bases 14 feet square. The recessed corners are strongly marked, and the mouldings and florid work in the niches upon them are in the style of, and seem to have been copied from, the Shâhpur Qâzi's mosque, and are wrought with the same elaborate detail distinctive of the latter. On Plate LV, fig. 2, is given a drawing of one of the niches from the north minaret. The stairs enter the end walls and turn into the bodies of the minârs, which, however, are cut off at the level of the roof.

The Rauza stands to the south-east of the mosque, but is quite a low domed building with one entrance, and otherwise dark. The principal tomb is of stone, with others beside it. On a loose slab within it is an inscription which, after the invocation, enumerates the names of Muḥammad, 'Ali, Fâtimah, Ḥusain and Ḥasan, and adds the chronogram:—"The year 1117 (A.D. 1705). Mother of Muḥammad Ja'far, son of Sayyid Muḥammad 'Ali, son of Sayyid Maḥmûd,—Sâdât Bâiah, a native of Kitûrah."

CHAPTER XI.

MOSQUE OF MUHAMMAD GHAUS GWALIARI; AND TOMB OF ABU TURAB.

PLATES XII, XLIX, FIGS. 4 AND 5, L, AND LI.

SHAIKH Muhammad Ghaus-al-'Alam—properly Hâji Hamîd-ad-dîn of Gwâlîâr, was a notable Indian Pir or Musalman saint, who, after long practice of asceticism, in which he acquired much renown as a prophet, went to Gwâlîâr, where he obtained an estate as jâgir yielding him a million *ṭaḥkas*.¹ He was the *murshid* or preceptor of Wajîh-ad-dîn 'Alwî of Gujarât.² He was the son of Kiyam-ad-dîn, who was buried at Kunbra in Ghâzipur, and grandson of Mu'in-ad-dîn Qattâl. He died at Agra 14th Sept. 1562, and was buried at Gwâlîâr, where a splendid mausoleum was erected to his memory. Ghaus-al-'Alam was the author of the *Galzâr-abrâr* which contains the lives of all the Sûfî Shaikhs of India with the places of their burial, &c.; he wrote also the *Jawâhir al-Khamṣa* and other works.

In the survey of 1824 this mosque is called the Daulatkhâna masjid, but it is generally known as the Ektoda or one-turret masjid. It is in the Sârangpur quarter on the Daulatkhâna street and about 330 yards to the south of Malik Sârang's mosque. Eighty years ago an area of 10,560 square yards, or two acres and 32 perches, belonged to it, but of this only half is now acknowledged as *waqf* or religious property, of which the mosque and ranza occupy 2857 square yards. The ground up to the *sen* is now taken up by huts of cotton-printers who carry on their trade in the area. On the west end and up to the back wall are several private houses.

It does not belong to the local style of Ahmadâbâd, and was certainly never planned by a Gujarât architect. It looks like a bad copy of the Jaunpur mosques, and, though originally not wanting in a certain amount of grandeur, it is painfully deficient in elegance.

But no building at Ahmadâbâd has lost more of its character at the hands of the local Public Works Engineers than this. Till about twenty-five years ago it had a great propylon, quite 48 feet in height by 43 feet wide, with a recessed arch in it about 38 feet high. This had survived the shock of the earthquake of 1819, but the front over the great arch had become dilapidated, and the whole was taken

¹ The value of the *ṭaḥka* is very uncertain. If the rupee was equal to 40 dâms and 5 *ṭaḥkas* went to the dâm, then the jâgir yielded Rs. 50,000 per annum. Thomas, *Pathan Kings of Delhi*, pp. 49n., 223f.; Blochman, *Āin-i-Akbari*, vol. I, p. 16n.

² His adventures were written in 946 A.H. by Sayyid Faḡl-ullâh in his *Munâkib Ghausia*; and biographies are given in the *Maâsir* of Badâoni, and the *Khazînatullâ'efiâ*. Blochman, *Āin*, vol. I, pp. 457-8.



MOSQUE OF MUHAMMAD GH AUS, AHMADABAD.

down to nearly the level of the roof, at a cost of 1160 rupees inclusive of some repairs at the south corner and pointing the front. This entirely changed the appearance of the façade—depriving it of all dignity. The illustration No. 6 from Colonel Bigg's photograph, taken about 1865, will give the reader some idea of its appearance at that time. The jambs of it were divided by carved string-courses into nine divisions—all, except the lowest, with a small arched recess in each, and the whole crowned by a line of antefixa. If we compare this with the façade of the Lâl-darwâza mosque at Jaunpur¹ we cannot fail to trace the resemblance.

The triple entry within the arch is the same; but at Jaunpur the propylon served the purpose of the minaret for the mu'azzin. Here a solid minâr is placed at the north end of the façade 82 feet high, octagonal above, but with the Hindû base of many recessed angles, and continued up to the level of the roof, where it becomes octagonal and is broken by five small balconies supported on brackets $8\frac{1}{2}$ to 9 feet above one another. The faces of the shaft are also ornamented with small arched recesses in two rows for each storey. This is entirely different from any other minarets at Ahmadâbâd, and has no counterpart at Jaunpur. At the south end of the façade an octagonal minaret, with quite a plain base, rises one storey above the roof; though it was probably intended to raise it to the same



6. UPPER FAÇADE OF THE MOSQUE OF MUHAMMAD GHAS BEFORE 1880.

height as the other, it had perhaps never been carried farther (Plates XII and LI). In this is the access to the roof, the entrance to the stair being in the south wall, in which also are two small closets about 2 feet by 5 feet 9 inches each. In the north wall are three somewhat larger chambers, measuring $4\frac{1}{2}$ feet by 11 feet (Plate XLIX, 4). Such an arrangement is quite unusual in a mosque. The pillars and lower portions of the walls have now been whitewashed.

Besides the three entries under the propylon, there are also three others in each wing, all arched with massive piers. The interior area is divided into squares by two rows of six pillars each, with corresponding pilasters, and, as in the mosque

¹ Fergusson, *Ind. and Eastn. Archit.* p. 523; *Shârqi Archit. of Jaunpur*, Plate xxix, also the Jâmi' masjid, Plate xliii.

at Shâh 'Âlam, the whole are connected by groined arches with carved pendentives supporting the almost flat domes of the roof (Plates L and LI).

"The mode in which these pendentives are brought up to receive the circular dome," Mr. Fergusson has remarked, "is quite as happy as any of the constructive experiments of the Gothic architects, and more elegant in execution. The Byzantine architects never accomplished this—their peculiar experiment—so successfully."

There are three narrow *qiblas* in the back wall with but little carved work, and the pediments of which differ considerably from the usual style (Plate LI). Outside, behind them on the back wall, are the usual buttresses with numerous horizontal mouldings.

To the north of the mosque is an open space with a *rauza* in which is said to have been buried two of the sons and a wife of Muḥammad Ghaus, but this has been rented for a shop, the doorways and windows having been filled up with brick and clay; and of the three graves inside one has been robbed of its marble wainscotting. Sayyid Muẓaffar, another son, was buried in the graveyard to the south. The present holders claim to be descendants of a daughter of Muḥammad Ghaus.

TOMB OF ABŪ TURÂB.

PLATE XLIX, FIG. 5.

Abū Turâb, a Salâmi Sayyid of Shirâz, was the grandson of Mir Ghyâs-ad-din, who came to Gujarât during the reign of Quṭb-ad-din (1451-1459), but returned again to Persia. During the reign of Shâh Ismâ'il i Šafawî, however, political disturbances obliged him again to seek refuge in Gujarât, where he arrived in the reign of Maḥmūd Baiqara and settled with his son Kamâl-ad-din at Châmpanir. There he became a teacher and writer of school books. Kamâl-ad-din was also renowned for his learning, and his son Mir Abū Turâb was a man of note. When the Emperor Akbar invaded Gujarât he sent Shâh Fakhr-ad-din and Hakîm 'Ain-al-Mulk to him and I'tmâd Khân. On the way they met Abū Turâb, who was thus the first to pay his respects to the emperor, and was subsequently distinguished for his fidelity to his new master.¹ He prevented I'tmâd Khân from joining the rebel Ikhtiyâr-al-Mulk and was afterwards sent by the emperor to Makkah as Mir Hajj in command of numerous nobles, among whom was I'tmâd Khân and a large party of begams. On his return, A.H. 987, he brought with him a large stone, which formed an elephant load, bearing the impress of the footprints of the prophet², which was received with great éclat, though Akbar is said to have looked on the whole as a pious farce but graciously

¹ Beale's *Biog. Dictionary*, s.v. Abū Turâb; Blochmann, *Āin i Akbari*, p. 506.

² Blochmann adds: The stone was said to be the same which Sayyid Jalâl i Bukhârî in the time of Sultân Firuz had brought to Delhi. This seems to be a mistake, though the stones may have been alike. To the east of Delhi is a tomb known as Qadam Sharif, erected by Sultân Firûz in 1375 for his eldest son Faḥ Khân, over the grave in which was placed a marble slab bearing the *qadam-i-rasûl*, said to have been sent by the Khalifah of Baghdâd: but as the Khalifat of Baghdâd finally ceased in A.D. 1258, this cannot have been the case, and the stone probably came direct from Makkah, and was that brought by Makhdam Jabânîan Jalâl-i-Bukhârî. See *ante*, p. 20; Carr Stephen's *Archæology of Delhi*, p. 147. The date or *târikh* of Abū Turâb's return is *khair ul aqdam*, A.H. 987, or "the best of the foot-prints."—*Āin-i-Akbari*, vol. I, p. 507.

allowed Abû Turâb to keep it in his own house. It is reported to have been afterwards placed over his tomb to the south of Ahmadâbâd, where for many years it became an object of pilgrimage. It was removed, it is said, by a Nawâb to Khambay.

When I'tmâd Khân Gujarâti was appointed viceroy of Gujarât in 1583, Abû Turâb followed him as *Amîn* of the *Ŝûbah*, and was accompanied by his sons, Mir Muhibbullah and Mir Sharaf-ad-din; his third son, Mir Gadâi, though he held a *manşab* and in 1601 served in the Dakhan, "adopted the saintly mode of life which his ancestors had followed."¹

Abû Turâb died in 1597 (A.H. 1005), and was buried in the tomb he had erected to the south of the city within the limits of Berhampur village, a little to the east-south-east of Bâbâ Lului's mosque. It stands on a platform 41 feet square, and consists of an outer enclosure of twenty pillars, being six on each face, forming the piers of the structural arches supporting the roof (illustration No. 7). On the south side are two



7. TOMB OF ABU TURAB.

advanced pillars at the entrance, and inside the verandah, which is partly flat-roofed and partly covered by eight small domes, is another square of twelve piers or pillars, also connected by arches, which support a deep architrave over which is a sort of clerestorey—once filled with stone tracery between the pillars under the principal dome. When complete, it presented the peculiar phases of the art in its most pleasing form, being of

¹ Blochmann's *Âin-i-Akbari*, p. 507.

one uniform style throughout. It is still strictly in the Ahmadâbâd style, though by the period when it was built the columns had entirely passed away to give place to piers supporting the arch which here pervades every part.

This tomb, however, is a more pleasing example of it than the Shâhpur mosque of Husain Muhammad Chishtî or Bâbâ Lulû's, because it is of one uniform style throughout. No minarets, in quasi-Hindû style, contrast with its plainness and disturb the harmony of design. Three larger and two smaller arches on each face point to the existence of the central octagon dome and relieve the sides from monotony without disturbing the symmetry of the whole.¹ The detail is generally simple and effective, without the minute surface chasing that prevails so much on many of the mosques.

As in other tombs, the inner arches were here also originally filled with perforated stone-work, but all except one screen had disappeared by 1888. The inside of the dome itself is plain; the pavement of the floor had also been torn up, and the central tomb had been shorn of its marble covering and is now in decay. There has been a grave on each side of the central one, and there are other two in the verandah (Plate XLIX, fig. 5).

The Masjid which stood to the north-west of the Rauza was of brick, but is now a complete ruin. The place is locally known as the Kâchni masjid. The area of the ground is about an acre and four perches.

This tomb, though deserving of conservation, has been hitherto much neglected.

¹ Hope and Fergusson, *Ahmedabad*, p. 92.

CHAPTER XII.

TOMB OF WAJĪH-AD-DĪN; 'ALĪ KHAN'S OR CHHOTA IDRUS MOSQUE AND
SHAH 'ALĪ RAZZAK'S RAUZA.

PLATES XLIV, 3, 4, LII, LIX.

SHAĪKH WAJĪH-AD-DĪN was a disciple of Shaikh Muḥammad Ghaus Gwāliāri, and had considerable renown as a scholar, being the author of several works. His poetical or literary name was 'Alwī, and he was regarded as a pīr or saint. He died on 20th November 1589, and was buried here in the Khānpur ward, about 150 yards north of the walls of the Bhadr and little more from the city wall.¹

The Rauza and Masjid stand in the middle of a large walled enclosure and are attributed to Amir Sa'ādat Khān and Shaikh Farīd-i-Bukhārī the son of Sayyid Aḥmad-i-Bukhārī, who was the eleventh viceroy of Gujarāt, had the title of Sayyid Murtaẓā Khān, and ruled 1606 to 1609.²

The buildings may have been begun early in the Emperor Jahāngīr's reign by Sa'ādat Khān in 1602, but Sayyid Murtaẓā Khān gets the credit of having adorned a *maḥalla* in Aḥmadābād to which the name Bukhārā was applied, and of having built this masjid and tomb of Wajīh-ad-dīn Shaikh, as also of repairing the fort at Kaḍi.

The dargāh (Plate LII) measures about 30½ feet by 58½ inside, having two rows of five pillars each along the floor. The tomb of the pīr occupies the central space of the west half of the structure, under the principal dome, whilst four squares in the south-east are occupied by nine graves, said to be of the pīr's relatives: two of them are of marble.

The principal tomb is of marble, as is also the pavement in the half of the area in which it is, whilst the rest is laid with square bricks. The pillars are 10 feet 4 inches high. Of the eighteen square roof areas formed by the lintels, thirteen are covered by small low domes: over the pīr's grave is a tower with a square base having windows on each side and changing to round, surmounted by a dome, the lower portion of which projects beyond its circular support; also the four areas entered by the side doors are covered by truncated pyramidal roofs rising but little outside above the level of the crenellation on the wall heads. It has two doors in each side and one in each end: these are square headed and are approached by steps from the level of the court; but there are four other openings in each side and two in each

¹ Mr. Hope ascribes this tomb to the time of Aurangzib (*Aḥmedabad*, p. 64), but this is quite a mistake. The *Aḥmedabad Gazetteer*, p. 278 n., places the death of Wajīh-ad-dīn in A.H. 988 by mistake for 998.—Blochmann, *Āin*, vol. I, p. 538.

² He was a man of the greatest liberality, and died at Pathānkōṭ in A.H. 1025 (A.D. 1616), but was buried at Dehli.—Blochmann, *Āin-i-Akbarī*, p. 415.

end with cusped arches, and though they come down to the floor of the dargâh, they may be regarded as windows closed with wooden shutters.

'Alî Khân's or Chhota Idrûs Masjid and Shâh Ali Razzâk's Rauza.

Nearly opposite the Civil Hospital in Jhaveriwâdâ, in the centre of the city, about 400 yards north from the Jâmi' masjid and on the east side of the Ghi Kânthâ, stood the fine mosque known eighty years ago as 'Alî Khân Qâzi's, but later styled the Qâzi's, Nânhâ Idrûs, or Chhota Idrûs Masjid; properly the two rauzas close by, are of Nânhâ Idrûs and Shâh 'Alî Razzâk. The mosque was built by Qâzi Âbu'l Farah Khân during the reign of 'Âlamgir (1658-1707).

Formerly this mosque was a very fine one with considerable architectural merits, but some twenty-five or thirty years ago the northern half of it was pulled down by Husain-ad-din, the Qâzi of Aḥmadâbâd, and the materials sold, probably for his own private advantage. On the ground thus cleared, and upon the large area in front, in despite of all sacred law, he erected a range of shops and small houses or huts, of which he and his successors drew the rents.

In 1824 the area belonging to this establishment was 13,756 square yards—or close upon 3 acres; now it is only about two-thirds of an acre—10,521 square yards having been alienated. The whole place is kept in a filthy condition.¹

From what remains it appears that the mosque had originally three *qiblas*, and the roof, which was flat, was supported by pillars in three rows, one of them forming the façade, and all joined by arches (Plate LIX, 1). The depth of the building was 23 feet 4 inches, and it had two windows in the ends and four in the back wall with neatly carved buttresses behind the *mihrâbs*. The only *mihrâb* left is of sandstone with a good deal of carving. A tastefully sculptured panel is inserted in the south wall, and two others in the modern wall that confines it at the north end (Plate XLIV, 3, 4). The four pillars inside are square for the lower 4 feet with the upper sections octagonal.

In front of the masjid stands Shâh 'Alî's Rauza, supported by sixteen pillars, open on all sides and roofed by nine small domes all beautifully carved. The tomb must have been of marble, but it has quite disappeared and the place is filled with rubbish.

Farther off, and to the north-north-east, is another mausoleum which has been, and even still is, a beautiful tomb, known as the rauza of Nânhâ Idrûs, which stands on a base 40 feet square, having twenty pillars on the outer square and in the inner twelve, which support the large dome over the tomb (Plate LIX, 3).

This dome is slightly stilted, the drum or base rising 4 feet, and giving effect to the dome. It is carefully carved inside. The supporting pillars, 11 feet 5 inches in height, are connected by perforated stone-work with doors on the west and south sides (Plate LIX, figs. 2, 3); but the building is suffering from shameful neglect—

¹ J. F. Fernandez in Appendix to Crawley-Boevey's *Scheme*, pp. xxxvi and xxxvii.

several of the perforated panels have been broken and carried off; the floor has been torn up; and the stone tomb in the centre has been ruined.

The entrance gate, originally of elaborate workmanship, is completely dilapidated.¹

MOSQUE AND TOMB OF NAWÂB SARDÂR KHÂN.

PLATES LX, AND LXI.

In 1659, when the unfortunate Dârâ Shikoh had been defeated by his younger brother Aurangzib and fled to Ahmadâbâd, where Sayyid Aḥmad was deputy viceroy for Shâh Nawâz Khân Şafâvi, Aurangzib's father-in-law, we find Nawâb Sardâr Khân had imprisoned Sayyid Aḥmad and closed the gates in face of the prince. For this he was thanked by the usurping Emperor. Four years later he was made governor of Bharoch, and a little later governor of Sorath, to which in 1666 Nawânagar was also added: in 1670 he was sent to Idar, and in 1685 he died at Thatta in Sindh, to which he had been appointed governor. His tomb, with the accompanying mosque, was doubtless begun when he was at Ahmadâbâd or before 1664, though it may have been completed whilst he ruled Sorath or Idar, or at latest by 1683.

The masjid and tomb stand a little to the east of the Jamâlpur road, behind Muḥammad 'Alî Sâheb's masjid, about 360 yards north of Haibat Khân's, and occupy a space of one acre enclosed by high walls, to which there is an imposing gateway.

Neither structure is large, but they attract attention as being of quite a different style of architecture from any in Ahmadâbâd, and the crescents on the domes and minarets may indicate that Sardâr Khân, like 'Âlam Khân and other viceroys, had come from Persia. The mosque is but small, is built of brick, stands on a brick platform, has one *qibla* of stone carefully plastered, and has three pointed arches in the façade. The minarets are of four storeys, the lower ones octagonal and the uppermost circular; but they are solid turrets without any staircases to the roof. There are balcony windows in the ends, and the floor seems to have been at one time paved with marble. The roof is surmounted by three domes that taper upwards and seem to be imitations of what is met with in Persian Saracenic architecture. The whole has been beautifully finished with that perfectly smooth white plaster so often seen in India.

The rauza is inside a separate court with large gates, and stands on a raised brick platform: it is in the same style as the mosque and on the usual plan of two concentric squares, the outer of twenty pillars enclosing the verandah and the inner of twelve surrounding the tomb. It is roofed by one large pear-shaped dome terminating in a brass crescent and star, very much like the Brâhman *triśula*; over the verandah there are eight smaller domes of the same pattern round the central one. The two spaces at each corner of the verandah and the sides of the inner chamber are filled with perforated stone panels in varied geometrical patterns and

¹ *Ut sup.* p. xxxvii.

of exceptional beauty. The floor is of white and yellow marble, much in the character of that of Nawâb Shujâ'at Khân's mosque. It contains three tombs, two of which were in good condition fifteen years ago, with the marble coverings complete, but the third seemed to have been despoiled of its ornamental slabs.

This tomb enclosure is entirely overgrown with trees and bushes and has been utterly neglected. The area in front of the mosque is used by silk-weavers for the preparation of warps for looms, and the rent from this is 20 rupees per annum. The south walls of both enclosures have been built against by private dwellings.¹

¹ J. F. Fernandez in Appendix to Crawley-Boevey's *Scheme*, pp. xxxix and xxxixa.

CHAPTER XIII.

SHAH-I-BAGH AND A'ZIM KHAN'S PALACE, NOW
THE JAIL.

PLATES LIII, LVII, AND LVIII.

ABOUT a mile and a half north from the Dehli gate of the city and a very little beyond Miyân Khân Chishtî's masjid, stands the Royal Garden Palace or Shâh-i-Bâgh, built on the left bank of the Sâbhramati, by Prince Mirzâ Khurram, afterwards Shâh Jahân when viceroy of Gujarât in 1616-1623. His minister was the able Muḥammad Šafî, who afterwards received the title of Saif Khân, and who was really the governing spirit in Gujarât. In 1624 he was appointed seventeenth viceroy until the death of Jahângir in 1627, when Shâh Jahân caused him to be imprisoned because of his loyalty to Jahângir. Tradition alleges that Shâh Jahân built this residence and pleasure-garden to give work to the poor during a season of scarcity: possibly it was partly also to please his wife, the famous Arjumand Bâno Begam, styled Mumtâz Mahâl, when she might come with him to Aḥmadâbâd, and in her honour the suburb was named Begampur. But Jahângir preferred generally to live at Ujjain, leaving a deputy at Aḥmadâbâd, which, however, he visited occasionally.

Mandelslo in 1638 describes the Shâh-i-Bâgh as "the king's garden, very large, shut in by a great wall with ditches full of water, with a beautiful mansion having very splendid rooms. A walk leads thence," he says, "by a stone bridge to another garden four hundred paces distant, which was styled 'The Jewel' and was planted by a beautiful and wealthy maiden. This garden is not large, nor is the house to which it is attached; but both are most advantageously situated on ground so raised as to overlook all the surrounding country and to present at the approaches to the bridge one of the most beautiful views I have ever seen. The ruins that fall in winter fill a large reservoir or pond in the middle of the garden, but in summer the water is drawn by machines worked by oxen from wells which are so deep that they never run dry." Thevenot adds that "in the centre of four walks which make a cross, there was a pavilion covered with green tiles, and thither went all the young people of the town to take the fresh air upon the banks of a bason full of water underneath."¹

A little beyond the Shâh-i-bâgh was an older garden, called the Andhârî-bâgh or dark garden, with large ruins.

About 1781, when James Forbes visited Aḥmadâbâd, he states that the Shâh-i-bâgh park and pleasure grounds had once extended to the city gates; "they were enclosed by a high wall, which is now in ruins; little of the gardens remain except broken fountains, aqueducts and a few trees,—some of foreign appearance. The

¹ Wicquefort, *Suite de la relation du Voyage*, tom. II, p. 143.

² Thevenot, *Travels*, part III, p. 10.

zanâna, or Sultâna's palace was situated at a little distance from the royal mansion, on the bank of the Sâbhramatî, with separate baths, gardens and fountains. It is now known as the Chhota Shâh-i-bâgh, and is the official residence of the Superintendent of Police. The apartments for the officers and attendants of the court were still further detached. Everything indicates the taste and judgment of Shâh Jahân in planning this lovely retreat from the cares of royalty. It now exhibits a scene of solitude and ruin, except the palace itself. The zanâna seems to have been intended to accommodate a great number of females." Further, he adds that the grounds still boasted of "some noble cypresses, cedars, palmetos, sandal, and cassia trees with mango, tamarind and other spreading fruit-trees, and large and small aqueducts, admirably contrived for conveying water to every tree and bed in the garden."¹

The Plate LIII. shows the style of this royal garden house. The whole is raised on a sunk storey of *Tah-khânas* or cellars, which form cool retreats during the hot days in April and May. Over these the palace rises in a large square block two storeys in height, with a third storey over the front only. The hall is a very fine apartment, the walls divided by deep recesses—four on each side, with two doors in each end—front and back—and another recess between each of these. In the words of Forbes,—“The saloon, spacious and lofty as the building, was a fine room; the wall covered with shell chunam,” or white stucco, “polished like the finest marble, and the ceiling painted in small compartments with much taste. The angular recesses lead to eight small octagon rooms, four below and as many above, with separate stairs to each: they are finished in the same style as the saloon, the walls like alabaster and the ceilings neatly embossed. The flat roof commands an extensive prospect, the substructions form a cool retreat under the saloon and a surrounding platform, ornamented with small canals and fountains. These substructions are on a level with the flower-garden, which reached to the river; everything appears to have been elegant and splendid. It was during the reign of Shâh Jahân that architectural taste in the Muhammadan structures of India attained its acme.”

About 1835 the two wings on the terrace and some other additions were made by Mr. Williams of the Civil Service. “How far this alteration was an improvement is very doubtful,” Mr. Vaupell remarked,—adding that it had “entirely changed the character of the building.”² It is now the official residence of the district judge.

In the great flood of 1875, the strong stone wall which prevents the river from passing south towards the city was slightly injured, and sand was washed over it, covering and destroying the garden beds. Since this flood the water is much deeper and the current much stronger along the base of the wall than before.³

Â'ZIM KHÂN'S PALACE, NOW THE JAIL.

Among the sixty viceroys appointed by the Mughal Emperors between the conquest of the country by Akbar and 1748, when the Marâṭhas seized the province,

¹ Forbes, *Oriental Memoirs*, 2d ed. vol. II, pp. 205–6.

² *Bombay Geograph. Soc. Trans.*, vol. VII, p. 110.

³ *Bombay Gazetteer*, vol. IV, p. 283.

few were so efficient as Mīr Muḥammad Bâqir, the brother of Âṣaf Khân Jâ'far Beg, who in 1606 had been honoured by the Emperor Jahāngīr with the manṣab of 1000 and the title of Irâdat Khân, had the office of Wizârat Kull conferred on him by Shâh Jahân in 1628, and two years later received the title of Â'zim Khân. He was governor of Bengal when the English obtained permission to trade at Pipli on the Orissa coast in 1634, and was selected as viceroy of Gujarât by the Emperor Shâh Jahân at the close of 1635, when the native chiefs and predatory tribes were holding that province in a state of turmoil, and he at once adopted firm and even severe measures. To ensure peace he fortified posts wherever they seemed required, as at 'Azimâbâd and Khalilâbâd in the Koli country, at Shâhapur, near Chuḍâ Rânpur in the Dhandhukâ district, and in fact all over the country of the Kolis and Kâthīs. From this circumstance Â'zim or Â'zam Khân came to be nicknamed *Udâi* or the White Ant, which builds its house wherever it goes. He was apparently of Persian origin, born in 1576, he died at Jaunpur in 1649.

What is the present jail was built by this Â'zim Khân as a residence, and it is still spoken of as his palace. It stands at the south-east corner of the Bhadr about 330 yards to the west of the Tīn Darwâza. The plan (Plate LVIII) shows that it consists of a main block 210 feet wide by 240 deep, with an extension on the north side through which is a passage into the Bhadr or fort, and another addition extending 250 feet to the south, which abuts on the front wall.

The structure (Plate LVII) has a handsome entrance on the east face about 18 feet high, leading into a very elegant octagonal hall $37\frac{1}{2}$ feet across, in the upper storey of which is a gallery faced in front by a low balcony breast-work of open cut stone. Each section of the gallery is roofed by a cupola whose marble chequering is concealed by coatings of whitewash. The walls are ornamented in plaster patterns. Beyond this hall is a large court 156 feet wide by 146 deep, surrounded by rooms in two storeys, now converted into cells for the prisoners, those on the left or south side being used as the hospital and female wards.

Over the entrance is a magniloquent Persian inscription stating that "this mansion (*sarâ'e*) like which the vision of the age has not seen the equal, was erected in the reign of Shâhjahân Shâhab-ad-dīn Muḥammad, by the brave A'zim Khân, the source of justice, whose sword is the soul of the kingdom," an edifice "whose height towers above Saturn in the sky—its beauty and grace is like to paradise, and is worthy that Ridvân (the gatekeeper of paradise) should be its porter. The sarâ'e and palace being completed by order of the Khân of Justice (*'adl*) the jewel of men, I asked echo for its chronogram, when the invisible herald replied—"the place of goodness and beneficence"—(*makân khair u ihsan*). The numerical values of the letters in which give 1047 A.H. or 1637 A.D.

It was during Â'zim Khân's own time that the Holstein traveller Mandelslo visited India, and was twice received by 'Azam Khân in 1638, apparently in the palace which he had built only a year or two previously. After visiting the fort, he says, the English agent and he "entered, also from the Maidân Shâh" or area between the Tripoli or triple gateway and the Bhadr, "a mansion built of brick which is called the Royal Palace. Over the entrance extends a corridor for the

music of violins, hautboys and bagpipes, which are played at morning, noon, evening and midnight, as in Persia," &c. All the apartments of this mansion "were beautiful, gilt and painted in distemper, in the fashion of the country; but more satisfactory to such as take delight in variety of colours than to those who seek it in invention or in exactness of proportion."¹

Architecturally, it is a really fine building, though what the internal arrangements exactly were in the seventeenth century may not now be quite clear; the plans show the present arrangements of the two storeys, as it has been adapted to the requirements of a prison. Thevenot,² about thirty years after its erection, mentions "a caravansary, a great ornament to the square" with its gate on the south; but he speaks also of "the palace belonging to the king" here. It was at a later date turned into a *madrasa* or college, and under the Marâthâs (1753-1820) it was occupied as the residence of one of their military chiefs, whilst lastly, under the British (1820) it was turned into a jail and still continues to be used as such.

¹ Wicquefort, *Seitte*, &c. tom. II, p. 135. The *Bombay Gazetteer* says Mandelslo does not mention the palace—Vol. IV, p. 274 n.

² Thevenot, *Travels*, tr. by A. Lovell, part III, p. 9.

CHAPTER XIV.

MOSQUE AND TOMB OF SHUJA'AT KHAN, AND HIDAYAT
BAKHSI MADRASA.

PLATES LXII TO LXV.

THE masjid of Nawâb Shujâ'at Khân stands on the west side of the road leading north from the Karañj to the Mirzâpur ward, and is about 120 yards north-east from the Lâl Darwâza of the Bhadr.

Kârtalab Khân appears to have succeeded Sardâr Khân as governor of Sorath in 1685, but very soon afterwards, on the death of Mukhtâr Khân in 1686, he was raised to the post of viceroy, being the thirty-ninth in succession, with Muḥammad Tahir as his minister. In addition to Gujarât he was also placed in charge of Jodhpur. In 1689, whilst he was on his way to Jodhpur, the troops in Aḥmadâbâd grew mutinous, when he immediately returned and by his firmness promptly restored order. His conduct so pleased the Emperor 'Âlamgîr that he bestowed on him the title of Shujâ'at Khân. He was an able ruler, and for fifteen years held the office of viceroy at a critical period, till his death, which, according to the *Mirat-i Aḥmadi*, occurred in 1703, but the inscription on his tomb here—without indicating his name says, "date of the decease, Thursday the 14th of the month Ṣafar in the year 1113 of the Hîjra," which corresponded to 21st July, 1701.

The mosque stands behind an open court about 80 feet by 70, and measures 73 feet by 41 over the walls: to the north of it, in an area about 100 feet square, is the Maqbara or tomb, and to the south—in an enclosure about 140 feet deep by 100 from east to west was a building containing many separate rooms round an open court—variously styled a *muzaffar khâna* or rest-house, a *madrassa* or college, and a palace. The rooms have now been converted by the Muḥammadan Panch into small dwellings in order to raise an income, and are let to low people, including Goanese servants, who keep the place in a filthy condition.

The whole site occupies 4133 square yards, of which the mosque with its court covers 1150.

The mosque and tomb are built of brick, and, with those of Sardâr Khân, are almost the only structures of that material in the city that can pretend to any magnificence. The ablution tank in the front court was once lined with marble slabs, but they have long since been all removed (see Plates LXII, LXIII).

The mosque is of the Indian Saracenic style, with five arched openings in front, the central one being the largest—9 feet 6 inches wide and 12 feet 10 inches high to the apex of the arch; the other four each measure 7 feet 3 inches wide by 10 feet in height. Two slender minarets are attached to the façade—three bays apart—and are of similar pattern to those of Nawâb Sardâr Khân's mosque, being octagonal and of four storeys. The stair up to the roof is in the south wall. The roof is

supported inside by eight square piers connected by pointed arches, and has three bulbous domes of the form prevalent in Northern India and Sindh in the seventeenth century, which are wanting in the expression of restful stability so marked in the earlier hemispherical form (Plate LXII).

The walls and piers are wainscotted with marble to a height of about 7 feet and above plastered with fine lime, perfectly white and so carefully polished as to rival marble or ivory in smoothness and brilliancy. The floor is of white and yellow marble wrought in compartments, in the pattern of a number of *muṣallās*, *jāi-namās*, or prayer-mats, divided from one another by parti-coloured mosaics. These features gave rise to its being popularly known as the "ivory" and the "marble mosque."

The *mihṛābs*, of which there are five, are very plain but highly finished, and over the central one is a Persian inscription containing the Muhammadan creed and the date A.H. 1107, corresponding to 1695-96, when the mosque would be finished.¹

The *mimbar* is of yellow marble and of three steps, as all pulpits in the time of Aurangzib were formed. Perforated windows are over the *mihṛābs* and differ in character from those in the earlier mosques.

To the north of the mosque is a nearly square enclosure in which stands the *maqbara* or *rauza* upon a raised platform 54 feet square. It has twenty piers in the verandah that surrounds it, connected by arches in the façades and with the chamber containing the tomb. This room, about 28 feet square outside and 21 feet inside, is covered by a good-sized dome and has four smaller ones at the corners; it contains one tomb only, on which is the inscription already quoted. The floor was of marble but is now much destroyed, and the plastering on the walls is gone. Behind this is a small *rauza*, close upon the wall of the court and much dilapidated, in which it is said a daughter of Nawāb Shujā'at Khān was buried.²

This mosque is claimed by the Shiah sect of Muhammadans, who, though the predominant sect in Persia, are in a small minority in India, but are largely prevalent in Audh. Their peculiar practices, however, have been popularised among the Sunni sect in many localities. They deny the title to the Imāmate of 'Abū Bakr, 'Umar, and 'Usman, and claim 'Alī the husband of Fāṭimah as the first legitimate Imām or Khalīfah.

THE HIDĀYAT BAKHSH MADRASA AND QĀZĪ'S MOSQUE.

PLATES LXIV, LXV.

The Madrasa-i-Hidāyat Bakhsh, formerly known as the Qāzī's Mandir-sâlâ, is on the south side of the Oliphant Road in the Astodiya quarter, about three hundred yards west from Dastur Khān's masjid and close to the City Qāzī's mosque, which indeed may be regarded as part of the group which occupies an area now reduced to 4129 square yards—much of the original land having been privately appropriated.

¹ *Arch. Sur. W. Ind.* vol. II, p. 10.

² H. Briggs, *Cities of Gujāraṣṭra*, p. 222, has given a tolerably good plan of this whole group, only his scale is too small for the sketch; instead of "100 feet," it ought to be about 72 feet to the inch.

The Ahmadâbâd Qâzî's mosque is a very small stone building of the beginning of the eighteenth century. It has eight windows, of which two in each end and two in front reach to the floor, whilst the two in the back are smaller and nearly square; these as well as the *mihrâb* appear to have been carried off from some earlier structure. It has an inscription giving the date. The Hidâyat Bakhsh Mosque¹ was built about A.D. 1699 by Muḥammad Akram-ad-dîn, styled Shaikh-al-Islâm Khân,² the Şadr-şubhâh of Ahmadâbâd, who built the madrasa and masjid at an expenditure of 1,24,000 rupees and whose marble tomb stands in the court. The mosque (Plates LXIV and LXV) is built of stone and brick, much in the general style of Shujâ'at Khân's, with five bays in length having lofty Saracenic arches in the façade. The length inside is 60 feet and the depth 36½ feet within the front piers, and the area is divided into three aisles by the pillars, which are all connected by arches. The roof has three domes of the usual form over the central aisle, whilst the other squares have coved roofs.

There are three *mihrâbs*, of which the central one and the low *mimbar* are in a recess. In the back wall are two windows, and in each end three, all above the level of the spring of the arching and are perforated in unique designs. The minarets are solid octagons after the style of those on Shujâ'at Khân's.

To the east is a walled enclosure containing the marble tombs of Maulânâ Nûr-ad-dîn Sidi—for whom the college was built—and of Qâzî Muḥammad Nizâm-ad-dîn Khân, the first Qâzî of Ahmadâbâd city, who died A.H. 1165 (A.D. 1752) at the age of 114 lunar years. These are under a small wooden shed, and to the west of it are the tombs of Qâzî Muḥammad Rukhu-al-Haq—with an inscription—and of Qâzî Muḥammad Sâleh—both of marble.

The mosque stands in a large court surrounded by arched rooms intended for the residence of the madrasa students—but they are now much dilapidated and are occupied by Mârwâdî dyers, who ply their occupation in the court, which is uncared for. To the south and west sides of the enclosures over the tombs, low rooms have been built within the last twenty or twenty-five years by the Qâzî who holds the property, and the whole is rented to occupants.

For the support of this madrasa three villages were originally assigned—one in Châmpānir district, one in Kaḍi pargana and the third in Pattan pargana along with an allowance of 2 rupees from Ahmad Shâh's Langarkhâna or almshouse. Nothing now remains of these endowments.³

¹ Hidâyat bakhsh means "imparting guidance," "teaching."

² Shaikh al-Islâm is a title given to the chief Maulavi or Qâzî of the cities of Stambul, Damascus, Cairo, &c. This Muḥammad Akram was a disciple of Hazrat Maulânâ Nûr-ad-dîn Sâheb.

³ J. F. Fernandez, in Crawley-Boevey's *Scheme*, App. pp. xlv, xlv.

CHAPTER XV.

OTHER MOSQUES AND TOMBS IN THE CITY.

THERE are many other mosques and tombs both within and without the walls of Ahmadâbâd that have not been noticed in the preceding account, but of which some such notes as the following may be found useful. It would be impossible to classify them chronologically, and probably a sort of topographical arrangement may be found even more useful.¹ Accordingly, they will be taken in order generally from the north of the city toward the south.

1. GANJ 'INÂYAT SHÂH'S MOSQUE.

Nang Sara, Gagâ Nâsâ, or Ganj 'Inâyat Shâh's masjid is close to the Shâhpur gate, on the west side of the street, and, though of brick and mortar, it appears to have been of some architectural pretensions. It was built in the time of Maḥmūd Shâh III (1537-1554) in honour of Ganj 'Inâyat. It has five brick *qiblas* and an inscription on a marble tablet over the central one, but the building has for long been roofless and ruined. The inscription reads thus:—

"The confider in the gracious Allah,—Nâsir-ad-dunyâ wa'd-din Abu'l Faṭḥ Maḥmūd Shâh, son of Latif Shâh, son of Muẓaffar Shâh, son of Maḥmūd Shâh, son of Muḥammad Shâh, son of Ahmad Shâh, son of Muḥammad Shâh, son of Muẓaffar Shâh the Sultân. For the purpose of worship Shams Khân built the masjid: the year nine hundred and (forty?) six was found to be the date of the building (A.D. 1539-40). Written by 'Abdu'l-Haiy."

The area of the site is 1094 square yards. (*Lists of Antiquarian Remains*, p. 160, No. 74 and p. 251; or *Revised Lists*, p. 74, No. 47 and p. 297).²

2. CHAMPÂ-KĪ MASJID IN SHÂHPUR.

About 80 yards south from the preceding, on the west side of the Shâhpur cakla, is a small mosque built of brick with a tiled roof and having three plain

¹ The following notes are largely based on the statements of Mr. J. F. Fernandez, Deputy Collector and City Magistrate, forming Appendix C (pp. xix-lix) to A. W. Crawley-Boevey's *Scheme for the protection and conservation of Ancient Buildings at Ahmedabad* (1886). The tabular form of arrangement there adopted is not suited for general use and is quite different from Mr. Crawley-Boevey's own arrangement (App. B. pp. v-xvii); in the *Lists of Antiquarian Remains in the Bombay Presidency* as revised by Mr. Cousens and supplemented from the above, another order has been followed, but it is also irregular. The principal structures having been already described, the arrangement here employed applies only to the remainder; and of these, several of little account have been omitted. There is considerable uncertainty, too, about the correct names of many of them.

² For brevity, the references to the *Lists of Antiquarian Remains in the Bombay Presidency* (1885) and the same *Lists* as revised by Mr. Cousens (1897) will be referred to below as *L.* and *R.L.* respectively.

mihrâbs in the back wall. On the survey map it is styled Shâhpur mosque, but from an old champā tree in the court it is locally known as the Champā kī masjid. It is said to have been first erected about A.H. 920 or A.D. 1515, by Makhdûm Jamâl-ad-din Jamman Shâh, whose tomb (now dilapidated) stands on the west side of the Sâbhramati in the village bounds of Naurangapâra.¹ The original masjid has entirely disappeared.

3. KHARÂTI MASJID.

The Kharâti masjid inside and on the west of the Delhi gate, which is half a mile to the east of the Shâhpur gate, is a very small brick structure roofed with tiles. It contains an inscription of four lines on a marble slab, but this may have been brought from elsewhere. It begins with a quotation from the *Qorân*, sura lxxii, v. 18, followed by the usual saying of the prophet about the house in paradise; then the statement:—"The erection of this blessed Jâmi' masjid (*was*) in the reign of the ruling Sultân Nâsir-ad-dunyâ wa'd-dîn Abu'l Fath Maḥmûd Shâh, son of Muḥammad Shâh, &c. . . . may Allah perpetuate his kingdom!—by the worshipper hoping for the mercy of Allah, the Mâlik Malik Ghani . . . Sultânî who received from his most exalted majesty the title of Maliku'l-barr and Qawâm-al-mulk—may his exaltation be permanent!—desirous of the approbation of Allah and craving his abundant reward. On the sixth of Dhu'l-Qa'dah in the year 880," i.e. Saturday, 3rd March, 1476.

4. BÂDShâH SAYYID'S MASJID.

Bâdshâh Sayyid's or Naginâ Pol masjid is a small mosque of brick and mortar in the Daryâpur quarter, about a hundred yards east of the Daryâpur chakla. Part of the entrance is of stone and the mosque is kept up and used by the people of the district. There are tombs in an enclosure about eighteen yards distant, among the houses on the opposite or north side of the street which must have originally belonged to this mosque. The site now claimed for it is only the ground on which it stands, measuring 111 square yards. (*R.L.*, p. 76, No. 85.)

5. MIRÂ SAYYID 'ALÎ'S MASJID.

Mirâ Sayyid 'Alî's or Mirâna Chhulâni Masjid in Lunsâwâdâ, south of Jordan road and about 230 yards south from the Fath Masjid, is dilapidated, but has a good entrance: it is a plain stone structure, and has several tombs in front. The ground measures quite a quarter of an acre but has been encroached upon: Mirâ Sayyid 'Alî died about the end of the fifteenth century and was buried at Unâo near Uñjhâ in north Gujarât, where his tomb is much frequented as a place of pilgrimage by the Muhammadans. (*R.L.*, Nos. 27 and 70.)

¹ This mosque is not mentioned in Mr. Fernandez's enumeration. The Rev. Geo. P. Taylor obtained part of the above details for me from Farid-ad-din Chishtî, the nephew of Qâḍî Sâlah-ad-din Chishtî of Shâhpur.

6. MIYÂN MUHAMMAD HUSAIN'S MASJID.

Miyân Muhammad Husain's Masjid, also known as Dādā Miyân's, otherwise called Roshau Pir, is near Chandan Talāvdi, south of Jordan road and about 230 yards south-east from Bādshāh Sayyid's. It is a good family mosque built of brick, about the last quarter of the eighteenth century. Dādā Miyân was the son of Sayyid Muṣṭafa, and great-grandfather of Narai Husain Shāhāb-ad-dīn to whom a *sanad* of possession was granted in 1879. The walls are ornamented with carved arches; the pillars are of carved wood, connected by wooden arches with carved panels. In the *rauza* are buried Dādā Miyân Mash-heddi and his younger brother Ghulām Nabī. On the other side is a second *rauza* containing the tombs of Sayyid Muṣṭafa and other members of the family. The buildings occupy a site of 740 square yards, but are badly kept. (*R.L.*, No. 73.)

7. HĀJĪ SĀHEB'S MASJID.

Hāji Sāheb's or Hāji Sākhi's Masjid in Lāl Bāwā's Tekrā in Daryāpur, about 120 yards S.S.W. from the preceding, is a brick mosque of about the middle of the seventeenth century, now in a dilapidated condition, and part has been walled off as a dwelling. To the north-east lie the tombs of Hāji Sākhi and Shāh Nur, of plain marble, under a canopy supported on carved wooden pillars—also decayed. On the east is a large graveyard with many tombs. In the survey of 1824 the ground belonging to this mosque measured 1564 square yards, but since then 285 square yards of it have been taken possession of as private property. (*R.L.*, p. 76, No. 72.)

8. 'ABDULLĀ RAZZĀQ'S RAUZA AND MASJID.

'Abdu'l Razzāq or 'Abdullā Razzāq's *Rauza* and Masjid are on the road leading from Dhalgarwāḍā to Popatiawād and about 80 yards west from Hāji Sāheb's masjid. The mosque is a small plain stone-built one, with marble flooring. The *Rauza* is octagonal and domed, with walls of perforated stone, but all whitewashed. It is the burial-place of 'Abdu'l Razzāq, and the tomb is of marble, though the rest is now of brick and mortar, but shaded by a handsome wooden canopy. Close to it is a Divānkhāna, the terrace of which forms a verandah to a private dwelling built over two graves. A large part of the Tānka of the Masjid lies outside the present enclosure, and the area, now only of 470 square yards, has been much contracted from encroachments and probably by sales. An allowance of one rupee per annum is made from the collector's treasury. From the lands and houses belonging to the mosque and *rauza* the holder derives an income of 200 to 250 rupees per annum. In the village of Sherkotḍa also, land measuring nearly five and a half acres belongs to this establishment, and is assessed at 68 rupees, but pays only 15½ rupees as quit-rent. It was granted by *Sanad* to Aras Bibī, who died in 1883, when the property was entered in name of the Panchāyat; the manager of the *Rauza*, however, enjoys the usufruct, the Muhammadan Panchāyat paying the quit-rent. There were besides 13 acres 2½ roods belonging to it outside the Kalupur gate, which was taken up when Sir Th. C. Hope laid out the Railway suburb in 1862-63. The compensation for the land was settled at Rs. 2850,

but Aras Bibi demanded land in exchange and refused the money. This had accumulated in 1886 to Rs. 7758, partly invested in Government securities. (*R.L.*, No. 28.)

9. PIR-I DASTGÎR'S MASJID AND RAUZA.

Pir-i Dastgîr's Masjid and *rauza* are in the Ghikântâ road, near Dayâbhâi's wâdî, about 110 yards south from Muhâfez Khân's masjid. The Masjid here has entirely disappeared and the site has been built over, whilst the *rauza* is in a dilapidated condition; the arches on the east and west have been filled in by a wall, and the spaces converted into rooms. The title Pir-i-Dastgîr is a name applied to Sayyid 'Abdu'l Qâdir al-Jilânî, the famous saint of Bâghdâd (A.D. 1078-1166) and founder of the Qadiriya order of faqîrs, the most popular sect of ascetics among the Sunnis of Asia.

The area is 963 square yards, but much of the ground formerly attached has been lost, and part of the Tâuka or reservoir of the Masjid is now in an adjoining property. (*R.L.*, No. 67.)

10. PIR VAZÎRSHAH'S MASJID AND RAUZA.

Wâhidshâh Pir's, otherwise called Pir Vazîrshâh's Masjid and *Rauza*, is in the Mirzâpur quarter, 160 yards south-west from the English church and about 100 yards north-east of the Mirzâpur Queen's mosque. It is a small one and, with the *rauza* formed by a few arches roofed in with outer walls, is of brick and mortar with no architectural claims. Wâhid Shâh, who died about 1780-90, is reputed to have been a man of piety, and his tomb in the *Rauza* is canopied and held in great veneration by Muhammadans who visit it from distant places. Within the enclosure, which has an area of 1466 square yards, are a few houses which, with a piece of land attached to the *rauza*, yield an income from which repairs and upkeep are provided. (*R.L.*, No. 80.)

11. SHÂH 'ABD-AL FATH'S MASJID IN SHÂHPUR.

Shâh 'Abd-al Fath's Masjid, in the Shâhpur quarter, south of the mills, and 420 yards north of Sayyid 'Âlam-ad-din's masjid, has a site measuring 1736 square yards, and is entered in the registers as *wagf* property, no name being mentioned as manager or holder. The mosque is small but massive and perfectly plain, with two slender minarets, and the domes are surmounted by finials. It has three *qiblas*. The interior is whitewashed and daubed in places with green, yellow and blue. The *zen* and *hauz* are in good repair, and the mosque is kept up by the Muhammadan workers of the adjoining mills of the Spinning and Weaving Company. Rooms are attached at the ends of the mosque for residence.

On the area to the north-east are tombs in good preservation, among which is that of 'Abdal Fath. The land to the east and south, measuring 34 perches, is held on summary settlement tenure by a Musalman who professes to be the holder of the mosque, but he spends no part of the income on the building.

12. SHÂH 'ABD-AL WÂHHÂB'S MASJID AND RAUZA.

Shâh 'Abd-al Wâhhâb's Masjid and *Rauza* are in Khânpur, in a secluded place without any entrance to it, and about 220 yards east from the mosque of Sayyid

'Ālam-ad-dīn. The mosque had almost disappeared twenty years ago, but was being replaced by a modern structure, altogether out of keeping with the *Rauzas*.

The rauza of Shah 'Abd-al Wāhhāb is to the east of the mosque and must have once been a somewhat imposing building. The central area is domed on arches and the surrounding double colonnade is roofed by smaller domes on numerous stone columns: but the whole structure has fallen into decay, the marble has disappeared from the tomb, and the canopy over it—similar to that over the tomb of Shāh Wajih-ad-dīn—which must have cost a large sum, is also dilapidated. The shrine is highly venerated and on certain days it is visited by Hindūs as well as Musalmāns. The mosque was to the west of it, and near it to the north-west stands the Rauza of Shāh Ghyās-ad-dīn, the father of Shah 'Abd-al Wāhhāb, and of Sayyid 'Abdu'l Jalil, the grandson of the latter. Though plain and much ruined, it appears to have been once a fine building. In the mosque were a number of inscriptions on marble slabs containing usual quotations from the *Qorān*, one mentioning the Rauza of Shāh Ghyās-ad-dīn and his son Malik Sarirat Sayyid Jalil, whilst another mentions the death of Rukn-al-haqq in A.H. 1200 or A.D. 1786. The area belonging to these buildings in 1824 extended to 2 acres 3 roods and 18 perches: since then a small portion has been appropriated as private property and another for roads, leaving 2 acres 1 rood and 29 perches. (*L.*, p. 160, No. 66, and pp. 262-3; *R.L.*, No. 40, and p. 308.)

13. NAWĀB SHĀHJAHĀN KHĀN AND MOMIN KHĀN'S MASJID, &c.

Nawāb Shāhjahān Khān and Momin Khān's Masjid and 'Alikhān's Masjid were situated about 330 yards from the Mirzāpur Rānī Rupāvati Mosque and half that distance east from the preceding. These buildings, up till about fifty years ago, occupied a large area: but a Faqir squatted in it, assumed the position of owner, and then began selling the land.

In 1864 he sold an area of 2285 square yards to a Mrs. King, a Eurasian, who built a dwelling-house on it. Gradually she appropriated other portions and removed all the original structures except a small Mausoleum with perforated walls, built for a Muhammadan wife of General Ballantyne, which she used as a fowl-house, after removing the tomb. On the ground she built other two houses, and in 1874 the spoliations were finally confirmed by Mr. J. E. Oliphant, the Collector.¹ All that remains of the original property is a small enclosed graveyard with an area of 156 square yards, without any means of access to it. In the centre of this enclosure is a marble tomb with a headstone bearing an inscription in memory of Mirzā Muḥammad Ja'far Najm-ad-daulah Sāhni, alias Momin Khān, who figured largely in the struggles in Gujarāt, with the Marāṭhas, and was fifty-seventh viceroy of Gujarāt from 1738 till his death. He was the first of the Nawābs of Cambay,² and died 8th Muharram 1155 A.H., 1742 A.D. (*R.L.*, No. 55.)

¹ Crawley-Boevey's *Scheme*, pp. 39-40.

² His son-in-law Zimal Abid-dīn Najm Khān was governor of Kambay till 1748, when he was poisoned by his brother-in-law Muftākhir Khān, who succeeded as Momin Khān II, and ruled till 1783. Najm Khān's son Muḥammad Qalī succeeded as Momin Khān III and died in 1789.—*Bombay Gazetteer*, vol. VI, p. 233.

14. MUHAMMAD SAYYID'S MOSQUE.

Muhammad Sayyid's or the Ghikântâ Masjid, about 170 yards south of Pir Dastgir's, on the same road, is a private mosque belonging to the family of the Dattawâlâs of Ahmadâbâd. A *sanad* was issued in October 1883, to Nânhâ Miyâh Muhammad Afzal as owner. The site covers 1498 square yards and in front it is studded with tombs of members of the family of past times; another portion is used as a firewood depôt. (*R.L.*, No. 66.)

15. SHAIKH MUHAMMAD JÂHID OR MORKI MASJID.

Shaikh Muhammad Jâhid or Morki Masjid and *Rauza* in Ghikântâ Road, stand about 120 yards south of the preceding. Of the mosque a part of the back wall containing the fine central *Mihrab*¹ is all that remains. The *rauza* is in fair preservation. The site covers 797 square yards, but the ground to the north and east has been built over with houses and shops by the Panchâyat.

16. RAUZA OF SAYYID ABDULLAH 'ÎDRUS IN JHAVERÎWÂDÂ.

The *Rauza* of Sayyid Hazrat Shams al-shamas Shaikh bin Abdullah al-'Îdrûs in Jhaveriwâdâ, lying about 220 yards to the east of the preceding, is a fine mausoleum of stone, of the usual domed type enclosed with perforated stone panelled screens. The accom-

panying illustration (No. 8) will best help to explain this building. It belongs to the family of Sayyid 'Îdrûs or Edrus, and contains three large and two small tombs, the central one being that of the first 'Îdrûs that came to India,² over which is a canopy inlaid with mother-of-pearl. Sayyid Abûbâkr 'Îdrûs, the ancestor of the 'Îdrûs family, is said to have come to Western India in the sixteenth century or in the reign of



8. RAUZA OF SAYYID SHAMS-AL-SHAMAS SHAIKH AL-'ÎDRUS.

¹ Conf. Hope and Fergusson's *Archit. of Ahmadabad*, Plate 92.

² The descendants of "that sun of suns, Sayyid Abûbâkr 'Îdrûs abandoned altogether their own land, and, attracted by the Sultân's (Mahmûd III) benevolence, settled at Ahmadâbâd."—*Mirât-i-Sikandari* in Bayley's *Gujarât*, p. 442. The illustration (No. 9), with information relating to it, I owe to the kindness of Sayyid F. Abûbâkr Edrûs, a member of the family and Huzûr Deputy Collector, Ahmadâbâd.

Maḥmūd III and died in 1623. In his honour Mirzā Sayyid Beg built a mosque in Sayyidpura, Surat in 1639. The Rauza here is all whitewashed and is held by the present Sayyid 'Īdrūs who lives at Surat. In the old survey of 1824, the area is stated at 3921 square yards, of which 226 have since been declared private property, but from the survey of 1863-67 Mr. Fernandez gives the area in 1886 as only 1926 square yards.¹

17. Qāzī 'Alī's MASJID, &c.

Husain Sayyid's Masjid, known as Qāzī 'Alī's Masjid in Pānchapati Road, at the entrance to the Mughal Poḷ—on the outer side of the gate and lying about 80 yards west from Sakar Khān's masjid, is a small one, probably not the original structure, and is in charge of Sunni Bohrās. On the other side of the entrance to Mughal Poḷ stands a very old marble tomb on an open platform which probably was originally in the same area. (*R.L.*, No. 76.)

18. ASHRAF KHĀN'S MOSQUE, &c.

Ashraf Khān's Masjid and Badā Miyān Sāheb's burial-place are in Navi-Moholat and Suigarā-poḷ in the Kālupur quarter, about a quarter of a mile south-south-east of the preceding and a hundred yards from the city wall. The original mosque was built by Ashraf Khān, a noble under Shāh Quṭb-ad-dīn, but has long since entirely disappeared; and the Bohrās, who own it, have erected a modern brick structure on the site, with carved wooden pillars and ceiling. Part of the west wall is constructed with perforated stone slabs. The structure is whitewashed and kept in good order. Built into the walls are two inscriptions on marble slabs that must have come from mosques that have long since been destroyed; the first is of the time of Aḥmad Shāh, and reads thus:—

"An atom of Thy grace, O cherisher of (thy) servants!
Is better than a thousand years of gifts and prayers.

In the reign of the Khalifah of the age, who trusts in Allah and asks his help, Naṣir-ad-dunyā wa'd-dīn Abū'l Faṭḥ Aḥmad, son of Muḥammad Shāh, son of Muzaḥfir Shāh the Sultān—may his Khalifah be perpetuated and his clemency extended!—this house and noble graceful place was built for Allah by the mean weak worshipper 'Ālamgir who hopes for the mercy of the creator. The 19th of the holy month Muḥarram the year 826"—24th December 1423.

The other inscription is on the wall on the right hand and belongs to the reign of Maḥmūd Shāh I. It begins with the verse *Qorān*, s. lxii, v. 18, and the usual saying of the prophet about the "house in paradise," and adds,—“The work of the great Sultān, the defender of the world and of the religion, the possessor of victory—Maḥmūd, son of Muḥammad Shāh, son of Aḥmad Shāh, son of Muḥammad Shāh,

¹ A. W. Crawley-Boevey's *Scheme*, pp. xlii, No. 36, and lxxxiv, No. 43; *I.*, p. 124, or *R.L.*, No. 57.

son of Muẓaffar Shāh the Sultān—may Allah perpetuate his Khalifat! . . . The eighteenth of the month Muḥarram in the year eight hundred ninety-six" (2nd December 1490).¹

To the north-east is the Rauẓa of Sayyid Shams-ad-din, with a canopy over the tomb. He is said to have been a man of learning and piety who died about 1735, and has since been recognised as a Pīr. To the north-west of this rauẓa are two tombs in niches:—the one of Shāh 'Abd-al Rassūl Khodā Noma, the pīr of Shams-ad-din and father of Badā Sāheb Khodā Noma, who is buried in the other tomb; he was the first pīr of the Junāgaḍh Nawābs, and his sixth direct descendant was Sayyid 'Ābd-al Qadr, alias Bāwā Miyān—the pīrzāda in 1885.

A permanent annual allowance of 155 rupees is drawn from the Collector's treasury for this mosque and rauẓa. Adjoining the mosque is a small low room where are buried fifteen 'Alim—men very learned in Muhammadan theology. The area belonging to this establishment is 1438 square yards. (*L.*, p. 160, No. 72; *R.L.*, No. 45.)

19. PīRMAD SHĀH'S MOSQUE AND RAUẒA.

Pīrmad Shāh's mosque and rauẓa are in Jhāveriwādā, near the civil hospital, on the way from Pankornākā to Ghikāntā, and about 170 yards south from Shaikh Muḥammad Jāhid's rauẓa. The mosque is of brick, was erected about the middle of the eighteenth century, but is of no merit. The rauẓa contains the grave of Pīrmad Shāh, and is well looked after; it is the principal masjid of the Sunni Bohrās, and the site has an area of an acre and 113 square yards: but possesses altogether ground of the extent of 2 acres 2 roods and 35 perches,—only 274 square yards having been alienated since 1824. Behind the rauẓa is another of Badā Miyān Sāheb—built of brick, of effective appearance, with a small ruined mosque having a Divānkhāna used as a dwelling. It has a site measuring 996 square yards (*R.L.*, No. 84).

20. SHAIKH MUḤAMMAD CHISHṬĪ'S RAUẒA.

Shaikh Muḥammad Chishṭī's, otherwise called Shaikh Aḥmad Chishṭī's rauẓa, in a secluded corner, off Patwasheri Khās Bāzār, is a fine domed brick structure containing three tombs with four arched doorways, and possibly has originally belonged to a mosque of which the site is now built over, leaving only 48 square yards for the rauẓa.

21. BĀWĀ AḤMAD'S MASJID.

Bāwā Aḥmad's (or Adham's) Masjid in Salopos Road is to the west of Malik Shāban's in Khās Bāzār. The original has disappeared, and a poor substitute with a

¹ *Lists*, pp. 257-258; or *R.L.*, p. 303.

qibla, has been erected on the site. The *rauza* is also a small tiled building in memory of one of the twelve *bâbâs* who are said to have aided the four *Aḥmads* at the founding of the city, Tuesday, 3rd March, 1411 A.D.¹

22. 'ALEF (OR AḤMAD) MURTAZA'S MASJID.

'Alef or Aḥmad Murtaza's masjid in Khâs Bâzâr, near the Karañj and across the street to the south-west of Malik Shâbân's, is a small building on a high plinth, originally built, it is said, about the same time as the Jâmi' Masjid, and was finished in the fifteenth century. It is in use and in good repair. The dwarf minarets have been renewed. The property extends to 512 square yards.

23. RÂO MAṆḌALIK'S TOMB.

The tomb of Khân Jahân or Râo Maṇḍalik of Sorath, who was defeated by Maḥmûd Baiqara about 1472 and accepted Muhammadanism², is in the Kandoi Ol at the commencement of Kâlupur Road from Mânîk-chauk, on the right side going eastwards. It is a small room about 8 feet square, part of which is let. The shrine is still venerated and flowers placed on the tomb daily.

24. GALIYÂRÂ'S MASJID AND PÎR KAMÂL'S GRAVEYARD.

These are on the way from Khadiyâ Chauki to Navâ Darwâzâ, about 80 and 100 yards north-west of Sârangpur masjid, and 50 yards apart. The original name of this fine little mosque is lost: it is peculiar in style—the entrance is surmounted by a finely carved stone arch. It must have stood in a large enclosure, as there is reason to believe that Pîr Kamâl's graveyard formed part of it; but it has been entirely built over on the south and east right up to the *sen*. In the graveyard enclosure, now measuring only 66 square yards, are three tombs, two of them still of marble, said to be of the time of Shâh 'Âlam, and held in veneration by the Bohrâ sect of Musalmâns, —devotions being paid at them on the occasions of weddings, &c. The site of the mosque measures only 7 perches (*R.L.*, Nos. 58, 59).

¹ The legend respecting the founding of Aḥmadâbâd by the help of "the four Aḥmads"—Sultân Aḥmad I, Shaikh Aḥmad Kattû, Qâzi Aḥmad and Malik Aḥmad—has been given elsewhere (*Arch. Surv. Westn. India*, vol. II, p. 2; Conf. Bayley, *Hist. of Gujarat*, p. 90; *Ind. Ant.*, vol. IV, p. 289). But an addition is made to the story, saying that they were helped by "twelve Bâbâs" or notable Qalandar faqîrs. Colonel John W. Watson gave their names as:—Bâbâ Khoju, Bâbâ Laru, Bâbâ Karâmal, buried at Dholkâ; Bâbâ 'Alî Shîr and Bâbâ Maḥmûd, buried at Sarkhej; another Bâbâ 'Alî Shîr, who used to sit stark naked; Bâbâ Tavakkal, buried in the Nasirâbâd suburb; Bâbâ Lulai, buried in Mañjhuri; Bâbâ Aḥmad Nâgori, buried near the Nâlband Masjid; Bâbâ Ladha, buried near the Ḥilim wicket gate; Bâbâ Dhokal, buried between the Shâhpur and Delhi gates, and Bâbâ Sayyâh, buried at Viramgâm. There is another—Bâbâ Kamâl Kirmânî, about whom authorities differ (*Bom. Gaz.*, vol. IV, p. 249 f.).

² Conf. Bird, *Hist. of Gujarat*, p. 209; Burgess, *Tarikh-i-Sorath*, p. 117 f; Bayley, *Hist. of Gujarat*, p. 189; and *Râs Mâlû*, vol. I, p. 274 f.

25. 'ÂLAM KHÂN'S RAUZA.

'Âlam Khân's rauza is in Dânapeth or the Grain Market, close to the municipal office. 'Âlam Khân is said to have been a noble of Ahmad Shâh's. The rauza is of stone with some architectural pretensions, but it has been got hold of, with the surrounding graveyard, by a family of faqîrs who have built rooms against all sides of it and use it as a store-room. The area is 1553 square yards or fully 51 perches.

26. RAUZA NEAR THE RÂYAKHAD GATE.

A small rauza stands near Râyakhad Gate, at the south end of the Jail garden, on the west of the city. This has been a fine domed brick building with two perforated stone windows to the north and south, and the entrance door to the west—also of carved stone. It is in the middle of a site measuring 1907 square yards, in which are several tombs: but this is one of the glaring instances of spoliation; for the rauza itself has been declared and confirmed by the City Survey Department as private property, while the surrounding area, which appears to have been a cemetery, has been brought under the Summary Settlement Act. The rauza and land are now in possession of a Pârsi family, and were probably acquired in the same way as Nawâb Shâh Jahân's and Momin Khân's Masjids were by Mrs. King.¹ (*R.L.*, No. 56.)

27. SAYYID MUHAMMAD JA'FAR AND SARÂZI SÂHEB'S RAUZAS.

The rauzas of Sayyid Muḥammad Ja'far and Sarâzi Sâheb are in Oliphant Road, about 270 yards W.N.W. from Dastur Khân's masjid. One of the rauzas is of stone with perforated panelled windows, and contains three tombs—now stripped of their marble casings. The other is of brick, but the tombs have been removed to convert it into a storehouse. (*R.L.*, No. 60.)

28. QÂZÎ SÂHEB'S MASJID.

Qâzi Sâheb's or Râyapur Masjid, originally called Naṣîr Sayyid's, in Pânchhatḍi Râyapur, about 670 yards E.N.E. from Râni Sipari's mosque, is a small masjid in ruins—the roof having fallen.

Though it once had extensive grounds, they have now been largely appropriated, leaving only 730 square yards chiefly in front and occupied by potters and dyers. Its adjunct rauza stood forty yards distant, where is a fine marble tomb over the grave of Naṣîr Sayyid, carved in the style of the royal sarcophagi at Sarkhej and in Ahmad Shâh's rauza; portions of marble, however, have been removed and replaced by plaster. (*R.L.*, Nos. 61, 62.)

29. SAYYID JA'FAR'S MASJID.

Sayyid Ja'far's Masjid near Sayyidwâḍâ in Astodiyâ Chakla—nearly opposite Râni Sipari's mosque—is of brick but well built. In the rauza was buried Sayyid

¹ *Supra*, No. 9.

Hâmid Ja'far Shirâzi, the founder of the sect of Sunni Bohrâs—an offshoot from the Shiah Bohrâs. Another rauza contains nine tombs, and the area is full of graves. The property extends to 1419 square yards. (*R.L.*, No. 69.)

30. SHÂH MUHAMMAD 'ALÎ'S MASJID.

Shâh Muḥammad 'Alî's masjid in Jamâlpur chakla, about 380 yards from the gate, is a stone and brick building, partly modern and very plain: the minarets rise only about three feet above the roof. Opposite to the mosque is the rauza of Shâh Muḥammad 'Alî, the floor and tomb of which are of marble. There is also another rauza of brick within the enclosure, which extends to 2293 square yards, and is let to workpeople. (*R.L.*, No. 64.)

31. MUṢṬAFÂ SAYYID'S MASJID.

Muṣṭafâ Sayyid's masjid, about 100 yards to the south of Nawâb Sardâr Khân's masjid and rauza, is a small stone mosque and whitewashed. It had once extensive grounds, but they have all been encroached upon. (*R.L.*, No. 36.)

32. PIR QUTB-AD-DÎN SAYYID'S RAUZA.

The Rauza of Qutb-ad-dîn, Qutb Shâh Divân, or Pîr Qutb Sayyid is about 80 yards to the east of Muṣṭafâ Sayyid's masjid. It is ascribed to the time of Aḥmad Shâh, and contains three tombs, but was taken possession of by a Faqîr about twenty years ago, when the area unappropriated was 608 square yards. An inscription in it, after quoting Qoran, sura xv, v. 46, proceeds in rather more than usual grandiloquent terms:—"During the time of the conquering rule and in the days of the permanent reign of the crown-bearing celebrated Khidiv, the Sultân of the Sulâns of the age, the abolisher of unbelief and rebellion, protector of the world and of religion—Aḥmad Shâh, son of Muḥammad Shâh, son of Muẓaffar Shâh the Sultân, son of a Sultân (*twice*)—may Allah perpetuate his kingdom and increase his rule and Sultânship. This tomb was built by the slave, hoping for the mercy of the 'Nourisher,' Qutb bin Khâjagî. The completion of this pious good work for the object of acquiring joy, in the month Muharram." But no year is stated. (*Rev. Lists*, Nos. 34 and 65.)

It probably had at one time extensive grounds, but they had been reduced to 782 square yards in 1824 and to 608 in 1863.

33. MAKHDÛM SÂHEB'S MASJID, &c.

Makhdûm Sâheb's Masjid, rauza and graveyard, near Dathapathar, in Jamâlpur, has now an area of 1976 square yards, 115 square yards having been appropriated before 1863. The mosque has disappeared and is replaced by a brick and clay erection; the rauza was of stone, but has lost its verandah on three sides. The tomb of Makhdûm Sâheb, said to have been a Vazîr of Shâh 'Alam—is of marble under an ornamental canopy. (*L.*, 59, or *R.L.*, No. 35.)

34. SHAH BAÐÂ QÂSIM'S RAUZA.

Shâh Bađâ Qâsim's rauza close by the Kachni masjid, at Tâjpur in Jamâlpur quarter, about a hundred yards north-east of Makhdûm Shâh's, is a fine stone building, the outer dome resting on twenty columns, and the walls formed of carved stone slabs resting on a base. Some of these slabs have been destroyed or removed and the spaces blocked up.

Within are four tombs, the chief having a canopy over it. Shâh Bađâ Qâsim is said to have been the teacher of Shâh 'Âlam. The grounds to the north and west have been encroached upon by private houses; they were at one time extensive and in 1824 measured 1645 square yards, now reduced to 992. (*R.L.*, p. 80, No. 114.)

35. KÂCHNI MASJID.

Kâchni masjid in Tâjpur, Jamâlpur, is about 170 yards east from Makhdûm Shâh's. This is a notable mosque, built of stone, the original name of which has been lost. It has a storey on timber beams which was formerly roofed with glazed tiles of a bluish colour—hence the epithet of Kâch (glass) mosque. The two pillars in front and the walls are of stone. It has three *mihrâbs* and a *mimbar* of five steps. On the walls are a number of inscriptions, among which the *kâlîma* appears six times; but the slabs over the central and left *mihrâbs* have been removed. The bases of the minarets are carved, but not richly. The interior is whitewashed and coloured. The court has a porch on the north side and has been enclosed by a high wall with balcony windows. In it is a water-cistern. The ascription of its erection to Maḥmûd of Ghazni is evidently an unfounded tradition. The area in 1824 measured 904 square yards, but it has now lost 192,—mostly declared private property. (*L.*, p. 159, No. 60, or *R.L.*, p. 80, No. 113.)

36. PIRÂNPIR'S DARGÂH.

The Pirânpir or Bâla Muḥi-ad-din's Dargâh is in Jamâlpur, near the Khânjâ Gate, a furlong west from Jamâlpur chakla. 'Abd-al Qâdir Jilânî,¹ also called Ghaus-al-A'zam Muḥi-ad-din Pîr-i-Dastagîr and Pirân-Pîr, a descendant of the Imâm Ḥasan, the grandson of Muḥammad, through his daughter Fâtimah and the Khalifah 'Alî, is the most notable Pîr of the Sunni sect of Islâm; and one of his descendants—Shâh 'Abd-al Khalak Sayyid 'Abd-al Qâdir—is said to have come from Baghdâd and settled here about the beginning of the seventeenth century. He is buried in this rauza, which has perforated walls and contains the marble tomb. The masjid is in a separate enclosure, and having fallen into decay, was


¹ He was born A.H. 471 (A.D. 1078) and died A.H. 551 (Feb. 1166), and was buried at Baghdâd. He was the founder of the Qâdiriya sect of Dervishes and is said to have written many books on mystical theology. A son named Sayyid 'Abdullah is said to have come to Sindu, and his tomb is shown at Tatta.

rebuilt of brick in a plain style not long since. The rauza of Hazrat Pir connected with these is of brick and contains two plain marble tombs, said to be those of Sayyid Miyân and Sayyid 'Askari Miyân, belonging to the Pirânpir family; and, outside the enclosure, which has been encroached upon on the east, under a tamarind tree, are two tombs of rough marble. These are the graves of Rajê Sharifa, daughter of Mahbûb Alla, A.H. 1150 (or A.D. 1738) and Sayyid Qâsim of the family of Shamê Burhânî. The ground extends to 3287 square yards, and the rauza receives from the collector's treasury an allowance of two rupees annually. (*R.L.*, No. 73.)

37. KHÂN JAHÂN'S MASJID.

The Khân Jahân Masjid, near the Khânjâ gate, and close to the Protestant cemetery, on the river side at the south-west corner of the city walls, is a cut stone building of trabeate style and apparent antiquity, but in good preservation,

but whitewashed inside. It is roofed with small domes and has three *mihrâbs*,—from over the central one of which the inscription slab has been removed. The minbar has seven steps. The rauza in front has partly fallen—only two of the original domes being left—but the tomb of Khân Jahân still remains, and is said to belong to the earlier half of the fifteenth century. The grounds extend to 1668 square yards. (*L.*, p. 160, No. 69.)



9. MODERN BIRD-ROOST AT AHMADABAD.

In a city like Ahmadâbâd, where *Śrāvaks* and other Hindû sects, that lay so much stress on the preservation of animal life, are so numerous, and where the hereditary office of Nagar Seth or "city chief" belongs to a distinguished *Śrāvaka* family, we naturally expect to find a Pânjrapol or animal asylum. In the district there are nine such established—at Ahmadâbâd, Dholerâ, Virungâm Mândal, Dholka, Sâmand, Parântej, Goghâ, and Barwâlâ, of which those at Ahmadâbâd and Dholerâ are the most important,—the first having an annual revenue of about 15,000 rupees and the second of 10,000. In these the inmates are cows, bullocks, buffaloes, blind cattle, goats,

horses, cats, monkeys, fowls and birds wild and tame. To each pânjrapol is usually added a Jivât-khâna or insect room for maggots and small vermin. These institutions are supported by taxes on marriages, mercantile transactions, &c.¹

And as it is a work of merit to support all living creatures, we find bird-roosts erected in the streets where birds can be fed with grain. Some of these are of considerable elegance of design and deserving attention. As an example the illustration No. 9 will convey a good idea of the usual style of these.

¹ Dr. Drummond, in the glossary to his *Illustrations of the Grammatical Parts of the Guzerattee, Mahratta, &c. Languages* (1808) has some severe remarks on the management of these asylums. But see also *Bomb. Gazetteer*, vol. IV, pp. 114-116.

CHAPTER XVI.

MUHAMMADAN MOSQUES AND TOMBS IN THE SUBURBS, &c.

THE survey of the architectural remains in the suburbs of Aḥmadâbâd, as of those within the city, has only included the more notable and better known; the number in the suburbs and neighbouring villages is not ascertained, but a few notes respecting some of them may be added in closing this account of the structures witnessing to the former greatness of the city.

1. TOMBS OF 'ĀZAM AND MU'AZZAM KHÂN.

To the south-west of the city on the way to Sarkhej, and scarcely a mile beyond Pâldî Kochrab is a massive brick mausoleum, like that of Daryâ Khân, and probably of about the same age, A.D. 1457. It is the tomb of two brothers—'Āzam and Mu'azzam Khân, who were Khurâsânîs and said to have been very skilful archers. The *Mirât-i-Sikandari* says they built this tomb at Shâh Gumân with a masjid close by, and a tank, but because one of them had committed a serious crime, the tank would not hold water. Tradition would have us believe that they were the architects of Sarkhej, and enriched themselves at the expense of the workmen they employed.¹ The mosque seems to have entirely disappeared.

2. RAUZA OF QÂSIM KHÂN.

About half a mile north of Kochrab, and about as far west from the Bhadr is the small village of Chhudâvâd, where is the rauza of Qâsim Khân. It stands on Government land of five and a third acres in extent, and the building—once a fine one with a high dome, but much dilapidated from neglect—is not claimed by anyone, but is used by the tenants of the land.

3. MÛSÂ SUHÂG'S MOSQUE AND RAUZA.

To the east side of the river in the lands of Daryâpur Qâzipur village, to the east of Daryâ Khân's tomb, is the Rauza and mosque known as Hazrat Mûsâ Suhâg's. They are in a fortified enclosure with a large gate at the entrance. Within the walls is a second enclosure arched on all sides, in which is the rauza: the buildings are of brick and lime; the masjid is low and has three arched entrances in the façade. In it is a dedicatory inscription stating that it was built by Ja'far "with elegant arrangements" in A.H. 1101 or A.D. 1690. The buildings have no architectural merits, and the tradition that they belong to the time of the

¹ Hope, *Ahmedabad*, p. 52; *Bombay Gazetteer*, vol. IV p. 291.

Ahmadâbâd Sultâns, has no support. The legend of Mûsâ, however, is curious :—He was a faqîr, generally known as *Auliya* or the Saint, and the story is that “once, in answer to his prayers, rain was sent and a famine stayed. Then the people pressed after him so much that, to escape their notice, he dressed like a woman. At his mosque there are five tombs, four of them inside and one outside of the mosque enclosure. The story of these tombs is that once the rains were too heavy and the king (or viceroy) went to the holy man to ask him to pray to have the rain stopped. But he, fearing a fresh attack of popularity, prayed that the ground might cover him. His prayer was granted and when the king tried to dig him out, his head rose in another place, and again disappeared. Digging at this place the head appeared in a new spot. And so it happened four times. Then the king said, ‘Let us offer flowers at his tomb.’ But the saint again appeared, this time outside of the mosque enclosure, and said he wanted no offerings. The five tombs mark the five places thus consecrated. In the mosque enclosure is a very old and large *champâ* tree with many of its twigs and branches hung with glass bracelets. Those anxious to have children come and offer the saint bangles, 7, 11, 13, 21, 29, or 126, according to their means and importunity. If the saint favours their wish, the *champâ* tree snatches up the bracelets and wears them on its arms. From Mûsâ Suhâg sprang an order of beggars who, like their master, dress in women’s clothes and wear nose-rings.”

The place is all studded with tombs. The land connected with it has an area of nearly 22 acres, assessed at 101 rupees, but the quit-rent paid to government is less than 13 rupees, the difference being 88 rupees 6 annas of loss to the revenue. This mosque has also another tract of land measuring fully 7 acres and $3\frac{1}{4}$ roods, assessed at 20 rupees, for which a quit-rent of only an eighth of the assessment is paid to the treasury.

Though Ahmadâbâd is the headquarters of the followers of Mûsâ Suhâg, there are usually only two men at the rauza. Celibacy, which formed the distinctive rule of the sect, and used to be rigidly observed by his disciples, is now set aside at pleasure; and the order is rapidly diminishing.¹

4. THE BADÂMÎ MOSQUE.

In the same vicinity is a plain massive brick structure known as the Badâmi mosque with adjoining rauza. The mosque had three domes and as many *mihrâbs*, but was seriously damaged by the great flood in 1875, whilst the rauza—of more ornate style—was less injured. There seem to have been two graves in it, but the floor has been robbed of its pavement. It is in possession of the Qâzi of Shâhpur, but the land belongs to Government and measures three and a half acres. Tradition ascribes its erection to the workmen employed in building the masjid of Achut Bibi close by, who subscribed a badâm or fortieth of a païs per diem.

¹ *Gazetteer of Ahmedabad*, p. 381; J. F. Fernandez, in Appendix to Crawley-Boevey’s *Scheme*, p. lxvii.

5. MOSQUE AND RAUZA OF BÂWÂ BÂRAKALLA CHISHTÎ AND OTHERS.

Near by is the ruined mosque and rauza of Bâwâ Bârakalla Chishtî, a contemporary of Shâh 'Âlam; also the Bâdâ masjid, and that of Shâh Isra 'Allah, the son of Shâh 'Abdul-Faṭḥ, whose mosque is in the Shâhpur ward. Besides these other brick remains in the same locality are enumerated in *Lists of Antiq. Rem.*, p. 164; or *R.L.*, p. 85.

6. TWO TOMBS OPPOSITE DARYÂ KHÂN'S.

On the way from the city to Shâh-i Bâgh, and nearly opposite to Daryâ Khân's Dargâh, stand two low tombs of a style quite different from anything else about Ahmadâbâd. They are represented in the accompanying illustration, No. 10, and



10. EIGHTEENTH-CENTURY TOMBS NORTH OF AHMADABAD.

are of brick, well plastered, and nearly square with two doors each—on the east and west sides, and three on the others, the arches over them being scalloped. One of them has a small porch standing on two advanced pillars. But the striking feature is their roofs, which come down at the corners, so as to present an arched façade on every face. This roof is ornamented by rosettes in plaster at the corners, middle of each side, and summit. The style is of Bengâli origin and seems to have

arisen from the form of huts in Bengal, constructed of bambu, in which a curvilinear form of roof is always employed; this, converted into brick and plaster, became the style of Bengal, and spread in the latter part of the seventeenth century to Dehlî, and later to the Panjâb, and since has become largely adopted all over Hindustan.¹ Thus, early in the eighteenth century it appears in the great palace of Jayasingh at Jaypur, and in the nineteenth it has been adopted by an English engineer in the Albert museum at the same city.

This style is exemplified in these two tombs at Ahmadâbâd, constructed in the eighteenth century, but in troublous times which perhaps prevented any further imitation.

7. SHÂH BÂDSHÂH PÎR'S RAUZA.

In the suburb of Shahrkotdâ, on the east side of the city, are several rauzas, among which may be mentioned Shâh Bâdshâh Pîr's, built of stone and standing on twelve pillars, open on all sides. In it are three graves (*qabr*) constructed of stone, one of which is said to be that of the founder. It is known by the name of

¹ Fergusson, *Ind. and Eastn. Arch.*, p. 546; R. Phené Spiers, *Archit. East and West*, p. 18.

Kasbin no Ghumto, as the ground round it is used as a cemetery by the courtezans of the city.

8. CHÂR TOĀ QABRASTÂN.

Châr Tolâ masjid or Châr Tođâ Qabrastân, in the same village, is a stone masjid without minarets. It has three *mihrâbs*—but the central one has been carried off—the other two are well carved and in good preservation, but whitewashed. The land belonging to it extends to $24\frac{3}{4}$ acres assessed at 152 $\frac{3}{4}$ rupees, but granted by a *sanad* at a quit-rent of one-eighth of this.

9. PİR QÂSİM KHÂN'S RAUZA.

PİR Qâsim Khân's rauza near by is of stone and brick. Under the dome are three tombs on a marble platform, over which is a gaudily painted ornamental canopy. The floor is of marble, as is also the floor of the vestibule leading into the rauza. The walls from about six feet above the floor are faced with carved stone panels, and in the middle of the side walls is a carefully wrought *mihrâb* under a domed vestibule. Qâsim Shâh was nephew of Imâm Shâh the founder of the Pîrânâ sect of Musulmâns and his shrine here is held in great veneration by his followers.

10. PİR BÂQİR SHÂH'S RAUZA.

Near it is the rauza of PİR Bâqir Shâh—a heavy brick structure containing the tomb of Bâqir Shâh, the son of Imâm Shâh of Pîrânâ. It is also held in great respect, and people come from a distance to make offerings and pay their devotions here.

11. PİR MASHÂYEK'S RAUZA.

PİR Mashâyek's rauza, also in Shahrkođâ, stands in a fortified enclosure and is a fine stone building with a verandah round it, having twenty pillars in the outer sides supporting the roof and connected by arches. The inner walls are formed of carved stone slabs between the pillars. The central tomb has a canopy over it, and round it are six other graves. To the west of the rauza is a plain but deep masjid of stone and brick; and a second rauza contains the tomb of PİR Abû Tâlib, the grandson of PİR Mashâyek. This was formerly open on all sides, but the arches were blocked up about twenty years ago. All the buildings here are whitewashed.

12. SHÂH MAHBÛB MAJZUB'S RAUZA.

Shâh Mahbûb Majzub's rauza is a low-roofed brick building in the railway suburb near the Kalupur gate, and is said to be the tomb of Shâh Mahbûb, a contemporary of Shâh Khûb, about 1530–40, a man of great piety and much venerated and in whose honour an *'urs* is held yearly on the anniversary of his death. The original mosque and rauza have disappeared.

CHAPTER XVII.

HINDU AHMADABAD.

ANCIENT CITY: JAINA TEMPLES IN THE CITY; SETH HEMABHAI'S TEMPLE.
PLATES LXVII-LXXI.

LONG before Ahmad Shâh laid out the capital for his kingdom, there had been a town on the site of the modern city. About A.D. 1070 Karna Solañki is said to have attacked a powerful Bhilla chief named Âsâ, who ruled at Âsâpalli or Âsâval, close to where the old step-well of Mâtâ Bhavâni is—and whilst in the district, he built a temple to the goddess Kocharabâ, which must have been at the present village of Kochrab on the west side of the river, opposite to Ahmadâbâd. He is also credited with founding a city under the name of Karṇâvatî, which has been generally regarded as the predecessor of Ahmadâbâd. In the following reign Śrīdeva, a great Jaina doctor, is mentioned as residing in an Upâśraya, connected with a Jaina temple there, and the famous Hemachandra seems to have been brought up in the house of the minister or local governor Udayana of the same city. At a later date we find the city designated as Śrinagara, and evidently a place of great importance.

But though the Bhadr still retains its old name, from a temple of Bhadrakâli, there is scarcely any reference in Muslim history to this earlier city. We find pillars and carved slabs, indeed, in the earlier mosques, that were certainly taken from much older Hindû temples.

But during excavations made in the Bhadr some twenty years ago, considerable portions of ancient Hindû sculptures were brought to light. Of these several examples are illustrated on Plates LXVII and LXVIII. Figures 1 and 2 are probably from some panelled screen of a Jaina temple of about the twelfth century, and bear some descriptive inscriptions in characters of that period; 3 is a form of Śiva as Naṭêśa; 4 represents Viṣṇu mounted on Śeṣha, in a way quite analogous to that in the roof panel of the Mânod temple,¹ though the knotting of the bodies of the Nâgas more closely resembles that on a large slab in the great Jaina temple at Rânpur in Godwâr. Figures 5 and 6 are representations of Mahishamardani or Mahishaghni, —a personification of Durgâ or Chandâ—slaying the Asura named Mahisha². Figure 7 has represented Gaṇeśa, the chief of the goblins, and fig. 8 is the same divinity with a female seated on his knee:—who this may represent it is difficult to say, since it is generally understood that the elephant-headed god has no Śakti ascribed to him—on the ground that he has never found a partner equal in beauty to his mother Pârvatî. Figure 9 has represented a four-armed Kâli, the terrible Śakti of Śiva, holding a skull in one of her left hands; fig. 10 perhaps represented a form

¹ *Arch. Sur. Westn. Ind.*, vol. IX, p. 109.

² Another Mahishâsura appears in the *Mahâbhârata*, and is killed by Skanda or Kârttikeya.

of Śiva or Bhairava, and fig. 11 is a form of Nārāyaṇa or Viṣṇu. Figures 12, 13 and 18, like most of the others, are from the outer walls of a temple and represent those dancing Yoginīs that are favourite subjects for such decorations; fig. 14 has been a small figure of Narasiṃha or Viṣṇu tearing up the body of the Daitya Hiranyakaśipu; fig. 15 is another small fragment; and fig. 17 represents Viṣṇu on Garuḍa, whilst figure 16 is a pāliṃ or monumental slab, dated Saṃvat 1359 or A.D. 1302.

It will be noted that though the majority of these fragments belongs to the Vaiṣṇava sect, Śaiva divinities are also fairly represented: the sculptures, however, are of inferior artistic merit.

JAINA TEMPLES IN AHMADABAD.

Notwithstanding all the efforts of the Muhammadan rulers to stamp out the Jaina religion in Gujarāt, it continued to be practised and buildings to be erected for its ritual during the whole period of their rule, and there are now some hundred and twenty temples of this sect in Ahmadābād, which is the headquarters of the Gujarāt Jains. Besides, in every Jain's or Śrāvaka's house, there is a cellar (*bhoyerāṭh*) containing images upon an altar for the family worship.

Of the Jaina temples, many of course require no notice, but a few of the more notable may be mentioned. In the Māṇḍvi poḷ of the Jamālpur ward, is a temple known as the Samara or Sameta Śikhara, from its containing an ideal representation of Sammeṃya or Sameta Śikhara—the religious title of Mount Pārśvanātha in the Hazāribāgh district of Bengal, which is particularly sacred among the Jainas, and where, they say, twenty-one out of their twenty-four Arhats or Tirthakaras attained to *moksha* or deliverance from transmigration,—all in a standing (*kāyotsarga*) attitude.¹ Hence it is visited by Śrāvaka pilgrims from the remotest parts of India; and those who cannot undertake the long pilgrimage pay their devotions to its representations here and elsewhere. For there are other temples in honour of the holy mount: thus in the two wings of the temple of Vastupāla and Tejahpāla on mount Gīrnār are solid structures called *samosanas*, built in tiers,—that in the south wing being Sameta Śikhara, and the other Sumeru or a personified Mount Meru; and on Śatruṅjaya, near the great temple of Adinātha, is another of Sameta Śikhara, with a representation of the same sort.²

This temple in the Māṇḍvi poḷ consists of a large room, the roof of which is supported by pillars about 6½ feet from the walls—four across each end and six on each side—including the corner ones. The entrance is close to the south-east corner, and near the south end of the west side is a shrine in the wall containing the image of Pārśvanātha, with other smaller Jinas in brass and marble. The floor is of beautifully inlaid marble. But the north end of the area within the pillars is

¹ *Trans. R. Asiat. Soc.*, vol. III, p. 349; Bühler, *The Indian Sect of the Jainas*, Eng. tr., p. 66. Mount Pārśvanātha is in lat. 23° 58' N., and long. 86° 11' E. See *Ind. Ant.*, vol. XXXI, pp. 65ff.

² *Arch. Surv. Westn. Ind.*, vol. II, Plate xxxiv, p. 170; Fergusson, *Indian and Eastn. Archit.*, p. 231; *Lists of Ant. Rem. Bombay Pres*, 1st ed., p. 197. (No. 103.)

occupied by a large wooden representation, locally known as *Samara-śikhara*.¹ It stands on a plinth about three feet high and rises in pyramidal form to a height of fully 10 feet. Little shrines are formed on it, some larger, some smaller, of which some are appropriated to various Tirthakaras, whilst others are surrounded by dancers and musicians—figures about 8 inches in height—the summit being crowned by a larger shrine with choristers under its canopy. The whole is moved by mechanism, by which the little figures dance round the temples to which they are attached. A wire railing surrounds this huge toy, and a silk canopy hangs over it.

This temple is ascribed to the second half of the seventeenth century, and is said to have cost 1,36,000 rupees; but another version says it was built by one Rupvijaya at much less cost, and the money raised by subscription.

In the same neighbourhood, in Tokarsâh's pol, is an old temple of Godî Pârsvanâtha, built by the Jaina *panch*, at a cost, it is said, of about half a lākḥ of rupees.

In the Khâdiyâ ward in Kâlupur is an old temple of Sambhavanâtha, the third Tirthakara, which, like many others, has an underground cellar (*bhoyerûn*), containing images of Sambhava and of Chintâman-nâtha. These underground cellars seem to have been introduced to save, if possible, their valued images from the iconoclastic propensities of the Muhammadans.²

There are also, in this division, an old temple of Neminâtha in the Chang-pol, and two in the Phatâsa-pol,—one of Mahâvira, rebuilt in 1866 by Śeṭh Umâbhâi Rupchand, and the other, known as Hanśanâthjî's, rebuilt in 1862 by Śeṭhâni Harkuṇwarbâi. The same lady, in 1859, also built a temple of Dharmanâtha—the fifteenth Arhat—in the Janksâl-pol of the Daryâpur division, at a cost of 20,000 rupees.

The temple of Adîśvara Bhagavân in Jhavêrîwâdâ was renewed about 1859 by Śeṭh Lallubhâi Pânâchand. Its underground cellar is about 17 feet square, is entered from the west side, and in the east end is the shrine containing three large seated Tirthakaras on a long marble plinth with small standing figures (*kâyotsarga*) between; the central Jina is Adîśvara Bhagavân or Rishabhanâtha. The shrine is cut off from the maṇḍapa by a wall with three doorways in it, through which the images are seen: one of them is dated Sam. 1666 or A.D. 1609.

The hall is domed on very flat arches, cutting off the corners of the square, and in the north and south walls are three small recesses as for images, whilst the floor is laid with coloured marbles. On the west and east of the dome and in the corners, shafts open into the floor above, and through gratings admit a certain amount of light as well as air.

The stair passes round the south-west corner of this hall and lands in the south-east of the larger hall above. In the lower landing of the stair, opposite the entrance, is a niche containing small figures of Lallubhâi Pânâchand and his wife.

The upper hall is square, with a marble floor, surrounded by a square of twelve pillars, and in the middle of the area they surround are three of the gratings giving

¹ The words *Samara* and *Sameta* are synonymous.

² *Notes of a Visit to Gujarât*, pp. 41, 42; *Archæol. Surv. Westn. India*, vol. II, p. 208.

light to the lower floor. The pillars support an architrave over which are coloured glass windows. In six recesses in the walls are figures of the Yakshas and Yakshinis that attend the different Tirthakaras, among which are readily recognized Gomukha and Chakresvari, the attendants on Âdinâtha, and also Ajita and Satârakâ belonging to Pushpadanta the ninth Jina, together with their cognizances or *chihnas*. The shrine is on the east side, has very elaborately carved wooden doors, and contains five principal seated figures, of white marble, about two and a half feet high; the central one representing Suvidhinâtha or Pushpadanta is slightly larger than the others and wears a golden crown, whilst many smaller figures are placed among the Jinas on the same plinth.

In the *pradakshina* or passage behind the images, are other two gratings over shafts from the lower hall; and all round the shrine walls are little recesses for figures of the Jaina mythology. Above the heads of the principal images the walls are filled in with looking-glass: below they are mostly coloured red, and the pillars, lintels and roof are of carved wood. Outside this hall is a marble-floored room leading to the street. Lakshmichand Kushalchand is said to have repaired or rebuilt the temple, or part of it, in 1844 A.D.

The temple of Sambhavanâtha, the third Tirthakara in Jhavêrîwâdâ-pol, is one of the largest and oldest of these shrines, and is said to have been built at an expense of a lākḥ of rupees. Outside, it is very plain and unpretentious, whilst inside it consists of three apartments—a *maṇḍapa* or porch, the *Sabha maṇḍapa* or assembly hall, and the *nijmandir* or shrine. The floors are laid with coloured marbles and the roof supported on pillars. From the principal hall a stair leads down to an underground temple of the same size and plan and similarly finished. The images are three Tirthakaras about double life size.

In Wisa-pol, in Jhavêrîwâdâ is an old temple of Jagavallabha Pârśvanâtha, which has two underground cellars, one containing a statue of Jagavallabha Pârśvanâtha with a smaller statue on each side; and the other has an image of Adîśvara with smaller figures also on each side.

There are several other temples besides these in the Daryâpura ward of the city, most of which have been restored by wealthy Śrâvaks within the last eighty years.¹

THE GREAT JAINA TEMPLE OF SETH HATHISINGH.

The most notable Jaina temple, however, at Ahmadâbâd is that of Sêṭh Hathisingh, son-in-law of Sêṭh Hemâbhâi Vakhatchand, which stands just outside the Dehli gate on the right of the way to Shâh-i-Bâgh. Together with a Dharmaśâla and a large mansion close by, it was finished in 1848 at an outlay of about a million rupees. The three buildings occupy a large rectangular area, the mansion standing next to the road with a classic portico and containing some handsome rooms.

The temple itself, with its enclosing cloisters, measures over all about 126 feet from north to south—and, exclusive of the entrance porch on the east, 160 feet from east to west. The court is surrounded by cloisters (*bhaṇṭi*) in which, besides three

¹ *Bombay Gazetteer*, vol. IV, p. 301.

small temples on the north, south and west sides—each in line with the centre of the principal *maṇḍapa*—there are the orthodox number of fifty-two small shrines, each crowned by a śikhara or spire. As will be seen from Plate LXIX, this gives a dignity to the outer enclosure, combined with a meaning which is seldom found in any other style of architecture, and the whole arrangement leads pleasingly up to the central feature, showing great skill in the subordination of the various parts.

The inner façade of the cloisters or *bhāmī* (Skr. *bhrama*) is interrupted only by the three small temples mentioned above, by the large entrance porch on the east, and by smaller entrances on the north and south near the east end. The corridor is about nine feet wide all round and is raised by four steps above the level of the court.

The entrance porch on the east projects considerably and is flanked inside by stairs, in line with the *bhāmī* on each side; these rise above the roof of the upper storey in turrets of the "broken square" pattern employed in the śikharas.

From outside some seven steps lead up to the platform of the external porch which is of great magnificence, two storeys in height and most elaborately ornamented. This porch has two advanced pillars and other four in front of the entrance. The platform is broken on the south side by a small old Śaiva shrine for the removal of which, it is said, a very large sum of money was offered on the part of Śeṭh Hathisingh and the Śrāvaks, and the porch was long left unfinished in the hope of its acceptance. This was refused, and finally the cell was left undisturbed, but built closely round on three sides.

The doorway leading into the court is much inferior to most of those of an earlier period; the jambs and lintel are cut up into many compartments and filled with small figures too numerous and too much alike in grouping and size to be effective. The columns of this porch at once strike us as designed after those in the temple on Mount Abu and others, whilst those of the temple itself are different, and resemble more those of the later Somaji's Chaumukh temple at Śatruṇjaya.

The temple was designed and constructed under the direction of a *salāt* or master-mason named Premachand. Fifty years ago Mr. A. K. Forbes thus stated the custom in such a case, which is still prevalent in India:—"When a Rajput chief erects his new residence, or a Jaina merchant consecrates a shrine to his religion,—no drawings are made, but the general design, with the accommodation required, is described in words by the rāja or the Śeṭh to the principal *salāt* or master-mason. Such lately erected edifices as are within reach are then examined, with the view that they may be used as models, and the improvements desired are suggested at this time or during the progress of the work, by one or other of the parties, the handicraftsmen being by no means excluded, and the result is an edifice substantially the same as those which immediately preceded it, but more adapted to the tastes and exigencies of the day. That these tastes are always purer than those which formerly prevailed is more, of course, than can be asserted, at a time when the false principle of servilely imitating a foreign model (because foreign) is already beginning to exercise a too powerful influence."¹

¹ *Bombay Quarterly Review*, vol. V (1856), p. 305.

The temple itself consists of the usual three parts: an open *maṇḍap* on a base about 37 feet square, with a double row of pillars on the three exposed sides, and roofed by a large ribbed dome standing on the twelve inner pillars. On each of the three outer sides it has a large projecting porch. Beyond this is the principal *maṇḍapa*—24½ feet square inside, also with projecting porches on the north and south sides two storeys in height: all porches are approached by steps from the east. In the inner corner of this *maṇḍapa* are two rooms, and in the front corners stairs lead to the upper storey, which is roofed in that style peculiar to Jaina temples, consisting of rows of sloping little moulded forms resembling a tiling of waterpots. Three doors with richly carved thresholds lead from the hall into the shrine, which is about 22 feet in length by 6 in depth—the plinth or throne along the back wall bears three larger figures of Tirthakaras and many others of various sizes.

The central figure is that of Dharmanâtha, the fifteenth Jina, to whom the temple is dedicated, whose symbol is the *vajra* or thunderbolt, and his attendant genii the Yaksha Kinnara and the Yakshinî Kandarpâ. Like the *maṇḍapa*, the shrine has an upper storey which is surmounted by a triple spire of the usual pyramidal form with slightly curving sides, crowned by *kalāśas* and surmounted by flags.

Under the west side of the portico is a long underground room with two small shrines on the west side and other two rooms on the east. This apartment is reached by a stair leading down from the court on the south side.

The temple has been finished with as much wealth of ornament as in the best days of the style, which has but little degenerated from its former excellence. But the sculpture is poor and the details have lost in purity. Still its whole arrangement is very perfect. "Each part," as Mr. Fergusson remarked, "goes on increasing in dignity as we approach the sanctuary. The exterior expresses the interior more completely than even a Gothic design; and, whether looked at from its courts (Plate LXXI) or from the outside (Plate LXIX), it possesses variety without confusion and an appropriateness of every part to the purpose for which it was intended."¹

HINDŪ TEMPLES.

In the preceding account no notice has been taken of the Brahmanical or strictly Hindū temples. They are numerous, of course, in a large city like Ahmadâbâd, but few of them are old or of architectural merit. There is, however, one deserving of some notice—that of the followers of Svâmi Nârâyana. This sect was founded in the early part of the nineteenth century by a Sarvaiyâ Brahman named Ghanaśayâma, born at Chhapaya, a village a little to the north of Ayodhyâ in Audh, in 1780. He became an ascetic and under the name of Nilakanṭha visited religious shrines, and came to Kâthiâwâḍ where in 1800 he took the name of Sahajânand, and began to preach a reformed type of the Vaishṇava religion, inculcating a moral, and even ascetic life. He made numerous converts in Gujarât,

¹ *Ind. and Eastn. Archit.*, p. 258; *Ahmedabad*, pp. 96ff.; Briggs, *Cities of Gujarashtra*, pp. 32f.

assumed the title of Svâmi Nârâyana, and established two *gâdis* or seats of episcopal rule—Ahmadâbâd and Vadṭâl (in Kheda district); but Gadhadâ, Muri and Junâgaḍh are also recognised as having their own temples and seats of authority. Svâmi Nârâyana died at Gadhadâ in 1829.¹ At these cities and in many other towns, the sect have temples—some of them large and noteworthy and with connected monastic establishments. Their temple at Ahmadâbâd is situated about 500 yards south-east from Muhâfiz Khân's mosque; it was completed in 1850, and is in the usual Hindû style. The shrine, like Śeṭh Hathisingh's, has three spires over the cells where the images of Kṛishṇa, Râdhâ and Svâmi Nârâyana himself are placed; and the maṇḍapa or hall is roofed by an octagonal dome supported, as usual, on twelve pillars. The one difference from the prevalent Jaina form is that the angles are filled in, making the porch squarer than is usual in Jaina temples, though this form is sometimes used by them also; and it is not an improvement but destroys that play of outline which is the great charm of the original arrangement. Barring this slight defect, the design of the whole is not unworthy of the earlier style. Its gateway is wanting in purity of detail and in perfect proportion, but is still so beautiful that it would be extremely interesting to trace back its form to the original.²

¹ See *Indian Antiquary*, vol. I, pp. 331-335; *Asiatic Journal*, vol. XV (1823), p. 348; Heber's *Journal* (4to. Ed.), vol. II, pp. 143-4; Briggs, *Cities of Gujarashtra*, pp. 226-229, and appendix, pp. xiii-xxiv.

² Fergusson, *Ahmedabad*, pp. 94-96, and plates 117, 118. This temple was not included in the survey, and we have no plan or recent photograph of it.

CHAPTER XVIII.

VIRAMGAM AND MANDAL; KAPADVANJ AND SARNAL.

VIRAMGAM.

PLATES LXXII TO LXXIV.

VIRAMGĀM is a town of about 23,000 inhabitants, lying 35 miles nearly due west from Ahmadâbâd, and connected with it by a railway which branches here to Mehsâna lying northwards, to Pâtri and Khârâghoḍa to the west, and to Wadhvân and Kâthiâwâd to the south-east. It has always been a place of considerable importance, and about A.D. 1100 Mayaṇalladevi, the mother of Siddharâja is credited with the formation of an artificial lake known as the Mânasa sarṇovar—and now called Mânasarovar or Mânsar talâv, on the west of the town—which is still its chief beauty. From this and two other reservoirs—the Gaṅgâsar lake on the south and south-east and the Dhuniya talâv in the south-west, the town is supplied with water.

The Mânasarovar is irregular in shape, but supposed to resemble the conch shell (Plate LXXII), and is quite surrounded by a *ghât* or flight of stone steps leading down to the water.

Collecting from the west the water forms a small lake and is thence received through a stone grating in the west side into a deep octagonal *kunḍa* or silt well, having niches in the sides occupied by images in bold relief. From this *kunḍa* it passes—by a masonry channel through five circular openings—three above and two below—into the lake. Over the terrace covering the tunnel is a large pyramidal roofed pavilion—repaired by the Marâṭhas—behind which are five shrines of the usual size dedicated to Baucharâji, locally styled Mânsar Mâtâ.

On the platform above the *ghât* or steps were raised a multitude of small shrines, each with its separate spire; originally there must have been in all about 520, but almost a third of these are ruined, especially along the north side and east end, where the platform has partially subsided and thrown them forward; but 357 are still left. With one or two exceptions these shrines are very small and of one pattern (Plates LXXII and LXXIII, figs. 2, 3 and 4).

The shrines on the north side of the lake were all Vaishṇava; those on the east end were most probably Śaiva, but the floors have been torn up. All the shrines on the south side and south half of the west side are Śaiva, and have figures of Mahâkâl, Bhairava and Naṭeśa outside—on the right, left and back, or east, west and south walls. In the two larger double temples on the south-east (Plate LXXIII, fig. 1), Bhairava is on the sides towards the lake and Mahâkâl on the south sides, whilst Naṭeśa is on the back of each and Gaṇeśa on the door lintels. These larger temples have a *maṇḍapa* on twelve pillars between the pair of shrines: the west shrine was Vaishṇava whilst the east one was Śaiva. The cells

in each case are fully double the dimensions of the others round the lake. On the north side, near the east end, are two long rooms with three niches in the back walls, and one in each end; the figures round the doors of these may perhaps be Vaishṇava but Gaṇeśa occupies the dedicatory block on the lintels. They have had a verandah in front with overhanging balcony. West of this is a descent or slope for cattle and on the west side of it, a somewhat larger shrine than usual facing east is Śaiva—the only one on this side. The surrounding *ghāṭ* is interrupted in several places by roadways, which descend to the water's edge. The appearance of this fine sheet of water is represented in the photographs on Plate LXXIV, the first being a view from near the double temples along the south side looking west, and the second another view along the east end looking northwards.

MĀNDAL.

PLATES LXXV, LXXVI, LXXVII.

About fourteen miles north-west from Viramgām and in the same tāluka is Māndal, a town of some 8000 inhabitants. It was also a place of some importance in mediæval times, and appears to have been under Jhâlâ chieftains till the time of Bahādur Shāh of Gujarāt, when Viramgām and Māndal were annexed to the royal domains. It contains some handsome temples, but the principal remains are four Musulman masjids—the Jāmi', Sayyidi, Qāzi and Ganjni, the last two comparatively modern and of but little importance.

The Jāmi' masjid is a large plain structure (Plate LXXV, fig. 1). Inside it measures 132 feet in length by 35 feet deep, having five large domes with small ones in front and rear of each—the other portions of the roof being covered in the Hindû manner by cutting off the corners of the squares formed by the lintels over the pillars. The pillars have all been reft from Hindû temples and stilted one upon another to attain the requisite height. There are five *mīhrābs* and the usual raised pulpit on the right of the central *mīhrāb*: the *mīhrābs* are very plain and devoid of taste. In the north end, is a gallery, or *mulūk khāna*, entered from outside by a stair landing in a small domed porch. Altogether, with its mass of dead wall above the doorways, this is a very poor specimen of Muhammadan architecture, and probably not of an early date.

The Sayyidi Masjid is much smaller than the preceding, measuring 31 feet square inside and roofed with a single large dome in the centre, small ones in front and behind it and at the corners what look like small domes from outside, but inside cover square areas of which the corners are first cut off and the remaining square space covered by a large flagstone.

The façade is open and divided by four neatly moulded pillars (Plate LXXVI, fig. 6): the cornice consists of a panelled projecting eaves slab, with neat string-course above it, and over a projecting tænia with pendent ornamentation are the usual *kangaras*. The figure, Plate LXXVII, fig. 2, will explain this.

The three *mīhrābs* in the back are very richly carved—differing in the patterns on the jambs from those prevailing at Aḥmadābād (Plate LXXVII, figs. 3, 4 and 5). In each end and in the back wall are two windows, richly carved outside, which have been filled with the usual tasteful and varied perforated stone-work—but this has been very much destroyed.

The back wall (Plate LXXV, fig. 2) conveys the best idea of the exceptionally rich decoration upon this beautiful mosque. The three buttresses are of a style quite distinct from what we find elsewhere, the lower portions of them being more like the bases of the minārs of the sixteenth century, about the middle of which this was probably constructed. The court and mosque are now very much below the level of the surrounding ground, and are reached by a flight of steps.¹

About Māṇḍal, as in many places in Kāthiāwāḍ and northern Gujarāt, are to be seen numbers of Pāliyas or memorial and sati stones. Figures 3 and 4, Plate LXXV, give representations of two of these: the first is the pāliya of a local hero of A.D. 1629–30, having above the sun and moon, and then a bas-relief of the warrior. The other—a *sati* stone—is dated 1607–8, A.D., and is in memory of one who was burnt on the funeral pyre of her husband.

KAPADVĀNJ.

PLATES LXXVII–LXXXIII.

Kapaḍvañj or Kapaḍvaṇaj—Sanskrit Karpāṭavāṇijya²—is an old city in the Khêḍā district on the Mohar river, lying thirty miles due east from Aḥmadābād, and is now a town of 18,000 inhabitants. Here a notable Jaina religious chief, Abhayadêva, died in the thirteenth century. Near the walls of the present town is the site of an ancient city, and among the buildings are several very old structures, as well as the ruins of many fine mosques and tombs. Among the modern ones the most notable is a Jaina temple, built about the middle of last century, at a cost of a hundred and fifty thousand rupees.

The Jāmi' Masjid deserves some attention (Plate LXXVIII). With the court in front, it forms a quadrangle measuring outside 87 feet from north to south by 129 from east to west, with entrances on the east and north sides. The west end of this enclosure is occupied by the mosque, which is 79 feet in length inside by 48 feet deep, roofed by six domes in two rows of three each. In front it is quite open and trabeate, and in the north-west corner is a small *mulūk khāna* measuring 18 feet by 24, with the entrance in the north wall. In the back wall there are three *mīhrābs*, and four narrow windows divided by thick mullions into four apertures each, and filled with perforated work, as shown in Plate LXXIX, fig. 3.

The *mimbar* is of the high type of earlier times, and the pillars, as illustrated by figures 1 and 2 on the same plate, are mostly hexagonal, of purely Hindū type,

¹ H. Cousens, *Progress Report*, Dec. 1889–Feb. 1890.

² *Ind. Ant.*, vol. XI, p. 248; *Epig. Ind.*, vol. I, p. 58; vol. II, pp. 41, 85.

and must have been torn from native temples. The domes testify to the same origin as is illustrated by the drawings of the central one on Plate LXXVIII, fig. 2, where it may be noted that, whilst the eight figures that adorned the inside have been removed, the blocks on which they stood have not been arranged symmetrically with the lintels of the supporting octagon.¹ Part of the corridor round the front court seems to be in ruins—the roof of a portion of the south side, apparently, and the whole of the north side corridor being gone.

The principal object among the remains at Kapadvanj, however, is a large square *kunḍa* or reservoir in the market place. This occupies an area about a hundred feet square, with a platform below the first descent, from which a series of short stairs, parallel to the sides, lead down from one narrow landing to another, and reaching a broader one about 23 feet from the first. Between each pair of descending steps in each of the five tiers is a niche—some hundred and thirty-six in all—originally occupied by images (see Plates LXXX and LXXXI). In the centre is a deep well about nine and a half feet square.

On the north, west and south sides the first platform is broken into on the level of the next landing to make room for pavilions about nine feet square, each standing on four pillars, and carved on the architrave with mythological figures (Plate LXXIX, fig. 4). On the south side, close behind the somewhat ruined pavilion, is a draw-well about sixteen feet in diameter.

On the east side, steps lead up to a platform on which stands a fine Kirtistambha or *Toraṇa* arch (Plate LXXXII), not very greatly injured, though it probably belongs to the early part of the twelfth century. It consists of two highly carved pillars, 4 feet broad at the plinth, and rising to a height of 13 feet 10 inches including a broad cruciform capital, whose inner arms support the ornamental *torāṇa* or cusped arch. Over this capital a prolongation of the shaft supports a sur-capital, 3 feet above the first, over which again lies the architrave in two fasciæ richly carved—the lower in florid pattern, and the upper with gods in the *lalita mudrā* in the middle, and elephants, horsemen, &c., at the ends. This supports the projecting cornice with its decorative guttæ, surmounted by a plinth, and on this stands the pediment in which Śiva or Bhairava is the central figure.

On the arms of the principal capitals are placed human and animal figures, which slope outwards as struts and are held in place by the heads of the sur-capitals. The column shafts are square below, then octagonal and above circular. At a height of ten feet are small projecting brackets that at one time supported other figures as struts held above by the lower capitals, but these have entirely disappeared.

To the south of the *Kunḍa* is an underground temple dedicated to Mahādeva which has never been properly explored.²

Mr. Cousens, in his survey, noted some very good old wood-carving in the town, especially in windows and brackets, and his drawings on Plate LXXXIII, of a

¹ No photograph or elevation of this mosque, nor any note respecting its architecture, has been supplied by Mr. Cousens, who conducted the survey.

² *Bombay Gazetteer*, vol. III, p. 173.

window in the wall of a brick house (figs. 1 and 2), and of a carved bracket (fig. 3), are given in illustration.

SARNAL.

PLATES LXXXIV AND LXXXV.

Lastly, in the Khêḍā district, 44 miles E.S.E. from Aḥmadâbâd and four miles east by south from the town of Thâsrâ, is the village of Sarnal, on the right bank of the river Mahi, in latitude $22^{\circ} 47'$ N. and longitude $73^{\circ} 20'$ E. Sarnal, along with the neighbouring villages of Bhadrâsa and Aklâcha, is said to occupy part of the site of an ancient city called Kuntalpur, the old foundations of which may still be traced.

Here there is an important old temple said to have been desecrated by 'Alâ-ad-dîn Khiljî when he invaded Gujarât in the end of the thirteenth century. The south-east side of the maṇḍapa is considerably ruined, but the plan is so purely Chalukyan in arrangement that the temple was deserving of a careful survey.¹

The maṇḍapa or portico is about 40 feet each way, and its roof is supported by the eight pillars of the central dome and by the smaller ones standing in pairs on the screen walls that surround it (see Plate LXXXIV).

In plan this portico follows the pattern of temples of the Chalukyan style in the Kanarese districts, with their numerous projecting angles. The inner eight columns are each 14 feet in height, have double capitals and are square for the lower third part of their height, then through an octagonal and sixteen-sided belt are changed into cylindrical form (Plate LXXXV, fig. 4). They are not spaced equally apart on the floor as in most Jaina and Musalman domes: those on the sides being quite 11 feet between centres, whilst at the corners they are only 5 feet: and this is so arranged as to bring them into line in each direction with the outer pillars on the screen wall.

A small ante-chamber or porch is formed in front of the shrine, and the doorway of the latter (figs. 1-3) is elaborately carved on the jambs, lintel and architrave in a style that must relegate this temple to the twelfth century; but it has been much damaged by the iconoclast. The figure sculpture on the middle of the lintel indicates a Śaiva temple, and a boldly cut kirttimukh² projects from the upper cornice.

The shrine or *garbha-griha* is 11 feet square inside, and its floor is somewhat lower than that of the Sabha-maṇḍapa. Outside, its walls are much broken up by


¹ To this temple attention was directed in the first edition of the *Lists of Antiq. Remains in Bombay Presidency* (1885), pp. 133, 134 as one "of primary importance," for the survey. Mr. Cousens, in surveying the eastern part of Gujarât, prepared the drawings produced on Plates lxxxiv and lxxxv, but without either architectural elevation or photograph of the temple, and as only the draftsmen visited Sarnal, he was unable to supply any notes respecting it.

² *Arch. Surv. Westn. Ind.*, vol. IX, p. 25.


numerous projections, which lie in a circle about 24 feet in diameter and among which are seven recesses for images, facing so many of the eight points of the Hindû compass—that on the east being the entrance of the shrine.¹ The regents of the eight points—Indra, Agni, Yama, Nairṛiti, Varuna, Marut or Vâyu, Kubera and Śiva, were among the greater gods of earlier times, and are mostly still held in reverence. Between each pair of the projections containing these niches are two other advanced angles, divided vertically into numerous members.

The temple takes its name from the Galtâ, a small stream which here joins the Mahî.

¹ These points are :—S.E., Dakṣiṇapûrvâ, over which Agni or Vahna presides with the elephant Puṇḍarîka ; S., Dakṣiṇa, held by Yama or Pitṛipati, with the elephant Vâmana ; S.W., Dakṣiṇapaśchimâ, held by Nairṛiti with Kumûda ; W., Paśchimâ, by Varuna and Añjana ; N.W., Uttarapaśchimâ, by Marut and Pushpadanta ; N., Uttarâ, by Kubera and Sârvabhauma ; N.E., Uttarapûrvâ by Îsana or Śiva and Supratika ; and E., Pûrvâdik, over which Indra presides with the elephant Airâvati. See *Ind. Antiq.*, vol. VI, p. 361.



PLAN




SECTION


SCALE OF 10 20 30 40 50 60 70 80 90 100 FEET.

H. CORRIE ARCHT.

1. MATA BHAVANI'S WAY: SCREEN.




2. PILLAR.




SCALE TO FIGS. 1 & 3.

Scale of 12 6 4 2 3 4 5 Feet.

3. BAI HARIR'S WAY: SCULPTURED NICHE.



4. BAI HARIR'S TOMB: WINDOW UNDER THE DOME.




SCALE TO FIGS. 2 & 4.


Scale of 12 6 4 2 3 4 5 Feet.

H. Consoni surr.

J. Burgess dir.




1. SECTION.



SCALE OF 10

10 30 40 50 FEET

2. PLAN.



H. Cousens surd.


J. Burgess dir.

SCALE OF 10

40 50 60 70 80 90 100 FEET.










PLAN


Scale of 10' 0 10 20 30 40 50 60 70 80 90 100 feet



C PLAN.

SCALE OF


2 3



SECTION OF WEST PORTION.

SCALE OF 10 20 30 Feet.

H. COMANS SUR.




1. PLAN.

Scale of 10 feet. 0 10 20 30 40 50 60 70 80 90 100 feet.

H. Cousens surt.


J. Burgess del.



2. ANTEFIXA ON THE UPPER CORNICE OF THE TOMB.

SCALE 1/10TH

3. PENDANT IN DOME



ELEVATION



PLAN LOOKING UP
SCALE 1/10TH




4. DRIP OF THE CORNICE OF THE TOMB.

SCALE 1/5TH

N. Dhanabhai,
Bombay Sch. of Art

1. NICHE IN THE WAY.





S. Pacheco.


3. NICHE IN THE MOSQUE.



2. NICHE IN THE WAY.



5. ELEVATION.




6. SECTION.

SCALE TO FIGS. 1, 2, 3.




4. PLAN OF NORTH MIHRAB.

L. J. FONSECA,
SCHOOL OF ART,
BOMBAY.




10 SCALE 10 20 FEET.



1. ELEVATION: SOUTH FACE.

SCALE OF 10 10 20 30 FEET.

2. SCREEN AT THE CORNER OF THE VERANDAH, S. FACE, E. END.




H. C. GREGG SURV.

J. BURGESS DRA.

SCALE OF 10 10 20 30 FEET.


3. NICHES IN THE MINARET
OF THE MOSQUE.



SCALE OF 12" 1 2 3 4 5 FEET.


BAI HARIR'S MOSQUE AND TOMB.

1. SMALL DOME ON CORNER
OF THE VERANDAH
OF THE TOMB.



PENDANT

2. PILLAR, &C.
OF THE TOMB.




SCALE OF 12" 1 2 3 4 5 FEET.

SCALE OF 12" 1 2 3 4 5 6 7 8 9 10 FEET.

H. Consens sculp.


J. Burgess del.






SECTION


20 30 40 50 60 70 80 90 100 FEET.



C SECTION.





C ELEVATION.




PILLAR AT D

4 5 6 7 8 9 10 FEET.



Scale of 10 20 30 40 50 Feet.



3. PLAN.








THE TOMB OF
SHAH ALAM
WITH ITS
SURROUNDING BUILDINGS.
*Scale: one mile north of
Agra.*





SCALE OF 12"  10 FEET.



1. OUTER GATEWAY.





2. INNER CORRIDOR OF THE MAUSOLEUM,
ON THE WEST SIDE, FROM THE SOUTH.

SHAH 'ALAM: PERFORATED WINDOW IN THE TOMB

PLATE XXVII


SIDI BASHIR'S MASJID:
ONE OF THE MINARS.





Scale of 10 Feet

J. Burgess del.

H. Collins sculp.



1. SHAH 'ALAM: PERFORATED STONE WINDOW



2. TOMB AT DARVESH ALI'S MOSQUE.




J. Burgess del.

3. MINARET AT
SHAH ALI'S MOSQUE




H. Cousens auct.



1. PLAN OF MOSQUE AND TOMBS.


SCALE
10 20 30 FEET.



4. SMALL DOME.

3. PLAN OF SMALL DOME.

SCALE OF 10' 1 2 3 4 5 6 7 8 9 10 FEET.





2. HALF ELEVATION AND SECTION OF THE MASJID.


SCALE OF 10 20 30 FEET.

1. WINDOW IN DARVESH 'ALI'S MOSQUE.

2. BUTTRESS IN DARVESH 'ALI'S MOSQUE.




SCALE





PLAN

SCALE





3, 4. PANELS FROM ADALAJ WAV.

S. J. Parbesi.




SCALE OF






THE MASJID.

TOMB.





SCALE OF 10 10 20 30 40 50 60 70 80 Feet






1. CROSS SECTION.

Scale of 10 20 30 40 50 Feet




TWO WINDOWS FROM INSIDE.


Scale of 1 2 3 4 5 Feet




Scale of 2 Feet



ELEVATION.



SECTION.




PLAN.


J. Burgess dir.

H. Cousens surr.







1. SECOND WINDOW FROM NORTH CORNER.



3. ON SOUTH FRONT.




2. SECOND WINDOW FROM SOUTH CORNER.




4. ON NORTH FRONT.

Scale 1/2" = 1' 0"

3. MIRZAPUR MASJID: MINAR.




2. SARANGPUR MASJID:
SIDE ELEVATION OF MINAR.



SCALE OF 15 FEET.

H. COLEMAN DEL.

1. SARANGPUR MASJID:
ENTRANCE TO THE STAIR.




SCALE OF 12 FEET.


J. BURGESS DEL.



2. FRONT PILLAR OF THE CENTRAL DOME.



H. Conner surt.




1. PLAN.

RANI RUPAWANTI MASJID IN MIRZAPUR.


PLATE XXXVIII.

1. WINDOWS IN NORTH HALF OF THE FACADE.




SCALE OF 10' 10 FEET

2. THE CENTRAL MIHRAB.



FRONT ELEVATION.

SECTION.




PLAN.

SCALE OF 10' 10 FEET

H. Cousens surt.

MIRZAPUR MASJID, AHMADABAD.


ROOF PANEL.



2. SECTION.




NICHOLS FROM THE MINERS.




II. Caring for the...

FATHI MASJID, AHMADABAD.




ELEVATION: SOUTH END OF FAÇADE.

1:125




PLAN.

1:200




J. Burgess del.

H. Cousins sur.




FRONT ELEVATION.




PLAN.

10 10 20 30 FEET

2. PILLAR FROM BAWA
'ALISHAH'S MASJID.




1. ELEVATION.




3. ELEVATION.

H. Cousens surr.




ELEVATION.



PLAN.

Scale of 10 20 30 40 50 60 70 80 90

1. NICHE FROM IBRAHIM SAYYID'S MASJID.



SOUTH MINAR, S. SIDE.


2. NICHE FROM RANI'S MASJID, MIRZAPUR.




FROM S. MINAR.

SCALE TO FIGS. 1 & 2.

SCALE OF




3, 4. NICHE IN THE WALL OF 'ALI KHAN QAZI'S MASJID.



SHAH JAHAN MUHAMMAD

SCALE OF 12"



1. NICHE FROM ISRAHIM SAYYID'S MASJID.





SOUTH MINAR, S. SIDE.

2. NICHE FROM RANT'S MASJID, MIRZAPUR.




FROM THE S. MINAR.

SCALE TO FIGS. 1 & 2.



3. 4. NICHES IN THE WALL OF
'ALI KHAN QAZI'S MASJID.






SHAIKH HASAN MUHAMMAD CHISHTI'S MASJID IN SHAHPUR.



SHAIKH HASAN MUHAMMAD CHISHTI'S MASJID IN SHAHPUR.



PLAN





SCALE OF 10 20 30 40 50 FEET.



H. Conder, surr.







5. PLAN OF THE TOMB OF ABU JURAB.




1. ELEVATION OF MIHRAB.

3. SECTION.

SCALE OF 12 1 2 3 4 5 6 7 8 9 10 FEET.

4. MOSQUE OF MUHAMMAD GHAFUS: PLAN.




SCALE TO FIGS. 4 & 5.

10 10 20 30 40 50 60 70 80 90 100 FEET.




INTERIOR OF THE MOSQUE OF MUHAMMAD GHAUS.



MIHRAB.



FRONT ELEVATION.

SECTION.



PLAN.

SCALE



SECTION.

SCALE OF 10


10

20


30

40

50 FEET.



VAJIHU'D DIN'S TOMB, AHMADABAD.




SHAHI BAGH, NEAR AHMADABAD.



MASJID OF BABA LULUI.

1885/1886.

BABA LULUI'S MASJID.




Scale of 10 20 30 40 50 Feet

2. NICHE IN MINARET OF BABA LULUI'S MASJID.




3. PERFORATED MARBLE WINDOW IN
PIR MUHAMMAD'S MASJID.



SCALE TO FIGS. 2 & 3.

12" 1 2 Feet

BABA LULJI'S MOSQUE.



ELEVATION.



Scale of 10 20 30 40 50 Feet.


H. COMANS, ARCHT.




PALACE OF 'AZAM KHAN, —NOW THE JAIL, AHMADABAD.

AZAM KHAN'S PALACE, NOW THE JAIL.






2. RAUZA OF NANA IDRUS.



SCALE OF 10 10 20 30 40 50 FEET.



3. RAUZA OF NANA IDRUS: ELEVATION.

S. J. Pacheco, dell.


SCALE OF 10 10 20 FEET.

J. Burgess sculp.






NAWAB SARDAR KHAN'S MASJID, AHMADABAD.




NAWAB SARDAR KHAN'S TOMB.







MASJID OF NAWAB SHUJAAT KHAN, AHMADABAD.








RASA MASJID.









ELEVATION OF BIBI'S MASJID AT RAJAPUR HIRPUR NEAR AHMADABAD.

SCALE OF 10 20 30 40 50 FEET.




SCALE IN INCHES 1 2 feet







Scale of 0 1 2 Feet



JAINA TEMPLE OF SETH HATHISINGH AT AHMADABAD.









SETH RATHSINGH'S JAINA TEMPLE FROM THE NORTH-EAST

PLAN OF THE MANASAROVAR AT VIRAMGAM.



SCALE 1:120

CELL-SHRINES AND STEPS
TO LARGER SCALE



TEMPLES

THE BLACK BLOCKS SHOW THE POSITIONS OF
THE CELL-SHRINES STILL STANDING

SCALE 1:1500

SCALE OF 100 200 300 400 500 FEET.

H. CHURCH, 1891.

S. J. Pacheco and S. Diakar, del.


PLANS AND ELEVATIONS

OF SMALL SHRINES


PLATE LXXIII.

On the margin of the Mana-Sarovar (lake) at Viramgam.

1. DOUBLE TEMPLE.




2. SINGLE SHRINE.




PLAN.

SCALE OF 10 10 20 FEET.



4. SIDE ELEVATION OF SINGLE SHRINE.



3. FRONT ELEVATION OF SINGLE SHRINE.

SCALE OF 12" 1 2 3 4 5 6 FEET

Hari Gopal, del.


H. Coxhead, corr.



1. VIEW ALONG THE SOUTH SIDE OF THE MĀNASAROVAR, LOOKING WESTWARDS.




2. VIEW ALONG THE EAST END OF THE MĀNASAROVAR, LOOKING NORTH.



SCALE OF 10 20 30 40 50 60 70 80 90 100 Feet

2. SAYYIDI MASJID, MANDAL--BACK WALL.



SCALE OF 10 20 30 40 50 60 70 80 90 100 Feet



SCALE OF 10 20 30 40 50 60 70 80 90 100 Feet







1. MANDAL: SAYYIDI MASJID.





2. MANDAL: JAMI MASJID.

MANDAL: SAYYIDI MASJID.

1. PLAN.




3. MIHRAB.




6. PILLAR.



5. SECTION.




ELEVATION




SECTION

2. CORNICE AND KANGARAS.

4. PLAN OF MIHRAB.




1. PLAN.




SCALE OF 10 FEET.

H. CROSTON SURV.




3. DOME.




SCALE OF 12 FEET.


1. PILLAR IN JAMI' MASJID.



3. WINDOW IN
JAMI' MASJID.




2. PILLAR IN JAMI' MASJID.



4. SMALL PAVILION.

SCALE OF 12" 1 2 3 4 5 6 7 8 9 10 FEET.


KAPADWANJ: PLAN OF OLD TANK.



SCALE OF 10 10 20 30 40 50 60 70 80 90 100 FEET.

H. Cousens sur.

SECTION OF WELL IN THE MARKET PLACE AT KAPADWANJ.



H. Cousins surt.




H. Cousens, surr.

S. Pacheco del.


SCALE OF FEET 1 2 3 4 5 6 7 8 9 10

KAPADWANJ: MODERN CARVED WINDOW AND BRACKET.


1.



2.




3.



SCALE OF 12"


3 FEET.



PLAN.

SCALE OF 10 10 20 30 40 50 FEET

H. Cousens archt.




1. ELEVATION.




H. Conquest xvi.

2. PLAN.

Scale of 1" = 10 Feet



3. SECTION.



Scale of 1" = 10 Feet



I N D E X

TO VOLUMES VI, VII, AND VIII OF THE ARCHÆOLOGICAL SURVEY OF WESTERN INDIA.

- 'Abdul Ghafūr Mazhīr 'Ālam, 3rd in descent from Shāh 'Ālam - - - VIII, 15
 'Abdul-Haīy, writer of inscription in Ganj 'Ināyat Shāh's mosque - - - VIII, 64
 'Abdul-Hamid Khān, acting governor of Ahmadābād, 1705 - - - VI, 17
 'Abdul-Karīm Laṭīf, architect of Hīlāl Khān's mosque at Dholkā - - - VI, 32
 'Abdullah Khān Bahādūr Firūz Jang, 13th viceroy of Ahmadābād - - - VI, 16
 'Abdullah Qutb al 'Ālam, Sayyid Burhān ad-dīn - - - VIII, 15
 'Abdullah Razzāq, *see* Abul Razzāq.
 'Abdul-Qādir Jīlānī, Pīr-i-Dastgīr or Pīrān-pīr - - - VIII, 75
 'Abdul-Rahīm Khān, Khān Mirza, viceroy of Gujarāt - - - VI, 14
 'Abdul-Rahmān al Marri, father of Junaid, governor of Ouidh - - - VI, 3
 'Abdus-Salām, son of Ahmad-al-Hājab-al-Quraishī - - - VI, 29
 Abhayadeva, Jaina teacher - - - VIII, 93
 Abhayasīmha, Mahārāja of Jodhpur, 54th viceroy of Gujarāt - - - VI, 18, 19
 Ābhīras or Ahīrs, early tribe in Saurāshtra - - - VI, 2
abjad, numerical arrangement of the alphabet - - - VIII, 44
 Abū, Mt., Vimala Śah's Temple on - - VI, 5, 7, 8 ; VII, 11, 14 ; VIII, 88
 Abū Bakr Khān, son of Maḥmūd Beg - - - VII, 84
 Abū Tālib's tomb in Shahrkotḍa - - - VIII, 81
 Abul Faṭh Maghrud-dīn, Jahāndar Shāh, Sultān of Dehli - - - VI, 18
 Abul Faṭḥ's *Āin-i-Akbarī* - - - VI, 6a, 11
 Abul Razzāq or 'Abdullah Razzāq's rauza and masjid - - - VIII, 66
 Abū Turāb, his tomb and *qadam-i-rasūl* - - VIII, 20, 50-51
 Aebut Bibi's mosque and tomb, VI, 12 ; VII, 64-66 ; VIII, 79
 Adālalj wāv or step-well - - - VIII, 2, 4, 10-13
 'Adil Khān Āsiri, officer under Muzaḥfar II. - - VIII, 28
 Adinātha, Jaina Tirthamkara Temple at Śatruṅjaya, VIII, 85 ; his attendant Yakshas, 87.
 Adīśvara Bhagavān, same as Adinātha, VIII, 86, 87
adl—justice - - - VIII, 59
 Afzal Khān Bombani, vazir to Bahādūr Shāh, his mosque - - - VIII, 82
 Agni or Vahna, guardian of the South-east - - VIII, 96
 Ahmad al-Hājab al-Quraishī - - - VI, 29
 Ahmad Ayyāz, governor of Gujarāt, 1325-1338 - - - VI, 8
 Ahmad Khān, son of Maḥmūd Shāh Beg - - - VII, 38
 Ahmads—the four - - - VII, 15 ; VIII, 72
 Ahmad Kattū Ganj Bakhsh, VII, 46, 50 ; mausoleum of, 47-48.
 Ahmad Shāh I, VI, 10, 14, 24, 39 ; VII, 1, 2-4, 8, 15-17, 25, 29, 30, 32, 35 ; VIII, 70, 72a, 74, 84 ; his masjid in the Bhadr, VII, 17-19, 71 ; VIII, 7a ; rauza, VII, 36-38 ; Langarkhāna, VIII, 63.
 Ahmad Shāh II (1554-1561), VI, 14 ; VII, 7, 8, 38
 Ahmadābād, VI, 1, 3, 4, 6, 10, 12, 16 and n, 19, 36 ; founded, VII, 1, 3, 7, 9, 46 ; architecture, VII, 10, 15.
 Ahmadābād Qāzī's masjid - - - VIII, 62, 63
 Ahmadnagar - - - VI, 11, 13
 Ahmad Shāhī Sultāns - - - VIII, 79
 Ajayapala, Chaulukya king of Gujarāt (1073-1076) - - - VI, 7
 Ajitanātha, 2nd Jaina Tirthamkara - - - VIII, 87
 Ajitrasīmha, brother of Virasīmha of Kālol - - - VIII, 12
 Ajit Sing, 48th and 50th viceroy, 1715 and 1719-1721 - - - VI, 18
 Akbar, Emperor, invasion of Gujarāt - - VI, 14-16, 30 ; VII, 7, 82 ; VIII, 50, 87
 Aklācha, village near Sarnal - - - VIII, 95
 'Ālamgir or Aurangzib, Sultān (1658-1707), VI, 16, 17, 27 ; VII, 7, 9 ; VIII, 54, 55, 61, 62
 'Ālam Khān Lodi, Gujarāt noble, 1540 - - - VI, 14
 'Ālam Khān's rauza in Dānapoth - - - VIII, 73
 'Alāud-dīn Husain Shāh of Bengal (1454-1521) - - - VIII, 20
 Alāud-dīn Khilji - - - VI, 8, 20, 24 ; VII, 1 ; VIII, 95
 Alexandrian traders - - - VI, 2
 'Alī bin 'Abdul-nabī al Baghdādī, 1621 - - - VI, 26
 al Idrisi, the geographer - - - VI, 6, 30
 Alif Khān Bhukāi's mosque at Dholkā, VI, 34-36 ; VII, 58
 Alif Khān, imperial guard - - - VII, 1
 Alif Khān or Bābi masjid - - - VIII, 42
 Alif or Ahmad Murtaṣa's masjid in Khās Bāzār - - - VIII, 72
 'Alī Khān's masjid - - - VIII, 68
 'Alī Khān's or Chhota Idrūs masjid - - - VIII, 54f.
Alim, Muhammadan theologians - - - VIII, 71
 'Alwi, poetical name of Wajihud-dīn - - - VIII, 53

- Amānat Khān - - - - VI, 17
 Ambarōṭha, temple - - - VI, 7
 Amin Khān Ghori, governor of Junāgaḍh, 1584 - - - VI, 15
 Amīr Husain bin Mirān, governor of Gujarāt, 1350-1364 - - - VI, 9
 Amīr Sa'ādāt Khān, founder of Wajīhud-dīn's tomb, 1602 - - - VIII, 53
 Amrā bin Jamāl, governor of Sindh, eighth century - - - VI, 3
 Ānandadeva Vāghelā, chief of Kālol - - - VIII, 12
 Andhārī Bagh or dark garden, at Shāh-i-Bāgh - - - VIII, 57
 Aṇḥilapātana, Aṇḥilapura, Aṇḥilwāḍa, VI, 3 5, 6, 8; VII, 2
 Animal life, preservation of, among the Jains - - - VIII, 76
 Anjuman-i Islām - - - VIII, 27
 Ankleśvar, tn. - - - VI, 18
 aṇkusa, elephant goad - - - VIII, 11
 Anupsingh Bhandari, deputy of Ajit-singh, 1720 - - - VI, 18
 Ānwā temple in Haidarābād districts - - - VII, 12
 'Arab Shāh, grandson of Shāh 'Ālam - - - VII, 60
 Arās, battle of - - - VI, 19
 Aras Bibī, Muhammadan lady, d. 1883 - VIII, 66, 67
 Arasur, mount, with Jaina temples - - - VI, 5
 Aravalli Hills - - - VI, 1
 arcuate style of architecture - - - VIII, 18, 22, 32, 45
 Arhats, or Jaina Tīrthāṅkaras - - - VIII, 85
 Arjumand Bāno Begam, Mumtāz Mahāl, wife of Jahāngīr - - - VIII, 57
 Arjunadeva Vāghelā (1261-1274) - - - VI, 8
 Arjorāja Vāghelā - - - VI, 7, 30
 Aśa, Bhilla, chief of Aśāwal - - - VIII, 84
 'Āsaf Khān, probably Ghayasud-dīn 'Alī 'Āsaf Khān - - - VIII, 19
 Āsaf Khān Ja'far Beg, brother of Azam or Azīm Khān - - - VI, 16a; VIII, 59
 Āsafud-daula Azad Khān Bahādur, governor of Gujarāt (1712) - - - VI, 18
 Āshū, Āśāpalli, now Asārwa or Asāwal, suburb of Aḥmadābād, VI, 6; step-well at, VIII, 15, 84
 Ashraf Khān's masjid - - - VIII, 70, 71
 Aśoka, Emperor - - - VI, 2
 Asura, demon - - - VIII, 84
 Audichya Brāhmans - - - VI, 4
 auliya, Saint, title of Mūsā Subhāg - - - VIII, 79
 Aurangzib, see 'Ālamgīr.
 Ayelhyā, city in Andh - - - VI, 16, 17
 A'zam Khān, title of Mir Ma'animad Bāqir, governor of Gujarāt, 1635-1642 - VI, 16, VIII, 59, 78
 A'zam Khān's palace, now the jail - - - VIII, 58ff
 Azamābād, tn. in the Koll country - - - VIII, 59
 azān, the call to prayer - - - VIII, 36, 66
 'Azīm Mirzā Azīz Kokaltāsh Khān, first viceroy of Gujarāt, 1572-1575, VI, 14; his mausoleum at Dehli, 16n.
 'Azīz Himar, a royal favourite, 1545 - - - VI, 9
 Bābās, the twelve - - - VI, 72 and n
 Bābā Lulū, also called Mubammad Ja'far, his masjid - - - VIII, 45-47, 51
 Bābā, or Alif Khān's masjid - - - VIII, 42
 badām, fortieth part of a pāis; Badāmi Masjid - - - VIII, 79
 Badā Miyān Sāheb's burial-place - - - VIII, 70
 Bādshāh Sayyid's or Naginā Pō, masjid in Daryāpur - - - VIII, 65
 Bāhā Piyārā ford, scene of defeat of the Muslims by the Marāṭhas - - - VI, 17
 Bahādur Gilāni, a Dakhni noble of Dābhōl - - - VIII, 28
 Bahādur Khān, Khān Jahān, governor of Gujarāt, 1668-71 - - - VI, 17
 Bahādur Shāh, Sultān (1526-1537) - VI, 13, 24, 40; VII, 6-8; VIII, 92
 Bahādur Shāh, Mu'ezzam Shāh of Dehli, 1707-1712 - - - VI, 17
 Bāi or Dādā Harīr's step-well or wāḍ, VI, 12; VIII, 1, 2, 4-6, 10-12; her mosque, VI, 12; VIII, 6-8, 25; and rauṇa, 8 9.
 Bailamān or Bailāimān - - - VI, 3 and n
 Bairām Khān, Khān Khānān - - - VI, 14
 Bālājī Viśvanāth, Marāṭhā Commander, 1707 - - - VI, 17
 baldachin - - - VI, 26, 27
 Bālā Mubīnd-dīn Pīranpīr's Dargāh in Jamālpur - - - VIII, 75
 Balhara of Mankīr, Chalukya ruler of Mālkheḍ - - - VI, 23
 Bande 'Alī Khān, Momin Khān IV, Nawāb of Kambhāy, 1823-1841 - - - VI, 25
 Bāqir Khān, deputy viceroy of Gujarāt, 1632 - - - VI, 16
 Bārapa, general of Tailapa, the Chālukyan king - - - VI, 4
 bari wāḍat, or wāḍat sharīf, anniversary of Muhammad's death - - - VIII, 20
 Baroda, sacked by Maḥmūd Baiqara, 1482 - - - VI, 1, 2, 9, 11, 15, 19, 39
 Barygaza or Bharukachha, now Bhāruch - VI, 2, 3, 20
 basilicas, Christian - - - VI, 26
 Basscin, treaty of, 1802 - - - VI, 25
 Batuvā or Vatuvā, buildings at - VI, 12, 46; VII, 60-63; VIII, 16, 40
 Baucharājī, a goddess - - - VIII, 91
 Bāurāh, Bāūrāh or Būda, title of Kanauj kings according to Mas'ūdi - - - VI, 3n
 Bāwā 'Alishāh's masjid at Pālājī Koehrab - VIII, 38
 Bāwā Bārakalla Chishtī - - - VIII, 80

- Bâwâ Faizulla, Sayyid, of the Imâm Shâh family of Pirâna; his mosque and tomb - - - - - VIII, 38
- Begampur, suburb named in honour of Mumtâz Mahâl - - - - - VIII, 57
- Behrâmpur, village south from Ahmadâbâd - - - - - VIII, 45, 83
- Bengali style of roof - - - - - VIII, 80
- Bhadre or fort, so named from Bhadrakâlî VI, 10, 18; buildings therein, VII, 43.
- Bhadrakâlî, goddess - - - - - VIII, 84
- Bhadrâsa, village near Sarnâl - - - - - VIII, 95
- Bhagatsîmha, Vâghela chief of Kâlâl - - - - - VIII, 12
- Bhairava, a form of Śiva - - - - - VIII, 85, 90, 91, 94
- bhāntī*, a cloister - - - - - VIII, 87
- Bhamaria well, at Maḥmūdâbâd - - - - - VI, 46
- Bhārgavas, a class of Brāhmins - - - - - VI, 20
- Bharoch, in. anet. Bharakachha, Gr. Barugaza, VI, 1, 2, 9 11, 15; mosque, 20-22; fort constructed by Bahâdur Shâh, VI, 13.
- Bhatârka, founder of the Valabhi dynasty - - - - - VI, 3
- Bhāvânî, goddess, a Śakti of Śiva - - - - - VIII, 2, 84
- Bhills, aboriginal tribe - - - - - VI, 2, 6
- Bhilsâ, tn. in Mâlwa taken by Bahâdur Shâh - - - - - VI, 13
- Bhîmadeva I, Chaulukya king, 1021-1063 - - - - - VI, 5, 7
- Bhîmadeva II, Vâghela king, 1178-1241 - - - - - VI, 7
- Bhîmarâja of Dwârkâ - - - - - VI, 12
- bhoyarâh*, cellars - - - - - VIII, 85, 86
- bhramā*, Skr. *bhāntī*, Guj. cloisters - - - - - VIII, 88
- Bhrîgu, a Vedic sage and founder of the Bhārgava race of Brāhmins - - - - - VI, 20
- Bhūvaḍa, Bhūvaḍa or Bhūrâja, early king of Kanauj - - - - - VI, 3, 4
- Bibi Achut Kuki, wife of Hâji Malik Bahâud-din, VIII, 7, 32; her mosque, VI, 12; VII, 466.
- Bibi Basti Begam, wife of Mir Ja'far 'Alî VIII, 17
- Bibi Fâtimah's tomb at Cambay - - - - - VI, 38
- Bibi Moghlâi, mother of Maḥmūd Baiqara - - - - - VI, 11
- Bibiji's mosque at Râjapur Hirpur - - - - - VII, 71-73; VIII, 82
- Bibi Râjâbâ's tomb at Sarkhej - - - - - VII, 50
- Bilâl Khân Qâzî, see Hilâl Khân.
- Bindusarovar at Siddhapur, formed by Siddharâja - - - - - VI, 6
- bird roosts - - - - - VIII, 76
- Bohrâ sect of Sunnis, VIII, 70; of Shiâhs, VIII, 74.
- Borradaile, Mr., VII, 86, 87; step-well, VIII, 83.
- brackets, carved - - - - - VII, 41
- Brihaspati or Gura, Jupiter - - - - - VIII, 11
- Buddha, substituted for Budha - - - - - VIII, 11
- Buddhism, VII, 11; Buddhist caves, VI, 2; Buddhist rail pattern, VIII, 3, 13.
- Budha, the planet Mercury - - - - - VIII, 11
- Bukhâriah Sayyids, Darveshes, VII, 60, 67; VIII, 15f
- Bundi, town and state in Mâlwa - - - - - VI, 11
- Burhân Nizâm Shâh of Ahmadnagar - - - - - VI, 13
- buttresses, VI, 26-27, 35, 42; VII, 20, 23, 34, 43, 71, 80, 86; VIII, 26, 37, 38, 47, 93
- Cambay or Kambhât, VI, 1, 4, 5; its monuments, VI, 23-29, Nawâbs of Cambay, VI, 25, &c.; VIII, 68.
- cantharus*, cistern for ablution - - - - - VI, 26
- capital, cruciform - - - - - VIII, 94
- Chakreśvari, Yakshini of Rishabhânâtha - - - - - VIII, 87
- Chalukya dynasty of the Dekhan, VI, 3 8; Chalukyan style, VI, 7; VIII, 95, 96.
- Chamardi Hills in Kâthiâwâd - - - - - VI, 2
- Champâ tree in Mûsâ Suhâg's mosque-enclosure - - - - - VIII, 79
- Champâ masjid in Shâhpur - - - - - VIII, 64
- Châmpânir, Shahr-ka Masjid - - - - - VI, 40
- Châmpânir Fort, VI, 7, 11-13, 16, 36; VII, 1, 2, 5-8; VIII, 50, 63; mosques, VI, 39-44.
- Châmunḍa, Chaulukya king - - - - - VI, 4
- Chandâ or Durgâ, goddess - - - - - VIII, 84
- Chanderi, town in Mâlwa - - - - - VI, 13
- Chandragupta, Gupta king - - - - - VI, 2
- Chandrâvatî, anc. esp. in N. Gujarât - - - - - VII, 15
- changizi*, coin of about the value of the *maḥmûdî* - - - - - VI, 15a
- Changiz Khân, a Gujarât noble who joined Akbar - - - - - VI, 14
- Châr Tolâ masjid or Châr Tolâ qabrastân in Shâhrkotḍa - - - - - VIII, 81
- Chashtana, early satrap of Gujarât - - - - - VI, 2
- Chandâ or Chapotkata, dynasty - - - - - VI, 4f
- Chauhan, sovereign of Ajmir - - - - - VI, 7
- Chaul, Portuguese fleet defeated near, in 1506 - - - - - VI, 12
- Chauṣa'ih Kambh, tomb of 'Azim Khân's family at Dehli - - - - - VI, 16a
- chauth*, Marâṭhi tax of a fourth share of revenue - - - - - VI, 18, 39
- Chhapaya, village in Andh - - - - - VIII, 89
- chhatris*, kiosks, canopies - - - - - VIII, 2, 5, 12
- Chhota Udaypur, small state in Rewa-kântha - - - - - VI, 39a
- Chhudâvâd, village - - - - - VIII, 78
- chînnas*, cognizances of divinities - - - - - VIII, 87
- Chintâman-nâth, Jaina figure - - - - - VIII, 86
- Chittor, tn. in Mâlwa - - - - - VI, 11, 13
- Chudâsamâ, chiefs of Junâgaḍh - - - - - VI, 9
- Cole (Major) - - - - - VII, 68, 86
- crescent symbol - - - - - VII, 80, 81
- Dabhoi or Darbhâvatî, tn - - - - - VI, 7
- Dâbhol, tn. in the Koṅkan - - - - - VIII, 28
- Dabishalim or Devishalim, puppet king set up by Maḥmūd of Gazni - - - - - VI, 5

- Dādā Miyān or Mir Muḥammad Husain's masjid - - - - - VIII, 66
- Dākor, tn. in Gujarāt - - - - - VI, 19
- Dāmāji Gaikwād - - - - - VI, 19; VIII, 83
- Daman, tn. in Gujarāt - - - - - VI, 1
- Dāni Limḍa, village S. of Aḥmadābād - VIII, 13, 16
- Dārā Shikoh, brother of Aurangzib - - - - - VIII, 55
- Darvesh 'Alī's or Ojā Bibī's masjid - - - - - VIII, 25
- Daryā Khān, governor of Gujarāt, 1371-1376 - - - - - VI, 9
- Daryā Khān, noble of Maḥmūd Baiqara's court, his *rauza* at Aḥmadābād - VI, 11, 34; VII, 58, 59; VIII, 78
- Daryā Khān, a Gujarāt noble under Maḥmūd Shah III - - - - - VI, 14
- Dastūr Khān's mosque - - - - - VI, 12; VII, 76, 77; VIII, 40
- Darbḥāvati, anc. name of Dabhoi - - - - - VI, 7
- dargāh*, origin of the word - - - - - VI, 38*n*
- Dargāh of Pirānpūr in Jamālpur - - - - - VIII, 75
- Daryāpur-Qāzīpur, village - - - - - VIII, 78
- Dāūd Khān Shāh, 1459 - - - - - VI, 11; VIII, 1-3, 8
- Daulat Khān Ghorī, a chief of Junāgaḍh, 1591 - - - - - VI, 5
- Daulat Rāo Sindia - - - - - VI, 40
- Daulatkhāna or Muḥammad Ghaṅg's masjid - - - - - VIII, 48
- Dehli - - - - - VI, 8, 9, 17, 18
- Devagaḍh Būriyā, a chiefship - - - - - VI, 39*n*
- Dhaudhukā, tn. - - - - - VI, 30
- Dhār, tn. - - - - - VI, 9, 10, 11
- Dharmasātha, 15th Jaina Tīrthaṅkara - VIII, 86, 89
- Dharmasāla, a rest-house - - - - - VIII, 87
- Dhavalā, ancestor of the Vāghela chiefs - VI, 7, 30 and *n*
- Dhavalakkaka or Dhavalagriha, now Dholkā - - - - - VI, 7, 20, 30
- Dholkā, Dholaka, Dhulakā - - - - - VI, 6, 30, 31*f*
- Dhuniya talāv at Viramgām - - - - - VIII, 91
- Dianāt Khān, minister Muḥammad Murād Bakhsh - - - - - VI, 17
- Diu, island in Kāthiawād - - - - - VI, 13; VII, 1, 6
- Diwān khāna at Shāh 'Ālam, VIII, 18, 22; at Abdulla Razzāq's *rauza*, VIII, 66.
- Dohād, tn. - - - - - VI, 11, 16, 18
- Dost Muḥammad Sakhar, writer of the inscription in Ḥasan Muḥammad Chishtī's mosque - - - - - VIII, 44
- Dungarsī, minister of Jayasingh Paṣāl of Chāmpānir - - - - - VI, 39
- Durgā or Chandā, goddess - - - - - VI, 10; VIII, 84
- Durlabharāja, Chaulukyan king (1009-1021) made the Durlabha sarovar at Aṇḥlapura - - - - - VI, 5
- Dwārakā or Dwārka, fort and temple of Kṛishṇa - - - - - VI, 2, 12, 15
- Earthquake of 1819, VII, 10, 32; VIII, 17, 22, 32, 48
- Ek-toḍa or one-turret masjid of Muḥammad Ghaṅg - - - - - VIII, 48
- Ellis (Sir Barrow H.), action for conservation at Aḥmadābād - - - - - VIII, 17, 18
- Fakrud-daulah Fakrud-dīn Khān Shujā'at Jang Bahādur, 59th viceroy of Gujarāt, 1747-48 - - - - - VI, 19
- Fakrud-daulah wa'd-dīn Abū Bakr, d. 1415; his tomb at Cambay - - - - - VI, 29
- Farhatul Mulk, title of Nau Khān; his masjid known as Shāh Khub Sayyid's - VII, 82, 83
- farṣ*, form of daily prayer - - - - - VI, 33 and *n*
- Faṭḥ 'Alī, Nawāb of Cambay, 1789-1823 - VI, 25
- Faṭḥ Khān, Maḥmūd Shāh I, Baiqara, VI, 11; VIII, 16
- Faṭḥ or Phuti Masjid in Daryāpur - VIII, 36-37, 65
- Faṭḥ Sing Gaikwād, 1778-1789 - - - - - VI, 19
- Faṭimāh, daughter of Muḥammad - - - - - VIII, 47, 75
- Fergusson, Jas. VI, 46; VII, 3, 11, 27, 31, 46, 49, 86, 87; VIII, 22, 33, 34, 50, 89
- Firūz Shāh III Tughlaq - - - - - VI, 23; VII, 46
- flood of 1875 - - - - - VIII, 58, 79
- Forbes, Jas., cited - - - - - VI, 20; VII, 10, 30, 33, 35; VIII, 4*n*, 57-59
- Gadhadā, tn. in Bhāunagar State - - - - - VIII, 90
- gādis*, thrones of Jaina pontiffs - - - - - VIII, 90
- Gagā Nāsā or Ganj 'Ināyat Shāh's masjid - VIII, 64
- Gajni, a name of Kambhāyat - - - - - VI, 23
- Galiyārā's masjid - - - - - VIII, 72
- Galtā river; Galtēśvara temple at Saroal, VIII, 95, 96
- Gāndhavi, fort in Kāthiawād - - - - - VI, 5
- Gapeśa, god - - - - - VIII, 84, 90
- Gangāsar lake, at Viramgām - - - - - VIII, 91
- Ganj Shāhodā's *rauza*s in Behrāmpur - - - - - VIII, 83
- Ganjai Masjid at Māndal - - - - - VIII, 92
- garba-griha* or shrine of a temple - - - - - VIII, 95
- Garuḍa, vehicle of Viṣṇu - - - - - VIII, 85
- Ghaṇḍasayāma, early name of Svāmī Nārāyaṇa - - - - - VIII, 89
- ghaṭ*, a descent, flight of steps - - - - - VIII, 89
- Ghaṅg-al-A'zam Muḥind dīn Pīr-i-Dastgir and Pirānpūr - - - - - VIII, 75
- Ghayāṣud-dīn 'Alī 'Aṣaf Khān - - - - - VIII, 19 and *n*
- Ghaṇaṣfar Kokah, brother of Mirzā 'Askari - VI, 13*n*
- Ghāzi Beg Tughlaq, Ghayāṣud-dīn Tughlaq Shāh I - - - - - VI, 8, 16
- Ghāziud-dīn Khān Bahādur Firūz Jang, viceroy of Gujarāt, 1708-1709 - - - - - VI, 17
- Ghikantā mosque, Mu'ammad Sayyid's - VIII, 54, 69
- Girnār, Mt. - - - - - VI, 2, 6, 85
- Goddard (Genl.) took Aḥmadābād, 1780 - VI, 19; VII, 10; VIII, 22

- Gadhadā, tn. and district in Gujarāt VI, 17, 39; VIII, 28
- Godī Pārśvanātha, Jaina image - VIII, 86
- Goghā, tn. in Kāthiāwād - VI, 12
- Gomakha, Yaksha of Rishabhānātha - VIII, 87
- Gondal, tn. in Kāthiāwād - VI, 15
- Gosvāmi Mahārājas or Vallabhāchāryas - VIII, 6
- Greek geographers and Western India - VIII, 2
- Gujarāt, VI, 1-19, 20; history, VII, 1-16.
- Gumti Masjid at Isanpur - VIII, 36f
- Gupta Dynasty - VI, 2
- Hāfiz Muhammad Nāsir, minister to Shaishtāh Khān, 1648 - VI, 17
- Haidat Khān's masjid - VII, 20-21; VIII, 55
- Haidar Qulī Khān Bahādur Zafīr Jang, 51st viceroy of Gujarāt, 1721-1722 - VI, 18
- Hāji Hamīdud-dīn, name of Muhammad Ghansul 'Ālam - VIII, 48
- Hāji Kālū, a slave of Mahmūd Baiqara - VII, 75
- Hāji Khān, reputed builder of Achut Bibi's mosque - VII, 64
- Hāji Sāheb, or Hāji Sakhi's mosque in Daryāpur - VIII, 66
- Hajipur suburb - VII, 64
- Hāji Yūsuf's tomb at Cambay - VI, 29
- Hakīm 'Ainul Mulk, officer of Akbar - VIII, 50
- Hālol, tn. in Gujarāt - VI, 39n, 40
- Handolā Tank - VIII, 37
- Hansanāthji's Jaina Temple - VIII, 86
- Haripūra, suburb of Ahmadābād - VIII, 6
- Hasan, grandson of Muhammad - VI, 29; VIII, 47, 75
- Hasan Muhammad Chishtī's mosque - VIII, 44-45
- Hathisingh's Jaina temple - VIII, 87-90
- hauz, a cistern, reservoir - VIII, 36, 42, 67
- Hauz-i-Quṭb or Kankariyā tank - VII, 44, 52, 53
- hāziri, distribution of food to holy men - VII, 37
- Hazrat Khān's rauza - VI, 38
- Hazrat Mūsā Suhāg's mosque - VIII, 78, 132
- Hazrat Pir's rauza at Dholkā - VIII, 76
- Hazuri Shāh's or Malik Shāhān's mosque in Ahmadābād - VII, 56
- Hemabhāi Vakhateband, Nagar Śeth of Ahmadābād - VIII, 87
- Hemachandra or Hemācharya, Jaina scholar - VI, 7; VIII, 84
- Hidāyat Bakhsh Madrasa and Masjid - VIII, 62
- Hidāl Khān Qāzi's mosque at Dholkā - VI, 30-32, 34, 36
- Hindāl Mirzā, brother of Humāyūn Sultān - VI, 13
- Hindū Architecture, VI, 5, 6, 10-11, 20, 38; VIII, 84ff; designs, VIII, 6, 10; planets, VIII, 11; horizon, eight points of, VIII, 96n; sculptures, VIII, 84; temples, VIII, 89.
- Hira gate at Dabhoi - VI, 7
- Hisāmud-dīn - VI, 8
- Hope, Sir Theod. C., - VII, 3, 25, 26, 41, 64, 86
- Humāyūn, Sultān - VI, 13, 24, 40; VII, 1, 6
- Husain Sayyid or Qāzi 'Alī's masjid - VIII, 70
- Husain of Khorāsān, father of the Mirzās - VI, 14
- Husain Yāwar Khān Momin Khān, Nawāb of Cambay, 1841 - VI, 25
- Ibn Batuta quoted - VI, 24
- Ibrāhīm Khān, viceroy of Gujarāt, 1705 - VI, 17
- Ibrāhīm Sayyid's tomb in the Bhadr, VII, 43; his mosque, VIII, 36, 39.
- Idar, tn. in Mahi-Kānthā, VI, 11; mosque, VI, 10.
- Idrisi, Arab geographer - VI, 6, 30
- Ikhtiyārud-daulah's tomb in Cambay - VI, 24, 29
- Ikhtiyārul Mulk - VIII, 50
- Imādul Mulk Khush Kadam - VI, 13, 14
- Imādul Mulk, Gujarāt noble - VIII, 28
- Imādul Mulk Malik Isan, his mosque in Isanpur - VIII, 40
- Imām, a leader in the worship of the mosque - VIII, 37, 41
- in'ām, land held rent free - VIII, 16, 37, 59
- 'Ināyat Shāh's Mosque - VIII, 64
- Indra, Hindū god, guardian of the east - VIII, 95
- Inscriptions: at Bharoch, VI, 21, 22; at Cambay, VI, 23, 26, 29; at Dholkā, VI, 30, 32-34; at Chāmpānir, VI, 40, 42; at Ahmadābād in Jāmi' Masjid, VII, 35; in Sultān Ahmad's tomb, VII, 38; at Sarkhej, VII, 48; in Malik Shāhān's rauza, VII, 55-57; at Batuvā, VII, 62; at Dastur Khān's masjid, VII, 76; in Mubāfiz Khān's masjid, VII, 78; in Shāh Khush Sayyad's masjid, VII, 82; in Rāoi Sipari's masjid, VII, 84; on Bāi Harir's wāv, VIII, 4, 8; on Adālal wāv, VIII, 12; at Shāh 'Ālam, VIII, 19; in Darvesh 'Alī's mosque, VIII, 25; in Alif Khān's masjid, VIII, 43; in Shaikh Hasan Muhammad Chishtī's masjid, VIII, 44; in Bābā Lulū's mosque, VIII, 47; in Shujā'at Khān's masjid, VIII, 61; in Qāzi Muhammad Rukhnul Haq's tomb, VIII, 63; in Ganj 'Ināyat Shāh's masjid, VIII, 64; in the Kharāti masjid, VIII, 65; in Ashraf Khān's masjid, VIII, 70; in Pīr Qutbuddīn Sayyid's rauza, VIII, 74; in the Kāchni masjid, VIII, 75; on Mūsā Suhāg's rauza, VIII, 78; in the Bhadr, VIII, 84.
- Irādāt Khān, title of A'zīm Khān - VIII, 59
- Isanpur: step-well of Jethābhāi Jivanlāl Nagjibhāi or Mulji, VII, 29, 73-74; VIII, 13, 14, 37, 83; Gumti masjid, VIII, 37; 'Imādul Mulk's masjid, 40-42.
- Islām Khān, governor of Gujarāt, 1632 - VI, 16
- Isma'il Qulī Khān, viceroy of Gujarāt, 1590 - VI, 14, 15
- Itimād Khān Gujarāti - VI, 14, 15; VIII, 50f

- Jagat or Dwārakā - - - VI, 12
- Jagavallabha Pārśvanātha, a Jaina image VIII, 87
- Jahāngir, emperor - - VI, 16, VIII, 23
- Jahāngir Qulī Khān, deputy governor of
Gujarāt, 1609-1611 - - VI, 16
- Jahānpānāb, wall of Chāmpānir citadel - VI, 12, 40
- Jains: VI, 2, 3, 5; Jaina or Gujarāt style of archi-
tecture, VI, 6, 7; VII, 11-16, 23, 32, 47; Jaina
temples, at Mount Abu, VII, 6; at Karnāvatī, VI, 6;
at Gīrnār, VI, 6; others, VI, 20, 23, 30, 38; VIII,
33; at Aḥmadābād, 85f, 93.
- Jalāl Khān Qutbūd-dīn Shāh, 1451-1459, VI, 11; VII, 27
- Jalālud-dīn Firūz Shāh, emperor 1290-
1296 - - VI, 8, 93
- Jalālud-dīn Mālī 'Ālam, 5th in descent
from Shāh 'Ālam - - VIII, 15, 20
- Jāmī' Masjids: at Junāgaḍh, VI, 12; at Bharoeb,
VI, 20; at Cambay, VI, 25, 26, 27; at Chāmpānir,
VI, 12, 41-44; at Dholkā, VI, 32, 33, 36; at
Aḥmadābād, VII, 10, 15, 17-19, 29, 30-36, 71;
VIII, 72; at Dehli, VIII, 20, 21; at Māndal,
VIII, 92; at Kapadvāj, VIII, 93.
- Jaras, hunter who shot Kṛishṇa - - VI, 2
- Jarasandha, early king of Magadha - - VI, 2
- Jaswantsingh of Jodhpur, viceroy of
Gujarāt, 1659-1662 and 1671-1674 - - VI, 17
- jat*, a personal grant - - VIII, 6
- Jannpur, VI, 13, 16n; mosques, VIII, 48, 49.
- Jawān Mard Khān Bābī, title of Kamālud
dīn, Khānī Khān - VI, 19; VII, 73; VIII, 24, 82
- Jayaṇtī-devī, Hindū goddess, temple at
Karnāvatī - - VI, 6
- Jayaśekhara, early ruler at Panchāsar - - VI, 3
- Jayasīma, Siddharāja, Chaulukya king VI, 6, 7;
VII, 10
- Jaysingh Patāi Rāwal of Chāmpānir - - VI, 39
- Jethabhāi Jīvanlal Nagjabhāi or Mulji's
wāw - - VII, 28, 73; VIII, 13, 37, 83
- Jhābua, native state - - VI, 17
- Jhālāwād VI, 13; Jhālā chieftains, VIII, 92.
- Jhīnjhuwādā, tn. in N. Gujarāt - - VI, 6
- Jiji-Bābā Rāpi's wāw at Isanpur - - VIII, 14
- Jina, or Tīrthāṅkara of the Jains VI, 22;
VIII, 85, 86
- Jitpur, tn. - - VI, 10
- jirātkhāna*, insect room in a Pāñjrapol - - VIII, 76
- Jodhpur, state - - VI, 1, VIII, 61
- Jogai Khānum, daughter of Momin Khān II - VI, 24
- johar*, or *jauhar*, immolation of the wives
of Rajputs - - VI, 39
- Jumlatul-Mulk, Nizāmud-Mulk, 52nd
viceroy of Gujarāt, 1722-1723 - - VI, 18
- Junāgaḍh, VI, 9, 10, 12, 15; VII, 1, 5, 6; VIII, 90;
Nawāb of, VIII, 71.
- Junaid, governor of Sindh, A.D. 724ff - - VI, 3
- Juzr, early Muhammadan name for
Gujarāt - - VI, 3
- Ka'bah of Makkah, the tras *qibla* VIII, 26 and n
- Kachh, prov. - - VI, 1-4, 9, 12, 15, 18
- Kāchnī masjid - - VIII, 52, 75
- Kaḍī, fort in Gujarāt, VI, 16; Kaḍī pargana, VIII, 63.
- kakshāsana*, seat-back or protection - - VIII, 30
- kalāśas*, finials shaped like vases - - VIII, 89
- Kāle Shāhid, tomb ascribed to - - VII, 38
- Kālī, goddess - - VIII, 84
- Kālimah*, the Musulman creed - - VIII, 75
- Kālol, tn. and dist. in Gujarāt - - VIII, 12
- Kālyāṇa, tn. in the Konkan - - VI, 2
- Kamāl Shāh Malwī's rauṇa - - VII, 29
- Kamālud-dīn, father of Abū Turāb - - VIII, 50
- Kamālud-dīn Gurg, officer of Muḥarak Shāh - VI, 8
- Kamālud-dīn Khān Bābī, Jawān Mard
Khān II - - VIII, 82
- kambha*, a pillar - - VI, 10
- Kambhāt, or Kambhāyat, Cambay, VI, 1, 2, 4, 5, 8,
9, 12, 15, 19, 20, 23, 24; VIII, 50
- Kanauj or Kanyākubja, capital in N. India - VI, 3n, 4
- Kankariyā talāv Hanḍ-i-Qutb, VI, 11; and palace,
VII, 4; VII, 44, 51-53, 73; VIII, 39, 82.
- Kanṭhkoṭ, fort in Kachh - - VI, 4, 5
- Kapadvāj, Skr. Karpaṭavāṇijya, tn., VIII, 15, 93-94;
Jāmī' Masjid at, VIII, 93; *kaṇḍa* or reservoir, and
Kirtistambha or Torana arch, VIII, 91.
- Karbālā or Mashadul Husain, place of
pilgrimage 50 miles S.W. of Baghdād - - VI, 28
- Karṇa, Chaulukya king, 1063-1093, VI, 6; VIII,
10, 12, 84; Karṇasāgara, artificial lake, VI, 6.
- Karṇa II, Ghelo, Vāghela king, 1296-
1304 - - VI, 8
- Karnāvatī or Sri Nagara, anc. city on site
of Aḥmadābād - VI, 6, 10; VII, 18; VIII, 2, 84
- Kārtalab Khān, or Shujā'at Khān, 39th
viceroy, 1686-1703 - - VI, 17; VIII, 61
- Kaship-no Ghumto, at Shāh Bādshāh Pīr's
rauṇa - - VIII, 81
- Kāthiāwād (Sorath) - - VI, 1-3, 5; VIII, 89, 91
- Kāthī tribe - - VI, 2; VIII, 59
- kātib*, a Mullā or Maulavi - - VI, 27
- kāyotsarga*, standing ascetic, attitude of
Jains - - VIII, 85, 86
- Kētn, moon's descending node - - VIII, 11, 12
- Khalil Khān, i.e. Mozaffar II, 1511-1526 - VI, 13
- Khalilābād, tn. - - VIII, 59
- Khān-i A'zam, Mirzā 'Aziz Koka - - VI, 14, 16
- Khān Jahān, deputy viceroy, 1624 - - VI, 16
- Khān Jahān or Rāo Maḡḡalik, VIII, 72; Khān Jahān
Gate, Aḥmd., VII, 10; Khān Jahān Masjid, VIII,
76.
- Khān-ki masjid or Alif Khān's mosque at
Dholkā - - VI, 34
- Khān Sarovar Tank at Patan - - VII, 51
- Khangār, prince of Junāgaḍh - - VI, 9n
- Khānkhānān, title given to Mirzā Khān,
viceroy, 1584 - - VI, 15

- Khânji Khân, Jawân Mard Khân, 1725 - VIII, 82
 Khârâghoḍa, vill. - - - VIII, 91
 Kharâti Masjid, near Dehli gate of
 Ahmadâbâd - - - VIII, 65
 Kheḍa, tn. and dist. - VI, 1, 18, 46, VIII, 93, 94
 Khizr Khân, son of 'Alaud-dîn Khilji - VII, 1
 Khonja Bibi, or Darvesh 'Alî's mosque - VIII, 25
 Khudâwand Khân, or Malik 'Alim - - VII, 26
 Khwâja Khidr: his tomb at Kambhay - VI, 29
kirtimukh, figure - - - VIII, 95
kirtistambha at Kapadvanj - - VIII, 94
 Kochrab mosque, VII, 73; VIII, 36, 84; Kochrava-
 devi or Kocharabâ, goddess, VI, 6.
 Koli-, wild tribe, VI, 2, 40; VIII, 59; of Balor, VIII, 82.
 Koṭâ, tn. in Mâlwa - - - VI, 11
 Krishṇa, god - - - VI, 2; VIII, 90
 Kshatraps or Satrap dynasty - - VI, 2
 Kubera, god of wealth and guardian of
 the north - - - VIII, 95
 Kumârapâla, Chaulukya king, 1143-1173 VI, 6, 7;
 VII, 11
 Kumârî Devi, goddess - - - VI, 23
 Kumbha Râpâ of Mewâr - - - VII, 54
kuṇḍa, well at Kapadvanj - - VIII, 91, 94
 Kunsâgar, artificial reservoir - - VI, 6
 Kuntalpur, anct. city at Sarval - - VIII, 95
- Lâdle Pir's rauza in Râyakhâd Rohilawâd VIII, 43
lalita mudra, attitude in sitting - - VIII, 94
 lampstands - - - VII, 79, 80
langarkhâna, almshouse - - - VII, 37
 Lâta, anct. name for Koṭkap - - VI, 4
 Latif Khân, brother of Bahâdur Shâh - VI, 13, 14
 Lavanaprasâda, Vâghela chief - - VI, 7, 23
 lighting of mosques - - VII, 28, 42, 65
 Lunsâwâḍâ, tn. - - - VIII, 65
- madrassa*, a college - - VIII, 60-62, 63
 Mahâbat Khân, viceroy 1662-1668 - VI, 17
 Mahâkâl, a god - - - VIII, 91
mahalla, a ward of the city - - VIII, 28, 53
 Mahāvîra, the 24th Jaina Tîrthaṅkara - VIII, 86
 Mâhî, river - - VI, 13, 23; VIII, 95, 96
 Mahîpa, a Vâghela chief of Kâlol - - VIII, 12
 Mahîsha, a demon, and Mahîshamarîṇî
 or Mahîsaghnî, the slayer of Mahîsha - VIII, 84
 Maḥmûd of Ghazni - - VI, 2, 5; VIII, 75
 Maḥmud Khilji of Malwâ - VI, 11, 13, 39; VIII, 15
 Maḥmûd Shâh I Baiqara, Nasîrud-dunya
 wa'd-dîn Abul Faṭḥ - VI, 11-14, 39, 45, 46;
 VII, 5-6, 9, 14, 15, 26, 46, *et passim*;
 VIII, 4, 18ⁿ, 28, 50, 70, 72
- Maḥmûd Shâh II of Gujarât, 1526 VI, 13; VII, 6, 8
 Maḥmûd Shâh III (1536-1553) - VI, 14, 45;
 VII, 7, 8, 61, 82; VIII, 64, 70
 Maḥmûd Shâh II of Dehli - - VII, 2
 Maḥmûdâbâd, tn. and remains at - VI, 20, 45-47;
 VII, 6
 Maḥmûdâbâd, name of Châmpânîr - VI, 12, 39-41
maḥmûdî, coin - VI, 15 and *n*; VIII, 4 and *n*, 12
Maidân Shâh, royal square or palace
 court, Ahmadâbâd - - VII, 25; VIII, 59
 Mainala Sarovar or Malâv, artificial lake
 at Virangâm - - - VI, 6, 36
majlis, social reunions - - - VIII, 23
 Makdhûm Jamâl ad-dîn Jamân Shâh, built
 the Châmpâ-ki masjid - - - VIII, 65
 Makhdum Shaikh Ahmad Kattû - - VII, 46
 Malâv talâv at Dholkâ - - - VI, 6
 Malik Ahmad, one of the four Ahmads - VI, 72ⁿ
 Malik 'Ainul Mulk Multânî - - VI, 8
 Malik 'Âfin's Masjid and rauza at Dâpî
 Lîmqâ - - - VII, 26-29; VIII, 13
 Malik 'Ambar Habshî, governor of
 Daulatâbâd - - - VI, 16
 Malik Bahâud-dîn, Imâdul Mulk, 1466 - VII, 64, 70
 Malik Dînâr, Zafar Khân, governor of
 Gujarât under Mubârak Shâh - - VI, 8
 Malik Ghânî Khâsazâd, Dasturul Mulk,
 built Dastur Khân's mosque - - VII, 76
 Malik Ghânî, built 'Inâyat Shâh's masjid VI, 65
 Malik Ḥusain Bahmanî Nizâmul-Mulk, a
 Gujarât officer, 1520 - - VIII, 28
 Malik Jamâlud-dîn, Muḥâfiẓ Khân - VI, 12
 Malik Makhsûd Vazîr, brother of Malik
 Bahâud-dîn - - - VII, 69
 Malik Muḥarriḥ Sultânî, Farhatul-Mulk
 Rastî Khân, governor of Gujarât,
 1377-1397 - - - VI, 9, 10
 Malik Mukbîl, governor of Gujarât,
 1338-1347 - - - VI, 8, 9
 Malik Sârang, founder of Sârangpur - VIII, 24, 28,
 40, 75
 Malik Sarîrat Sayyid Jalîl, son of Shâh
 Ghayâsud-dîn - - - VIII, 68
 Malikush-sharq, title of Amîr Ḥusain bin
 Mirân - - - VI, 9
 Malik Shâbân, Imâdul-Mulk, VI, 61; VIII, 72;
 rauza and masjid, VII, 54-57.
 Malik Wajîhud-dîn Kuraishi Sadarul-
 Mulk Tâjûl-Mulk, governor of
 Gujarât, 1320 - - - VI, 8
 Malik Ya'kûb Muḥammad Hâjî, governor
 of Gujarât, 1387 - - - VI, 10
 Mamlatdâr's treasury, payments from - VIII, 23, 44
 Mânasa sarovar lake at Virangâm - VIII, 91-92
 Manasar Mâtî, a name for Baucharâjî, a
 goddess - - - VIII, 83
 Manohra's Masjid in Rakhayâl - - VIII, 83
 Mândal, anc. Mândale, tn. in Jâlâwâd, Malesvari
 temple at, VI, 4, 13; mosques at, VIII, 92.

- maṣḍapa*, portico of a temple - VIII, 87, 88
Maudelslo, Holstein traveller - VI, 17; VII, 25*n*, 53; VIII, 57, 59
Maṇḍalik Rāo, of Junāgaḍh - VII, 5
Māyḍu, capital of Mālwa - VI, 13
Ma'gala or Bhauma, Mars - VIII, 11
Manik Chauk in Aḥmadābād - VII, 31, 39; VIII, 72
Mankir, old name of Mālkhed - VI, 23
Mānol Temple - VIII, 84
al-Mansur, Khālif of Baghdād, 754-775 - VI, 3
maqbara, a tomb - VII, 40; VIII, 62
Marāṭhas - VI, 2, 17-19, 24, 40; VII, 9, 19, 41; VIII, 22, 58, 60, 82
Mariam Bibi's maṣjid and rauṇa - VII, 73; VIII, 82
Marino Saundo referred to - VI, 23
marqad, a burying ground - VII, 40
Marut or Vāyu, guardian of the N.-W. quarter - VIII, 96
Mas'udi, Arab writer - VI, 23
Mātā Bhavāni's wāy or step-well - VII, 10; VIII, 1-3, 5, 84
Maulānā Nurud-dīn Sidi's tomb - VIII, 63
Mayaṇalladevi or Mainaladevi, mother of Siddharāja - VI, 30; VIII, 91
Mazum Quli Khān, styled Shujā'at Khān - VI, 18
Melani Rāi, Hindu minister of Maḥmūd Khilji - VI, 13
Mehers, tribe - VI, 2
Mehmudābād, *see* Maḥmūdābād.
Memorial stones or Pāliyās - VIII, 85, 93
Mera, mythical mountain - VIII, 85
mihrabs - VI, 21, 25-27, 30, 32, 35, 37*n*, 42; VII, 19, 23, 26, 34, *et passim*; VIII, 19, 25, 26, 30, *et passim*.
minbar or *minbar*, pulpit - VI, 27, 31, 35; VII, 45, 49, 65, 71, 75, 76, 79; VIII, 26, 30, 31, 34, 37*n*, 47, 63.
minars or minarets - VI, 41; VII, 35, 42, 44, 67, 68, 80; VIII, 22, 24, *et passim*.
Mir Gadāi, son of 'Abū Turāb - VIII, 51
Mir Muḥammad Bāqir, A'zam Khān, viceroy - VI, 16 and *n*, VIII, 59
Mir Muḥibbullah, son of Abū Turāb - VIII, 51
Mira Sayyid 'Alī's maṣjid - VIII, 65
Mirān Muḥammad Shāh II Āsirī, Gujarāt Sultān, 1537 - VI, 13
Mirān Muḥammad 'Adil Khān Farukhi of Khandesh - VI, 12
Mirāna Chulāni maṣjid - VII, 65
Mirgī, wife of Shāh 'Ālam - VIII, 15
Mirzās, revolt of - VI, 14
Mirzā 'Askari, imperial general - VI, 13 and *n*
Mirzā Aziz Kokā, Khān-i-A'zam, governor of Gujarāt, 1573-1575 - VI, 14, 15, 16
Mirzā 'Isa Tarkhān, viceroy of Gujarāt, 1642-1644 - VI, 17
Mirzā Ja'far Najmud-daulah, governor of Cambay - VI, 24
Mirzā Khurram, afterwards Shāh Jahān, VIII, 57-59
Mirzā Muḥammad Ja'far Nazm Sāhni Momin Khān's maṣjid - VIII, 68
Mirzā Sayyid Beg, built the Idrūs mosque at Surat - VIII, 70
Miyān Khān Chishtī's mosque - VI, 12; VII, 69, 70; VIII, 7, 24, 57
Miyān Muḥammad Husain, known also as Dādā Miyān, his maṣjid - VIII, 66
Mokalasimha or Mugatsimha, chief of Kālol - VI, 9
moksha, deliverance from transmigration - VIII, 85
Momin Khān I, Najmud-daula Firūz Jang, 55th viceroy, 1737-1743 - VI, 18, 19; VII, 9; VIII, 68, 73
Momin Khān II, Najmud-daula Bahādur Firūz Jang, Mirzā Ja'far, governor of Cambay, 1748-1783 - VI, 24
Momin Khān III, Najmud-daula Montazul-Mulk Bahādur Dilāwar Jang, Nawāb of Cambay, 1789-1823 - VI, 25
Morki or Shaikh Muḥammad's maṣjid - VIII, 69
mu'azzan, caller to prayer - VI, 35; VII, 75, 80; VIII, 8, 36, 41, 49
Mu'azzam Khān's tomb - VIII, 78
Mubārak Sayyid's tomb at Sojālī - VI, 45, 47; VII, 6, 60
Mubārizar-Mulk Sorbuland Khān Bahādur Dilāwar Jang, viceroy 1723-1730 - VI, 18, 19; VIII, 82
Mudherā, tu., tank and sun temple at - VI, 6
Mufarrah Mufakr-al-Kowas Khas, Sultāni - VI, 33
Muftākhir Khān, son of Momin Khān - VI, 19, 24
Mughali Bāi's tomb - VII, 40
Muhāfiz Khān, Jamālud-dīn Silābdār, VI, 12; his maṣjid, VII, 78-81, 83, 85; VIII, 67.
Muḥammad's birthday - VI, 45*n*
Muḥammad Akramud-dīn, founder of Hidāyat Bakhsh mosque - VIII, 63
Muḥammad Amin Khān, viceroy 1678-1682, his mosque - VI, 17; VII, 43
Muḥammad Amin Khān Umdatul-Mulk, viceroy 1674 - VI, 17
Muḥammad Anwar Khān Bābi's tomb - VII, 73; VIII, 82
Muḥammad Ā'zam Shāh, son of Aurangzib, viceroy 1686 and 1703-1705 - VI, 17
Muḥammad Ghans Gwālārī's mosque - VIII, 48-50, 53
Muḥammad Mu'azzam Shāh, son of 'Ālamgir, afterwards Bahādur I - VI, 17
Mu'ammad Quli, Nawāb of Cambay, 1783-1789 - VI, 24
Muḥammad Šafi, styled Saif Khān - VI, 16; VIII, 57
Muḥammad Sālīb Badākshi, his mosque - VIII, 21

- Muḥammad Sayyid's or Ghī-kāntā masjīd VIII, 69
 Muḥammad Shāh I of Gujarāt, Tatar Khān, 1403-1404 VII, 1, 2, 8
 Muḥammad Shāh II Karīm Ghayāsud-dunya wa-nd dīn, 1443-1451 VI, 11, 39; VII, 1, 4, 8, 37; VIII, 22
 Muḥammad Shāh Tughlaq I VI, 8, 9, 24, 28
 Muḥammad Shāh Tughlaq II, 1387-1389 VI, 9, 10
 Muḥammad Shāh Tughlaq III VII, 2
 Muḥizud-dīn bin Sām, called also Shāhābud-dīn Muḥammad Ghori of Gaznī VI, 7
 Muḥizud-dīn Nizāmud-Mulk, governor of Gujarāt, 1347 VI, 9
 Mukhtar Khān, 38th viceroy, 1683-1686 VI, 17; VIII, 61
 Mūlarājā, Solāṅki king, 941-996 A.D. VI, 4, 5, 23; VIII, 12
 Mūlarājā II, Solāṅki king, 1176-1178 VI, 17
 Mullā, or Kātib, reader in a mosque VI, 27
 Mūlūk khāna, royal chapel or gallery VII, 18, 23, 34, 71; VIII, 92, 93
 Murād Baksh, viceroy 1654-1657 VI, 17
 Muri, a seat of the Svāmī Nārāyaṇa sect VIII, 90
 murīd, a disciple of a murshīd VIII, 21
 Murkī-Bībī's tomb VII, 40, 44
 murshīd, a religious guide VIII, 48
 Mūsā Miyān, late ināmdār of Shāh 'Ālam VIII, 21
 muṣallās, jai-namas, or prayer-mats VIII, 62
 Muṣṭafa Sayyid's masjīd in A. madābād VIII, 74
 Muṣṭafābād, Muhammadan name for Junāgaḍh VI, 12, 15
 muṣaffar khāna, a rest house, refuge VIII, 61
 Muṣaffar Shāh I, 1396-1403 VII, 2, 8, 15, 46
 Muṣaffar Shāh II, 1511-1526 VI, 13; VII, 6, 7, 84; VIII, 40 and n
 Muṣaffar Shāh III, 1561-1572 VI, 14-15; VII, 7, 8; VIII, 22
 Mylāssa, tomb VII, 12, 21

 Naḍiād, tn. VI, 11, 19
 Nadol, Muṣaffar Shāh III defeated at, in 1584 VI, 15
 Nāgara, old site of Kambhāyat VI, 23
 Naginā gardens at Kankariyā-tālāv VII, 53
 Naginā masjīd at Chāmpānīr VI, 43-44
 Naginā Pōl masjīd or Bādshāh Sayyid's VIII, 65
 Nahrvalah or Pātān, Anhilwādā VI, 3, 4, 6, 10
 Nairitī, Hindu god, ruler of the S.-W. quarter VIII, 96
 Najābat Khān, built the minārs at Shāh 'Ālam VIII, 21
 Nānha Idrus rauṇa VIII, 54
 Nang Sara or Ganj 'Ināyat Shāh's mosque VIII, 64
 Narasīnha or Vishṇu, god VIII, 85
 Narmadā, river VI, 1, 4, 17, 20, 30, 39
 Nārāyaṇa or Vishṇu, god VIII, 85
 Nāṣir Khān, Maīmūd II, 1526 VI, 13
 Naṣir Sayyid or Qāṣi Sāheb's masjīd VIII, 73
 Naṣirud-dīn Khusrū, Shāh of Dehli, 1320 VI, 8
 Naṣirud-dīn, Nawāb of Baroda, his tomb VIII, 21
 Nāṭeśa, form of Siva VIII, 84, 90, 91
 Nau Khān Farbatul-Mulk, repaired Sulṭān Aḥmad's tomb VII, 38, 82, 83
 Nausāri, tn. in the Koṭkāṇ VI, 2
 Navagraha, nine so-called planets VIII, 10
 Nawāb Sardar Khān's masjīd and tomb VIII, 55, 56, 95, 102
 Nawāb Shāhjahān Khān, and Momīn Khān's masjīd VIII, 68, 73
 Nawāb Shujā'at Khān's mosque VIII, 56, 61-62, 106
 Neminātha, old Jaina temple of, in Aḥmadābād VIII, 86
 Nenpurwādā masjīd VII, 73; VIII, 13, 83
 nijmandīr or shrine of a temple VIII, 87
 Nizāmud-dīn's tomb at Maḥmūdābād VI, 46

 Ojā Bībī or Darvesh 'Alī's mosque VIII, 25

 pāduka, footprints, worship of, by Hindūs, Jains and Buddhists VIII, 20
 Pāḍī Koehrah, suburb of Aḥmadābād VIII, 37
 pāṭiyā or monumental stone VIII, 85, 93
 Pauchāsar, old capital in Gujarāt VI, 3
 pāṭjīrūpol, animal asylum VIII, 76
 Pārsis VI, 23
 Pārśvanātha, sacred mountain of the Jains and the 23rd Tīrthāṅkara VIII, 37
 Pārvatī or Bhavānī, a goddess VIII, 2
 Pātān step-well, VIII, 13; pargāṇa, VIII, 63, 82.
 Pāwāgaḍh, fort of Chāmpānīr VI, 12, 23, 39; VII, 78
 pendentives, employment of VIII, 22
 Phuti or Faṭha masjīd VIII, 86
 pillars VII, 39-40
 pīppal leaf symbol VII, 80; VIII, 21
 Pīr, a holy man VII, 69
 Pīr Bāqir Shāh's rauṇa VIII, 81
 Pīr Kamāl's graveyard VIII, 72
 Pīr Mashāyok's rauṇa VIII, 81
 Pīr Qāsim Khān's rauṇa VIII, 81
 Pīr Vazīrshāh or Wāḥidshāh Pīr's masjīd and rauṇa VIII, 67
 Pīrānā sect of Musalmāns VIII, 81
 Pirmad Shāh's masjīd and rauṇa VIII, 71
 pīrṇadā or spiritual guide VIII, 44
 pośhālā, Jaina paushadhā or monastery VI, 23
 Prabhūsa Pattana, tn. VI, 2
 pradakṣhīṇa, circumambulatory passage VIII, 87

- Prayāg, Allahābād - - - VI, 4
 prayers, Muhammadan - - - VI, 33*n*
 Premachand, *salāt* of Hathisingh's Jaina temple - - - VIII, 88
 propylons of Jaunpur mosques - - - VIII, 49
 propylon of Muhammad Ghang's mosque - VIII, 49
 Public Works Department - VII, 17, 23, 26, 80 ; VIII, 7, 29, 35, 48
 Pushpadanta, 9th Jaina Tirthamkara - VIII, 87
- qabr*, grave, VI, 38*n* ; VII, 21, 59, 65, 72 ; VIII, 39, 41, 80 ; *qabrgāh*, *qabristān*, burying ground, VII, 40 ; VIII, 18.
qadam-i-Mubārak, *qadam-i-rasul*, foot-prints of the prophet - - - VIII, 20, 21, 50
 Qadam Rasul masjid, at Dehli, Gaur, &c. VIII, 20, 50, 51
 Qādiriya sect of Dervishes - - - VIII, 67, 75*n*
 Qalandar faqirs - - - VIII, 72*n*
 Qāsim Khān, viceroy 1657-1659 - VI, 17
 Qāsim Khān's rauza at Chhūdāwād - VIII, 78
 Qāzī 'Abul Farah Khān's mosque in Jhavēriwādā - - - VIII, 54
 Qāzī 'Alī or Husain Sayyid's masjid - VIII, 70
 Qāzī Husainud-dīn of Ahmadābād - VIII, 13, 54
 Qāzī Muhammad Nizāmud dīn Khān, first Qāzī of Ahmadābād - - - VIII, 63
 Qāzī Muhammad Saleh's and Qāzī Muhammad Rakhnūl-Haq's tomb - VIII, 63
 Qāzī Nānha 'Idrūs or Chhota 'Idrūs masjid - - - VIII, 54
 Qāzī Salahud-dīn Chishtī - - - VIII, 65*n*
 Qāzī's Masjid at Mānilāl - - - VIII, 92
 Qāzī's Mandirsālā or Hidāyat Bakhsh madrasa - - - VIII, 62
 Qāziul-Mulk, Ahmad Shāh II, 1554-1561 - VI, 14
qiblas or *mihrābs*, VI, 21, 25, 26, 27 ; origin of, VI, 26, 37 and *n* ; VIII, 33*n* ; peculiar form, VIII, 50.
 Queen's or Rānī Rūpāvatī's mosque in Mirzāpur, *q.v.*
 Qulij Khān Andajāni, governor of Surat, and afterwards of Gujarāt - VI, 16
 Qutbud-dīn Aibak of Dehli, 1206-1210, invaded Gujarāt - - - VI, 7
 Qutbul 'Ālam or Qutbul Kitāb's tomb at Batuwā - - - VI, 46 ; VII, 60-62 ; VIII, 40
 Qutbul Auliya Shaikh Hasan Muhammad Chishtī's masjid - - - VIII, 44-45, 51
 Qutb bin Khājagi, builder of Qutbud-dīn or Pīr Qutb Sayyid's, or Qutb Shāh Divān's rauza - - - VIII, 74
 Qutbud-dīn Shāh of Gujarāt, 1451-1459, VI, 11 ; VII, 4, 7, 46, 54, 60, 61, 71 ; VIII, 50, 70 ; his masjid, VII, 44-45, 49.
 Qutbul 'Ālam, *see* Shāh 'Ālam.
- Rādha, worshipped by the Svāmi Nārāyaṇa sect - - - VIII, 90
 Rāhu, moon's ascending node - - - VIII, 11, 12
 Rājapur Hirpur mosque and rauza - VII, 44, 71-74 ; VIII, 25, 39, 82
rājyachintākāri, a Hindu state minister - VI, 7
 Rakhiyāl village, VII, 54, 57 ; VIII, 83 ; small mosque, VIII, 83.
 Rāpā Nākha, a Rājput chief - - - VI, 3
 Rāqī's Mosque, Sārangpur, *see* Sārangpur.
 Rāqī Udayāmātī's well at Anhilavādā - VI, 6
 Rāqī-ka Hājirā or Queen's tombs - VII, 39-40
 Rāqī Rūpāvatī's masjid and tomb in Mirzāpur - - - VIII, 32-35, 68
 Rāqī Siparī's mosque - VII, 73, 79, 83-87 ; VIII, 25, 29, 30, 32, 34, 36
 Rānpur, Jaina temple at - - - VIII, 84
 Rāo Bharmal, 1585-1631 - - - VI, 15
 Rashid Miyyān Pīr's Shrine - - - VIII, 44
 Rasulābād or Shāh 'Ālam - - - VIII, 16, 40
 Rāshod or Rāshtrakūṭa dynasty - - - VI, 4
 Ratnasingh Bhandāri, deputy viceroy 1733 - - - VI, 19
 Rāyapur or Qāzī Sāheb's masjid, VIII, 73 ; Rāyapur gate, VIII, 82.
 Revatāchala and Urjayata, ancient names of Mt. Girmār - - - VI, 2
 Ridvan, gatekeeper of paradise - - - VIII, 59
 Rishabhānātha, 1st Jaina Tirthamkara - VIII, 86
 Roho, step-well - - - VIII, 13
 Roshan Pīr or Dādā Miyyān's masjid - VIII, 66
 Rudra-Māla, Śaiva shrine at Siddhapur - VI, 4-5, 6, 8
 Rustum 'Alī Khān, governor of Surat, 1724 - - - VI, 19
 Rupen, river - - - VI, 6
- Sabhā maṇḍapa* or assembly hall of a temple - - - VIII, 87, 95
 Sābhramatī, river at Ahmadābād - VI, 6, 11 ; VII, 46, 69 ; VIII, 57, 58, 65
 Sa'adat Baish, a native of Kitūrā - - - VIII, 47
 Sadhāran, a chief of Thāsra, ancestor of the Ahmad Shāhi family - - - VI, 10
 Sālri or Rānpur, Jaina temple - - - VII, 28, 32
 Safdar Khān Bābi, a title of Muhammad Anwar Khān - - - VI, 18 ; VIII, 82
 Sahajānand, name assumed by Svāmi Nārāyaṇa - - - VIII, 89
 Sahasraliṅga tank at Patan - - - VI, 6
 Saifud-dīn, brother of Nizāmud-dīn - VI, 46
 Saif Khān Muhammad Safi, VI, 16 ; his tomb, VIII, 21.
 Śaiva Jyotrlīṅgas, VI, 5 ; Śaiva shrines, VI, 4, 7 ; VIII, 88, 91.

- Sakar Khân's mosque and rauza - VII, 75-76 ; VIII, 70
- Salâbat Muḥammad Khân, brother of Jawân Mard Khân - VIII, 82
- salât, master-mason - VIII, 88
- Sambhava, Sambhavanâtha, 3rd Jain Tirthakara - VIII, 86, 87
- Sameta Śikhara, Sammeya or Samara Śikhara, mythological mountain of the Jains - VIII, 85, 86
- samosan, representation of a sacred mount - VIII, 85
- Samsâmul-daula Basârat Jang Bahâdur, 49th viceroy, 1716-1719 - VI, 18
- Sârâ cave temples, in Kâthiâwâd - VI, 2
- Saṅgramasîmha Râpâ of Mewâd - VI, 13 ; VIII, 28
- Sani, Saturn - VIII, 11, 12
- Sanjar Khân, called Ulugh Khân, brother-in-law of 'Alâud-dîn Khilji - VI, 8
- Sapâdalakshî, Sâkhambarî or Sâmbhar - VI, 4
- sarâ'e, a mansion, a rest-house - VIII, 59
- Sârâṅgadeva, Vâgbela king, 1274-1296 - VI, 8
- Sârâṅgpur Queen's mosque - VI, 12 ; VII, 70, 72 ; VIII, 28-31, 37, 72
- Sarasvatî, river - VI, 3
- Sarâzi Sâheb's rauza - VIII, 73
- Sarkhej buildings, VI, 3 ; VII, 4, 46-51, 69 ; VIII, 78 ; sarcophagi, VIII, 73.
- Sarnal, vill. and old temple - VIII, 95, 96
- Satârakâ, yoginî of Pushpadanta Tirthakara - VIII, 87
- Satranjaya, hill and Jain shrines near Pâlitânâ - VI, 2 ; VIII, 88
- Sati or Pâliyâ stones - VIII, 93
- Saurâshṭra, ancient name of Kâthiâwâd - VI, 2
- Sayyad Murtaẓâ Khân Bukhârî, viceroy of Gujarât, 1606-1609 - VIII, 51
- Sayyid 'Abdul Jalîl's rauza - VIII, 68
- Sayyid 'Âbdul Qâdir al-Jilânî, founder of the Qâdiriyyah dervishes - VIII, 67, 75a
- Sayyid 'Âbdul Qâdir, Bâwâ Miyân, the pûrâda, 1885 - VIII, 71
- Sayyid Adham, son of Sayyid 'Âlam, a Bukhârîah Sayyid - VII, 67
- Sayyid Aḥmad, deputy viceroy at Aḥmadâbâd, 1659 - VIII, 55
- Sayyid Aḥmad Gilânî, governor of Sorath 1711 - VI, 18
- Sayyid Aḥmad Kabîr, father of Quṭbul-'Âlam - VIII, 15
- Sayyid Aḥmad Shahîd Panâh 'Âlam, grandson of Shâh 'Âlam - VIII, 15
- Sayyid 'Âlamud-dîn or 'Âlam Abû Bakr's masjid - VI, 31 ; VII, 22-24 ; VIII, 67
- Sayyid 'Askarî Miyân's tomb - VIII, 76
- Sayyid Badha bin Sayyid Yâqût, tomb of his wife at Râjapur-Hîrpur - VII, 71
- Sayyid Burhânud-dîn Quṭb 'Âlam - VII, 60, 67 ; VIII, 15
- Sayyid Hamîdî Bukhârî, left by Akbar to govern Dholkâ - VI, 30
- Sayyid Hamîd Ja'far Shirâzi, founder of the Sunni Bohrâ sect - VIII, 74
- Sayyid Hasan Nur 'Âlam, 4th in descent from Shâh 'Âlam - VIII, 15
- Sayyid Hazrat Shams al-shamas Shaikh bin Abdulla al-Idrûs - VIII, 69
- Sayyid Ja'far Bhadr 'Âlam, 8th in descent from Shâh 'Âlam, VIII, 15, 20, 22 ; his rauza, VIII, 73.
- Sayyid Jalâl-i-Bukhârî or Makhdûm Jahânîan Jahângasht - VIII, 15, 20, 50a
- Sayyid Jalâlud-dîn Mâh 'Âlam, 5th in descent from Shâh 'Âlam - VIII, 15
- Sayyid Jalâlud-dîn Maqâud 'Âlam, 7th in descent from Shâh 'Âlam - VIII, 15, 20
- Sayyid Muḥammad Ja'far's masjid - VIII, 73
- Sayyid Muḥammad Mahbûb 'Âlam, 9th in descent from Shâh 'Âlam - VIII, 15, 20
- Sayyid Muḥammad Maqbul 'Âlam, 6th in descent from Shâh 'Âlam - VIII, 15, 20
- Sayyid Muḥammad Shâh 'Âlam, son of Quṭbul 'Âlam - VIII, 15
- Sayyid Muṣṭafa's tomb - VIII, 66
- Sayyid Qâsim, son of Sayyid 'Âlamud-dîn - VII, 22
- Sayyid Shaikh Muḥammad or Sayyid Jîn - VII, 60
- Sayyid Sharaf Tamîn, builder of Cambay mosque - VI, 23
- Sayyid 'Usmân, VII, 60 ; masjid and tomb, VI, 12 ; VII, 67-69 ; VIII, 40.
- Sayyidi Masjid at Mândal - VIII, 9a
- sen of a mosque - VIII, 48, 67, 72
- Shâh 'Abdul Faṭḥ's masjid in Shâbapur, VIII, 67, 80
- Shâh 'Abdul Khalak Sayyid, 'Abdul Qâdir - VIII, 75
- Shâh 'Abdul Wâḥab's masjid in Khân-pur - VIII, 67, 68
- Shâh or Shaikh Aḥmad Khattû's tomb at Sarkhej - VI, 11, 13 ; VII, 46, 50 ; VIII, 72a
- Shâh 'Âlam buildings - VI, 12 ; VIII, 15-23
- Shâh 'Âlam Muḥammad Bukhârî - VII, 40, 44, 60 ; VIII, 15, 37
- Shâh 'Âlî Razzâq's rauza - VIII, 54
- Shâh 'Altî Kamdhani's masjid and rauza - VIII, 42
- Shâh Bâda Qâsim's rauza - VIII, 75
- Shâh Badshâh Pîr's rauza in Shahrkotdâ - VIII, 80
- Shâh Faẓl's mosque in the arsenal - VII, 77
- Shâh Ghaznî's masjid in Râyakhâd Rohilawâd - VIII, 43
- Shâh Gumân, suburb - VIII, 78
- Shâh Isma'îl-i-Safawî, king of Persia - VIII, 50
- Shâh Jahân, Prince Khurram - VI, 16 ; VII, 7 ; VIII, 59
- Shâh Khûb Sayyid Muḥammad Chishtî's mosque - VII, 82-83 ; VIII, 38, 81
- Shâh Mahbûb Majzub's rauza - VIII, 81
- Shâh Muḥammad 'Alî's masjid in Jamâl-pur - VIII, 74

- Shâh Nawâz Khân Safâvi, viceroy, VI, 17; VIII, 55
 Shâhi Bâgh palace - - VI, 16; VII, 57-58
 Shâhpur mosque, known as Champâ-ki masjid, VIII, 44, 64; Qâzi's mosque, VIII, 46, 47.
 Shaikh Farid-i-Bukhârî, VI, 16; VIII, 53; Shaikh Farid's tomb at Pattana, VIII, 29.
 Shaikh Hassû Muqarrab Khân, 14th viceroy, 1616 - - - VI, 16
 Shaikh Muhammad (or Ahmad) Chishtî's rauza - - - VIII, 71
 Shaikh Muhammad Jahid's, or Morki masjid and rauza - - - VIII, 69, 71
 Shaikhul-Islâm, a title - - - VIII, 63 and *n*
 Shâistah Khân, viceroy 1647-48 and 1652 VI, 17; VII, 62
 shaking minarets - - - VII, 32
 Shamsîr Khân, Sadhu, brother of Wajihul Mulk of Thâsarâ - - VI, 10
 Shamsud-din Damghânî, governor of Gujarât, 1377-1387 - - - VI, 9
 Sharifa râja's grave - - - VIII, 76
 Sher Khân Bâbî - - - VII, 73
 Sher Khân Tar, viceroy 1637-1642 - - VI, 16
 Siddhapura, tn. - - - VI, 4, 6, 7, 11
 Siddharâja Jayasîmha - - - VI, 23; VIII, 91
 Sidi Bashir's mosque - - - VII, 70; VIII, 24*f*
 Sidi Sayyid's masjid and its windows - VII, 41-43
 Sikandar Shâh (1526) - - - VI, 13; VII, 6, 8
*śikhara*s, spires of temples - - - VIII, 88-90
 Śilāditya IV, of Valabhi - - - VI, 3
 Sindhapura, now Sibor - - - VI, 3, 4
 Sipahdâr Khân, viceroy 1633-1635 - - VI, 16
 Śiva, a god - - - VI, 23
 sluices - - - VII, 51-52
 Sojâlî tomb - - - VI, 45-47; VII, 60
 Soma or Chandra, the moon - - - VIII, 11
 Somaji's Channmukh Temple at Satruñjaya VIII, 88
 Somanâtha - - - VI, 2, 5, 6-8, 10
 Songadh - - - VI, 11, 18
 Sorath or Kâthiâwâd - - - VI, 1, 4, 9, 11, 16-19
 spiral domes - - - VII, 34, 71
 Śrāvaks or Jainas - - - VIII, 76, 85, 87, 88
 Śrîdeva, Jaina scholar - - - VIII, 84
 Śrinagara, a name of Karpûravatî - VI, 6; VIII, 84
 Stambhatirtha, Cambay; Stambheśvara, a god - - - VI, 4, 23
 Sojâ'at Khân Bahâdur, title of Mazum Quli Khân, VI, 18; his mosque, VI, 20; VIII, 61-62.
 Śûkra, the planet Venus - - - VIII, 11, 12
 Sultân Dâwar Bakhsh, called Mirzâ Bulâqî, viceroy 1622-1624 - - - VI, 16
 Sultân Murâd Mirzâ, viceroy 1595-1599 VI, 16
 Sumeru, mythical mount of the Jainas - VIII, 85
 sun-worship - - - VIII, 11
 Sunni Muhammadans - - - VI, 23; VIII, 67, 71
 Supârâ, vill. in the Koṅkan - - - VI, 2
 Surat, tn. - - - VIII, 70
 Sûrya temple at Mudherâ - - - VI, 6, 11
 Suvidhinâtha - - - VIII, 87
 Svâmi Nârâyana, his sect and temples VIII, 89-90
 Taghî or Taghâ, a rebel - - - VI, 9
Tah khânas, underground rooms - - - VIII, 58
 Tailapa-deva, Châlukyan king - - - VI, 4
 Tâj, Khân Narpâlî, builder of the Shâh 'Âlam rauza - - - VIII, 16, 18
 Tâka or Tânka masjid at Dholkâ - - - VI, 32
 Tânka Rajputs - - - VI, 10
 Tanâkawâlâ or Darvesh 'Alî's mosque - VIII, 25
 Tâtâr Khân Muhammad Shâh, son of Muzaffâr Shâh - - - VI, 10; VII, 2, 8
 Tejalpâla's temple at Abû - - - VI, 30; VIII, 85
 Thâsarâ, taken by Ahmad Shâh - - - VI, 11
 Thâsarâ, in Khedâ dist. - - - VI, 10; VIII, 95
 Thattâ, in Sindb - - - VII, 9
 Thevenot quoted - - - VII, 17; VII, 53
 Tiastanes, Gr. for Chastana, an early satrap - - - VI, 2
 Timûrîang's invasion of India, 1398 VI, 10; VII, 2
 Tin Darwâza, in Ahmadâbâd VII, 25-30; VIII, 59
 Tirthamkaras, Jaina hierarchs VI, 2, 3; VIII, 85-87
 Torapa, ornamental arch - - - VIII, 94
 trabeate style - - - VIII, 26, 32, 34, 45
 Tribhuvanapâla, Solânkhi king, 1241-1244 VI, 7
 Trimbak Bhûpadâs, râja of Châmpânîr - VI, 39
 triple spires or *śikhara*s - - - VIII, 89, 90
triśula, trident of Śiva - - - VIII, 55
 Udai or white ant, nickname of A'zam Khân - - - VIII, 59
 Udayâmatî, queen of Bhûmadeva I, Solânkî king - - - VI, 6
 Ujjain, city - - - VI, 2, 3; VIII, 57
 Ulugh Khân, Sanjar Khân - - - VI, 8
Upâsraya, Jaina monastery - - - VIII, 84
 Urjayata and Revatâchala, names of Mt. Gîrnâr - - - VI, 2
'urs, celebration of festivities - VIII, 22, 23 and *n*, 42, 46, 81
 Usmanpura, VII, 60, 69; mosque, VII, 78, 85.
 Uvarsâd step-well - - - VIII, 13
 Vadtal, vill. - - - VIII, 90
 Vâghela or Vyâghrapallî Râjâ of Dholkâ, VI, 7, 30; clan, VI, 30; VII, 2.
 Vaishnavya shrines at Viramgâm - - - VIII, 91
vajra, thunderbolt - - - VIII, 89
 Vakhat Singh of Jodhpur, 54th viceroy, 1730-1737 - - - VI, 19
 Valabhi, modern Valâ - - - VIII, 2, 3, and *n*

- Vallabhāchārya sect - - - VIII, 6
 Vallabharāja, third Chaulukya king - VI, 4
 Vanarāja, of Anhilavādā - - - VI, 3, 4
 Varuṇa, god, guardian of the West - VIII, 96
 Vastupāla, a Jaina chief, VI, 23, 30 ; VII, 11 ;
 temple, VIII, 85.
 Vāṭuvā or Batuwā, tombs VI, 12, 46 ; VII, 4, 60-63 ;
 VIII, 16, 40
 Vayad step-well - - - VIII, 13
 Vimala Śāh's temple at Abū - VI, 5 ; VII, 11, 14
 Virāḍhavalā, of the Vāghela clan - VI, 7, 30
 Viramgām and its remains - - VI, 6, 13 ;
 VIII, 82, 91-92
 Virasīnha, chief of Kālol - - VIII, 12
 Virata, where the Pāṇḍavas resided - VI, 30
 Virāval, seaport - - - VI, 15_n
 Visaladeva, Vāghela king, 1243-1261 - VI, 7
 Vishṇu, a god - - - VIII, 84
- Wahidshāh Pīr, or Pīr Vazīrshāh's masjid
 and rauza in Mirzapur - - VIII, 67
 Wajīhud-dīn, 'Alwī of Gujarāt, VIII, 48 ; his tomb,
 VIII, 53-54, 68.
 Wajīhud-dīn Maghribī, Shaikh Aḥmad
 Kāṭṭu - - - VII, 15
 Wajīhul-Mulk, father of Muzaḥḥar II - VI, 8, 10
 Wajīhul Mulk Gujarātī - - - VI, 14
- waqf*, a sacred endowment - VI, 28 ; VII, 21, 81 ;
 VIII, 16, 48, 67
 Wasna Faṭhpur, village revenues - VIII, 17
wāvs, step-wells : Bāī Harīr's at Asārwa, VIII, 1, 2,
 4-6, 10, 12 ; Mātā Bhavānī's at Asārwa, VIII,
 1-3 ; at Adālaī, VIII, 10-13 ; at Roho, VIII, 13 ;
 at Vayad, VIII, 13 ; at Pātān, VIII, 13 ; at
 Uvārsad, VIII, 13 ; at Chhatrāl, VIII, 13 ; near
 Īsaupur, VIII, 13 ; at Rakhyal, VII, 56.
waḥā, religious ablution - - VI, 26 ; VII, 24
 Williams, Col. Monier - - - VII, 32
 wood-carving at Kapaḍvanj - - VIII, 94
- Yādavas, the clan of Kṛishṇa - - VI, 2
 Yāhyā, a poet - - - VII, 38, 82
 Yakshas and Yakshīnis - - - VIII, 89
 Yama, a god, guardian of the South - VIII, 96
 Yāwar 'Alī Khān, brother of Momin
 Khān IV - - - VI, 25
 Yoginis - - - VIII, 85
 Yuvarāja or deputy ruler - - VI, 7
- Zafar Khān, afterwardz Muzaḥḥar I - VI, 8, 9, 10
 Zafar Khān Gustarī - - - VI, 29
 Zainul-Abidīn Najm Khān, son-in-law of
 Momin Khān I - - - VI, 24
 Zerbaksh or "Gold-bestower," title of
 Muḥammad Shāh I - - - VI, 11

Published by order of the Secretary of State for India.

ARCHÆOLOGICAL SURVEY OF WESTERN INDIA.

REPORTS.

By JAS. BURGESS, C.I.E., LL.D., F.R.S.E., M.R.I.B.A.

Super-royal 4to, half morocco, gilt tops.

VOL. I.—REPORT OF THE FIRST SEASON'S OPERATIONS IN THE BELGAUM AND KALADGI DISTRICTS.

With 56 Photographs and Lithographic Plates and 6 Wood-cuts. 2l. 2s.

VOL. II.—REPORT ON THE ANTIQUITIES OF KATHIAWAD AND KACHH.

With 74 Photographs and Lithographic Plates, 242 pages. 3l. 3s.

VOL. III.—REPORT ON THE ANTIQUITIES OF THE BIDAR AND AURANGABAD DISTRICTS.

With 66 Photographs and Lithographic Plates and 9 Wood-cuts. 2l. 2s.

VOL. IV.—THE BUDDHIST CAVES AND THEIR INSCRIPTIONS.

With 60 Plates and 23 Wood-cuts.

VOL. V.—THE CAVES OF ELURA AND THE OTHER BRAHMANICAL AND JAINA CAVES IN WESTERN INDIA.

With 51 Autotype and other Plates and 18 Wood-cuts. The two Volumes. Price 6l. 6s.

LONDON:—KEGAN PAUL, TRENCH, TRÜBNER, & Co.

VOL. VI.—THE MUHAMMADAN ARCHITECTURE OF GUJARAT:— BHARUCH, CAMBAY, DHOLKA, &c.

With 76 Collotype and Photo-Lithographed Plates. Price 20s. nett.

VOL. VII.—THE MUHAMMADAN ARCHITECTURE OF AHMADABAD: PART I.

With 112 Collotype and Photo-Lithographed Plates and 11 Wood-cuts. Price 31s. 6d.

VOL. VIII.—THE MUHAMMADAN ARCHITECTURE OF AHMADABAD: PART II. WITH MUSLIM AND HINDU REMAINS IN THE DISTRICT.

With 85 Collotype and Photo-Lithographed Plates and 10 Illustrations in the Text. Price 31s. 6d.

VOL. IX.—THE ARCHITECTURAL ANTIQUITIES OF NORTHERN GUJARAT, MORE ESPECIALLY OF THE DISTRICTS IN THE BARODA STATE.

By JAS. BURGESS, C.I.E., LL.D., F.R.S.E., and H. COUSENS, M.R.A.S.

With 112 Collotype and Photo-Lithographed Plates and 10 Illustrations in the Text. Price 31s. 6d.

LONDON:—B. QUARITCH; W. GRIGGS AND SONS; KEGAN PAUL, TRENCH, TRÜBNER, & Co., ETC.

CALCUTTA:—THACKER, SPINK, & Co. BOMBAY:—THACKER & Co.

THE CAVE TEMPLES OF INDIA.

By J. FERGUSSON, R.C.L., C.I.E., F.R.S., F.P.R.A.S., and JAS. BURGESS, LL.D., C.I.E., F.R.S.E.

Super-royal 8vo, half morocco, gilt top, pp. xx and 536, with Map, 99 Plates, and 76 Wood-cuts. 2l.

LONDON:—LEZAC & Co., 61, Russell St.

Super-royal quarto, half-bound, gilt top, 1887. 3 Guineas.

THE BUDDHIST STUPAS OF AMARAVATI AND JAGGAYYAPETA DESCRIBED AND ILLUSTRATED.

By J. BURGESS, C.I.E., LL.D., F.R.S.E.

With the Asoka Edicts at Dhauri and Jaugada, translated by PROFESSOR G. BOHLER, C.I.E., PH.D., LL.D., Vienna.

With 69 Plates of Sculptures and Inscriptions, mostly autotypes, and 32 Wood-cuts.

"Dr. Burgess has recently issued an admirable monograph on the Buddhist Stūpas at Amarāvati and Jaggayyapeta, supplementary to the late Mr. Fergusson's 'Tree and Serpent Worship,' and has thus, to some extent wiped away the reproach of the Southern Presidency."—*Quarterly Review*, July 1889.

LONDON:—KEGAN PAUL, TRENCH, TRÜBNER, & Co. CALCUTTA:—THACKER SPINK, & Co.
BOMBAY:—THACKER & Co.

EPIGRAPHIA INDICA

SUPPLEMENTARY TO

THE CORPUS INSCRIPTIONUM INDICARUM.

Edited by JAS. BURGESS, C.I.E., LL.D., F.R.S.E., ETC.

Vol. I, super-royal 4to, 482 pages, with 35 facsimile Plates, and Vol. II, 518 pages, with 51 Plates. 21s. 6d. each.

"A côté des diverses séries de 'Reports' dont la marche est forcément peu régulière, M. Burgess a créé un organe périodique, l'*Epigraphia Indica*, spécialement réservé aux inscriptions. L'épigraphie indienne aura ainsi son *Ephemeris* avant d'avoir son *Corpus*. Si M. Burgess arrive de cette manière à centraliser, ne fût-ce que dans une certaine mesure, les travaux épigraphiques actuellement éparpillés dans une infinité de recueils, dont plusieurs sont des publications locales absolument inaccessibles en Europe, il aura rendu une fois de plus un service inestimable aux études indiennes."—*Revue de l'Histoire des Religions*.

CALCUTTA:—SUPERINTENDENT OF GOVERNMENT PRINTING, INDIA; THACKER, SPINK, & Co.

LONDON:—BERNARD QUARITCH; KEGAN PAUL, TRENCH, TRÜBNER & Co.; A. CONSTABLE & Co.; LEZAC & Co.

MISCELLANEOUS PUBLICATIONS OF THE ARCHÆOLOGICAL SURVEY OF WESTERN INDIA.

- | | |
|---|--|
| <p><i>4to demy.</i></p> <p>No. 1. Memorandum on the Buddhist Caves of Junnar, by J. BURGESS, LL.D.; and Translations of three Inscriptions from Badami, Pattadakal, and Aihole, by J. F. FLEET, Ph. D. 1874.</p> <p>No. 2. Memorandum on the Antiquities at Dabhoi, Ahmedabad, Than, Janagadh, Girnar, and Dhank, with Appendix of Inscriptions, and 10 plates of facsimiles, by J. BURGESS, LL.D. 1875.</p> <p>No. 3. Memorandum on the Remains at Gumli, Gop, and in Kachh, etc., by the same. 1875.</p> <p>No. 4. Provisional Lists of Architectural and other Archæological Remains in Western India, by the same. 1875.</p> <p>No. 5. Translations of Inscriptions from Belgaum and Kaladgi Districts, by J. F. FLEET, Ph. D.; and of Inscriptions from Kathiawad and Kachh, by HARI VAMAN LIMAYA, B.A. 1876.</p> <p>No. 6. Notes on the Antiquities of the Talukas of Parner, Sangamner, Ankole, and Kopergaum, in Ahmadnagar, by W. F. SINCLAIR, Bc. C.S., with revised Lists of Remains in the Ahmadnagar, Nasik, Puna, Thana, and Kaladgi Zillas, by J. BURGESS, LL.D. 1877.</p> <p>No. 7. Architectural and Archæological Remains in Khandesh, by W. H. PROBERT, Bc. C.S., Collector. 1877.</p> | <p>No. 8. Reports regarding the Archæological Remains in Sindh, with plans of Tombs; by District Officers. 1879.</p> <p>No. 9. Notes on the Bauddha Rock-Temples of Ajanta, their Paintings and Sculptures; and on the Paintings of the Bagh Caves, Modern Bauddha Mythology, and the Sanskrit Inscription at Citra, with 31 plates, by J. BURGESS, LL.D. 1879. Rs. 5.</p> <p>No. 10. Inscriptions from the Cave-Temples of Western India, with Descriptive Notes, a S'ilâhâra grant Mârasînha, and three Sanskrit Inscriptions in possession of the American Oriental Society: with 52 plates, by J. BURGESS, LL.D., and BHAGWANLAL INDRAJI PANDIT, Ph.D. 1881. Rs. 6.</p> <p>No. 11. Lists of the Antiquarian Remains in the Bombay Presidency, Sindh, and Berar, with an Appendix of Inscriptions from Gujarat: pp. 340, by J. BURGESS, LL.D., C.I.E. 1885. Rs. 6.</p> <p>Report on the Architectural and Archæological Remains in the Province of Kachh, with Inscriptions and 10 Native Drawings, by DALPATRAM PRANJIVAN KHAKAR; with five papers by the late Sir ALEX. BURNES. Edited by J. BURGESS, LL.D. 8vo. pp. 120. (<i>Selections from the Records of Bombay Government, No. 152, 1879.</i>)</p> |
|---|--|

BOMBAY:—GOVERNMENT CENTRAL PRESS.

THE SHARQI ARCHITECTURE OF JAUNPUR; WITH NOTES ON ZAFARABAD, SAHET MAHET AND OTHER PLACES IN THE N.-W. PROVINCES AND OUDH.

By A. FÜHRER, PH.D., and EDMUND W. SMITH, ARCHITECT.

Edited by JAS. BURGESS, C.I.E., LL.D., *Director-General of the Archæological Survey of India.*

Illustrated by 74 Plates of the Sharqi Architecture of Jaunpur, etc. Super-royal 4to. Sewed. Price 21s. 6d.

"The Government may properly be urged and expected to continue this survey in the North-Western Provinces, and to utilise the Architectural members of the Survey, moreover, in advising and controlling a reasonable conservation of Historical Monuments in the Indian Empire."—*Journal R. Institute of British Architects*, 19th June 1890.

"The first volume of Dr. Burgess's new series is a scholarly and exhaustive monograph on a special and well-defined architectural period. It is published in the form of a handsome quarto . . . supplying a valuable and interesting record of the history and architecture of Jaunpur, a city which for nearly a century vied with imperial Delhi, both in power and splendour.

"Unlike the majority of the volumes in the former series, the Report is one of which the Government has no reason to be ashamed, and it may be safely recommended to anyone interested either specially in Jaunpur or generally in Indian architecture as an adequate and trustworthy source of information."—*The Pioneer*.

CALCUTTA:—GOVERNMENT OF INDIA PRINTING PRESS. LONDON:—BERNARD QUARITCH; LEZAC & Co.

*Large Folio 17 × 14 inches. With 22 Plates.
One Guinea.*

THE ANTIQUITIES OF DABHOI IN GUJARAT.

By J. BURGESS, LL.D., C.I.E., and H. COUSENS, M.R.A.S.

LONDON:—GEORGE WATERSTON AND SONS.
BOMBAY:—THACKER & Co.

CORPUS INSCRIPTIONUM INDICARUM. INSCRIPTIONS OF THE EARLY GUPTA KINGS AND THEIR SUCCESSORS.

By JOHN FAITHFULL FLEET, C.I.E., PH.D.

With 45 Plates, cloth, 33s. 6d.; without Plates, 20s.

CALCUTTA:—SUPERINTENDENT OF GOVERNMENT PRINTING
INDIA.

Folio, 100 Plates, £3.

PRESERVATION OF NATIONAL MONUMENTS IN INDIA :

PHOTOGRAPHS AND DRAWINGS OF HISTORICAL BUILDINGS.

Reproduced by W. GRIGGS from the collection in the late Office of Curator of Ancient Monuments in India.

Works by the same Author :—

THE TEMPLES OF ŚATRUŅJAYA, THE JAINA PLACE OF PILGRIMAGE

NEAR PĀLITANA IN KATHIAWAD.

Photographed by SYKES AND DWYER.

With historical and descriptive introduction.

Plan and 45 Photographs. *Atlas folio*. 1869.

PHOTOGRAPHS FROM SOMANATH, GIRNAR, JUNAGADH, AND OTHER PLACES IN KATHIAWAD.

With descriptive introduction and plans.

Plans and 41 Photographs. *Large oblong folio*. 1870.

THE ROCK TEMPLES OF ELEPHANTA OR GHARAPURI.

With Plans, &c., and 13 Photographs by D. H. SYKES. 1871.

Oblong folio, Rs. 50. *Royal 8vo*, without Photographs, Rs. 5.

BOMBAY :—D. H. SYKES & Co.; THACKER & Co.

PHOTOGRAPHS OF ARCHITECTURE AND SCENERY IN GUJARAT AND RAJPUTANA.

With historical and descriptive letterpress.

30 Large Photographs. *Atlas folio*, Rs. 100.

CALCUTTA, BOMBAY and SIMLA :

BOURNE AND SHEPHERD. 1874.

Large 8vo, cloth, 12s. 6d.

BUDDHIST ART IN INDIA.

Translated from the "Handbuch" of Prof. ALBERT GRÜNWEDEL by A. C. GIBSON.

Revised and enlarged with 154 illustrations, by
JAS. BURGESS, C.I.E., LL.D., F.R.S.E.

"The letterpress of the English work is about twice as long as that in the original German and the number of illustrations is 154. . . . The result is a volume quite indispensable to anyone, whether in Europe or in India, who is occupying himself with the real meaning and history of Indian Art; and it would scarcely be possible to estimate too highly the debt they owe to both author and editor."—*Journal R. Asiatic Soc.*, Jan. 1902.

LONDON :—BERNARD QUARITCH.

THE ROCK TEMPLES OF ELURA OR VERUL.

By JAS. BURGESS. 12mo. 1877.

TARIKH-I-SORATH :

A history of the provinces of Sorath and Hallar in Kathiawad,
by RANCHODJI AMARJI, Diwan of Janagadh.

Translated from the Persian, with Notes. Cr. 8vo. 1882.

BOMBAY :—EDUCATION SOCIETY'S PRESS; THACKER & Co.

LONDON :—TRÜBNER & Co.

THE ANCIENT MONUMENTS, TEMPLES, AND SCULPTURES OF INDIA.

Illustrated in a series of reproductions of photographs in
the India Office, Calcutta Museum, and other Collections.

With Descriptive Notes and References. 1897.

Part I.—The Earlier Monuments.

170 Plates in Portfolio.

Part II. in advanced preparation.

LONDON :—W. GRIGGS AND SONS, LTD.

THE GANDHARA SCULPTURES.

A selection of illustrations in twenty-five plates from
the British and Lahor Museums.

With Notes on the Age of the Sculptures and Descriptive
Remarks. Folio.

LONDON :—W. GRIGGS AND SONS. 1899.

Cr. 8vo, cloth, 3s. 6d.

ON THE INDIAN SECT OF THE JAINAS.

By the late J. G. BÜHLER, C.I.E., LL.D.

Translated from the German.

Edited with an outline of Jaina Mythology,

By J. BURGESS, LL.D., C.I.E.

LONDON :—LUZAC & Co. 1903.

CONSTABLE'S HAND-GAZETTEER OF INDIA.

Compiled under the direction of J. G. BARTHOLOMEW, F.R.G.S.
By J. BURGESS, LL.D., C.I.E., F.R.G.S.

WESTMINSTER :—ARCHIBALD CONSTABLE & Co. 1896.

THE INDIAN ANTIQUARY,

A Journal of Oriental Research in Archaeology, History, Literature, Languages,
Folklore, etc., etc.

(FIRST SERIES, 1872-1884.)

Edited by JAS. BURGESS, C.I.E., LL.D., F.R.S.E.

A complete Set—Vols. I to XIII, bound in cloth, with numerous facsimiles of inscriptions and other
illustrations; 4to demy. £21 cash nett, and carriage extra.

Volumes I, II, and III are not sold separately.

Volumes IV to XIII together, £12 nett, and carriage
extra.

Volumes V to XIII may be had separately, bound in cloth,
at 22s each, cash; or the nine volumes together
for £9 nett, and carriage extra.

Volumes XIV to XXX, not bound, Rs. 20 each, carriage paid

THE SUPERINTENDENT, EDUCATION SOCIETY'S PRESS, BOMBAY, LONDON :—LUZAC & Co.

LIST OF VOLUMES CONSTITUTING THE NEW IMPERIAL SERIES OF THE REPORTS OF THE
ARCHAEOLOGICAL SURVEY OF INDIA.

Prescribed Number in New Series.	Name of Book.	Author or Editor.	Year of Publication.
I	Report of the First Season's Operations in the Belgaum and Kaladgi Districts.	Burgess - - -	1874
II	Report on the Antiquities of Kāthiāwād and Kachh - - -	Ditto - - -	1876
III	Report on the Antiquities of the Bidar and Aurangābād Districts - -	Ditto - - -	1878
IV	The Buddhist Caves and their Inscriptions - - - -	Ditto - - -	1883
V	The Caves of Elura and the other Brahmanical and Jaina Caves in Western India.	Ditto - - -	1884
VI	The Buddhist Stūpas of Amrāvati and Jaggayyapeta - - -	Ditto - - -	1887
VII	Lists of Antiquarian Remains in the Presidency of Madras (Volume I) -	Sewell - - -	1882
VIII	Lists of Inscriptions and Sketch of Dynasties of Southern India (Volume II)	Ditto - - -	1884
IX	Southern Indian Inscriptions (Volume I) - - - -	Hultzsch - - -	1890
X	Ditto ditto (Volume II) - - - -	Ditto - - -	1891
XI	Report on the Sharqi Architecture of Jaunpur - - - -	{ Burgess, Führer, and Smith - - }	1889
XII	Monumental Antiquities and Inscriptions in the North-Western Provinces and Oudh.	Führer - - -	1891
XIII	Epigraphia Indica of the Archaeological Survey of India (Volume I) -	Burgess - - -	1891
XIV	Ditto ditto ditto (Volume II) -	Ditto - - -	1893
XV	South Indian Buddhist Antiquities - - - -	Rea - - -	1894
XVI	Revised List of Antiquities, Bombay - - - -	Burgess and Cousens	1897
XVII	List of Architectural and Archaeological Remains in Coorg - - -	Rea - - -	1894
XVIII	Report on the Moghal Architecture of Faṭhpur-Sikri (Parts I-IV) -	Smith - - -	1895-98
XIX	List of Monumental Antiquities and Inscriptions in the Central Provinces and Berar.	Cousens - - -	1897
XX	The Jaina Stupa and some other Antiquities of Mathura - - -	V. A. Smith - -	1901
XXI	Chālukyan Architecture including Examples from the Ballāri District in Madras.	Rea - - -	1896
XXII	Bower Manuscripts - - - -	Hearnle - - -	1894
XXIII	Muhammadian Architecture in Gujarat:—Bharoch, Cambay, Dholkā, Chāmpānir, and Mahmudābād.	Burgess - - -	1896
XXIV	The Muhammadian Architecture of Ahmadābād, Part I - - - -	Ditto - - -	1900
XXV	Monumental Remains of the Dutch East India Company in the Presidency of Madras.	Rea - - -	1897
XXVI	Report on Results of Explorations in the Nepal Tarai, Part I - -	Mukherji - - -	1901
XXIX	South Indian Inscriptions, Volume III, Part I - - - -	Hultzsch - - -	1899
XXX	Moghul Colour Decoration of Agra, Part I - - - -	Smith - - -	1901
XXXI	List of Antiquarian Remains in His Highness the Nizam's Territory -	Cousens - - -	1900
XXXII	Archæology of North Gujarāt, Baroda Territories - - - -	Burgess and Cousens	1902
XXXIII	Muhammadian Architecture of Ahmadābād, &c., Part II - - - -	Burgess - - -	1905



NSol-
3017170-
NC

Central Archaeological Library,
NEW DELHI. 21625

Call No. R 913.012/1DA/Bur.

Author—Burgess, Jas.

Title—Muhammadian architecture

"A book that is shut is but a block"

CENTRAL ARCHAEOLOGICAL LIBRARY
GOVT. OF INDIA
Department of Archaeology
NEW DELHI

Please help us to keep the book
clean and moving.
